

**SUPPLEMENTAL SITE INSPECTION REPORT**

**RICHARDSON FLAT TAILINGS**

**SUMMIT COUNTY, UTAH**

**TDD F08-8903-06 - PAN FUT0039HDA**

**EPA ID UTD980952840**

**FILE PLAN**

**1.06**

**EPA SITE ASSESSMENT PROJECT MANAGER: THOMAS BURNS**

**E & E PROJECT OFFICER: KEVIN MACKEY**

**PREPARED BY: KEVIN MACKEY AND SUSAN KENNEDY**

**REVIEWED BY:**

KAM FORD

**SUBMITTED TO: JANET LINER, FIT-RPO  
THOMAS BURNS, NPL COORDINATOR**

**DATE SUBMITTED: OCTOBER 13, 1989  
DATE RESUBMITTED: DECEMBER 20, 1989**

## TABLE OF CONTENTS

LIST OF FIGURES AND TABLES.....	i
1.0 INTRODUCTION.....	1
2.0 OBJECTIVES.....	1
3.0 BACKGROUND.....	2
3.1 Location and Site Description.....	2
3.2 Previous Work.....	3
3.3 Site Geology, Hydrogeology and Hydrology.....	3
3.3.1 Geology.....	3
3.3.2 Hydrogeology.....	4
3.3.3 Hydrology.....	4
4.0 SAMPLING ACTIVITIES.....	5
4.1 Sample Collection.....	5
4.1.1 Tailings Samples.....	6
4.1.2 Surface Water Samples.....	7
4.1.3 Sediment Sample Collection.....	9
4.1.4 Opportunity Samples.....	9
4.2 Sample Shipping.....	9
5.0 QUALITY CONTROL.....	10
5.1 Instrument Calibration.....	10
5.2 Sample Containers.....	10
5.3 Background Samples.....	11
5.4 Blank Samples.....	11
5.5 Duplicate Samples.....	11
5.6 Decontamination Procedures.....	11
5.7 Documentation.....	12
5.8 Quality Assurance Review.....	12
5.8.1 Sediment Samples.....	12
5.8.2 Water and Tailings Samples.....	13
6.0 RESULTS.....	13
6.1 Analytical Results.....	13
6.1.1 Tailings Samples.....	14
6.1.2 Surface Water Samples.....	15
6.1.3 Sediment Samples.....	16
6.2 Field Observations.....	18
6.2.1 Source Data.....	18
6.2.2 Pathway Data.....	19
6.2.3 Target Data.....	20
7.0 CONCLUSIONS.....	20
7.1 Surface Hydrology.....	21
7.2 Observed Release.....	21
7.3 Sources.....	22
7.4 Surface Water Diversion.....	23
7.5 Summary.....	23
8.0 REFERENCES.....	25

## APPENDICES

- APPENDIX A SAMPLE COLLECTION AND SHIPMENT INFORMATION
- APPENDIX B SAMPLING PHOTO LOG
- APPENDIX C QUALITY ASSURANCE REVIEW
- APPENDIX D RECORDS OF COMMUNICATIONS

## LIST OF FIGURES

- FIGURE 1 SITE LOCATION MAP
- FIGURE 2 DETAILED SITE LOCATION MAP
- FIGURE 3 SAMPLE LOCATION MAP
- FIGURE 4 CONCENTRATIONS OF ARSENIC AND LEAD IN TAILINGS SAMPLES
- FIGURE 5 CONCENTRATIONS OF ARSENIC AND LEAD IN UNFILTERED SURFACE WATER SAMPLES
- FIGURE 6 CONCENTRATIONS OF ARSENIC AND LEAD IN SEDIMENT SAMPLES
- FIGURE 7 SURFACE HYDROLOGY MAP

## LIST OF TABLES

- TABLE 1 SURFACE WATER FIELD DATA
- TABLE 2 SOIL AND SEDIMENT FIELD DATA
- TABLE 3 INORGANIC ANALYTICAL RESULTS FOR TAILINGS SAMPLES
- TABLE 4 INORGANIC ANALYTICAL RESULTS FOR SEDIMENT SAMPLES
- TABLE 5 INORGANIC ANALYTICAL RESULTS FOR SURFACE WATER SAMPLES

SUPPLEMENTAL SITE INSPECTION REPORT  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUTOC39HDA  
EPA ID UTD980952840

1.0 INTRODUCTION

This report was prepared to satisfy the requirements of Technical Directive Document (TDD) F08-8903-06, issued to Ecology and Environment, Inc.'s Field Investigation Team (FIT) by the Region VIII office of the U.S. Environmental Protection Agency (EPA). This report details sampling activities and provides a discussion of analytical results for samples collected during this supplemental site inspection (SI) at Richardson Flat Tailings in Summit County, Utah.

The FIT performed the field work from July 18 through July 20, 1989. FIT members conducting this investigation included Kevin Mackey, project officer; Steve Yarbrough, site safety officer and Dan Kenney, sampler. Site access was coordinated by Tom Burns of EPA and EPA Regional Counsel. Sampling procedures used during this investigation conform to requirements established in the Region VIII Standard Operating Procedures for Field Operations at Hazardous Waste Sites (SOP III-2 E & E 1989). The sampling effort was conducted under the approved Sampling Plan (TDD F08-8903-06).

2.0 OBJECTIVES

The supplemental site inspection of Richardson Flat Tailings was designed to support EPA efforts to respond to comments on the nomination of the site to the National Priorities List under the current Hazard Ranking System. Specific objectives of field activities were to:

- o Define the surface water drainage patterns throughout the site area;



- o Verify a release of inorganic contaminants into Silver Creek;
- o Identify source material contributing to metals contamination in Silver Creek;
- o Measure the distance from the site to the point at which water is diverted from Silver Creek by the G.M. Pace ditch.

All of the aforementioned objectives were addressed during the July 18 through July 20, 1989 sampling effort and during a site visit conducted by Kevin Mackey and Robert Henry of E & E FIT on March 9, 1989.

### 3.0 BACKGROUND

#### 3.1 LOCATION AND SITE DESCRIPTION

Richardson Flat Tailings lies within the northwest quarter of Section 1 and the northeast quarter of Section 2, Township 2 South, Range 4 East, Salt Lake Meridian, in Summit County, Utah. The tailings cover an area of approximately 160 acres on a topographic depression located one and one-half miles northeast of the town of Park City (Figures 1 and 2).

The mill tailings at Richardson Flat came from the Keetley Ontario Mine and other metal mining operations currently owned by United Park City Mines (UPCM). The most recent use of the area for tailings disposal was from 1975 to 1981. During that time UPCM had all its mining properties leased to either Park City Ventures or Noranda Mining, Inc. who constructed and operated milling facilities on UPCM properties. In May of 1974, the Utah Division of Health - Water Pollution Committee approved plans by Park City Ventures to construct an embankment, dikes and a diversion ditch to contain mill tailings deposited on Richardson Flat.

### 3.2 PREVIOUS WORK

The original FIT site inspection at Richardson Flat Tailings was conducted during the summer of 1985. One background monitoring well was installed by the FIT as part of the investigation. The background well and two existing UPCM wells located at the base of the dam were sampled. In addition, six surface water samples, one surface soil sample, two subsurface soil samples, four surface tailings samples and four subsurface tailings samples were collected during the 1985 sampling effort. Findings of the original site inspection are discussed in the Report of Sampling Activities (TDD R8-8505-27) and the Analytical Results Report (TDD R8-8508-07).

In July, 1986 the FIT conducted high-volume air sampling at the site. A report of air sampling activities (TDD R8-8605-12) and an analytical results report for air sampling (TDD R8-8608-05) provide details of field work and data results.

The FIT submitted a Hazard Ranking System (HRS) package for Richardson Flat Tailings on September 3, 1987. Based on documented observed releases of inorganic contaminants to surface water and air, the site received an overall migration score exceeding the 28.50 threshold value required for nomination to the National Priorities List (NPL). EPA proposed Richardson Flat Tailings to the NPL on June 14, 1988.

### 3.3 SITE GEOLOGY, HYDROGEOLOGY AND HYDROLOGY

#### 3.3.1 Geology

Richardson Flat Tailings lies within a broad, gently rolling flat north of Park City, identified as Parleys Park (Figure 1). Over half of the total area (approximately 35 square miles) of Parleys Park is underlain by unconsolidated deposits of a poorly sorted mixture of clay to cobble size material. The unconsolidated deposits, which are saturated to within a few feet of the ground surface, occur primarily

along Silver and East Canyon Creeks and in the flats northwest of Quarry Mountain. The rest of the park is underlain by consolidated rocks including volcanics of Tertiary origin and Knight Conglomerate (Baker 1970).

### 3.3.2 Hydrogeology

The water sources for wells in the Heber-Kamas-Park City area are primarily consolidated rocks in the mountains and unconsolidated alluvial fill in the valleys. Few wells exist within Parleys Park, so the unconfined aquifer characteristics in the area are not well understood. There appear to be no well-defined beds of material of very high or very low permeability and no indications of the existence of artesian conditions. The average saturated thickness of the unconfined aquifer is broadly estimated to be about 40 feet.

The general ground water flow direction corresponds with the regional surface water flow directions. Recharge to ground water in the unconsolidated deposits in Parleys Park comes from direct infiltration of precipitation, runoff from the mountains and secondarily from subsurface inflow through consolidated rocks (Baker 1970).

### 3.3.3 Hydrology

Parleys Park is drained by East Canyon Creek and Silver Creek, both tributaries to the Weber River. Silver Creek which flows in a northerly direction west of and near the northern extension of Richardson Flat Tailings, has been channelized for irrigation purposes both upstream of and downstream from the tailings. The nearest diversion from Silver Creek downstream of the tailings is the G.M. Pace Ditch used for flood irrigation of alfalfa fields and pasture. The confluence of Silver Creek and the G.M. Pace Ditch is 2340 feet from the north side of U.S. Route 40, as measured along the course of Silver Creek.

A diversion ditch was constructed as part of the effort by Park City Ventures to contain tailings material deposited on Richardson Flat.

Construction of the diversion ditch has altered the drainage pattern as depicted on the 1955 USGS topographic map (Figure 2). The diversion ditch originates east of the tailings and terminates in the marshy area near the embankment at the northwest portion of the tailings. Figures 3, 4, 5 and 6 depict the course of the diversion ditch as viewed on an oblique aerial photograph provided by EPA Environmental Monitoring Systems Laboratory (EMSL), dated June 1984.

Normal annual total precipitation for Richardson Flat is reported between 16 and 20 inches (Baker 1970). The one-year 24-hour rainfall for the area is 1.25 inches (U.S. Dept. of Commerce 1963).

#### 4.0 SAMPLING ACTIVITIES

##### 4.1 SAMPLE COLLECTION

FIT sampling activities at the Richardson Flat Tailings began on Tuesday, July 18, 1989 and continued through July 20, 1989. The sampling team consisted of Kevin Mackey, project officer, Steve Yarbrough, site safety officer and Dan Kenney, sampler.

FIT sampling activities were observed by UPCM personnel Kerry Gee and Ed Osika and consultant Bill Bullock of MSE, Inc. of Butte, Montana. The FIT provided split samples to UPCM personnel for each sample FIT collected. Each split was treated in an identical manner to those samples FIT submitted for CLP analysis.

Samples were collected in a manner which took into account drainage patterns throughout the Richardson Flat area. The FIT collected samples in order to assess possible migration of contaminants offsite into Silver Creek and determine the presence of contaminants in drainage areas. Additional samples were taken from two possible seep locations at the base of the tailings dam in order to assess the likelihood of contaminant migration via seeps and springs from the tailings pond area.

Three tailings samples were collected from the area south of the diversion ditch to characterize the surficial material as a potential source of contamination. According to Summit County ownership plat maps, the property on which these "unimpounded" tailings lie is owned by United Park City Mines.

Two tailings samples were collected from the "floodplain tailings" located on the opposite side of Silver Creek from the Richardson Flat impoundment. There is no containment feature associated with these areas and the tailings material could easily be washed into Silver Creek during storm events. According to plat maps obtained from the Summit County Assessor's office, these floodplain tailings are on land which is currently owned by the U.S. Department of Transportation.

The FIT collected samples from the diversion ditch associated with the tailings impoundment. These samples were taken in such a manner as to determine availability of contaminated material for transport offsite via the diversion ditch structure. In addition, these samples will help the FIT assess the integrity of runoff control structures onsite.

#### 4.1.1 Tailings Samples

The FIT collected a total of five tailings samples from various locations throughout the area, as illustrated in Figure 3. These samples included:

- RFT-TA-1     Eastern end of tailings between access road and diversion ditch.
- RFT-TA-2     Southern end of tailings between Union Pacific Railroad tracks and diversion ditch.
- RFT-TA-3     Southwestern edge of tailings between Union Pacific Railroad tracks and diversion ditch.

RFT-TA-4 Floodplain tailings located on the west side of Silver Creek.

RFT-TA-5 Downgradient-most sample along the floodplain tailings near Silver Creek.

All tailings samples were collected using a plastic scoop or a decontaminated stainless steel spoon. The FIT composited samples on a plastic sheet prior to placing them in the appropriate sample containers.

#### 4.1.2 Surface Water Samples

The FIT collected 12 surface water samples during the course of this investigation. Two sample aliquots were collected at each station. One sample (designated by the station location number followed by an "A" designator) was filtered with a 0.45 micron filter and a barrel filter prior to preservation with nitric acid to a pH <2. The second aliquot (designated by location number followed by a "B" qualifier) was preserved in the same manner without filtering. These samples were collected from Silver Creek west of the tailings pond, from the diversion ditch and from the marshy area located downgradient of the diversion ditch at the base of the tailings dam. The FIT collected one additional sample from the Pace Homer irrigation ditch which discharges into Silver Creek upgradient of the tailings impoundment. Sample locations are shown in Figure 3. Specifically, the samples included:

RFT-SW-1 Background sample collected from the Pace Homer Ditch.

RFT-SW-2 Sample collected from Silver Creek near the floodplain tailings.

RFT-SW-3 Additional sample collected from Silver Creek near floodplain tailings.

- RFT-SW-4 Upgradient sample in runoff diversion ditch.
- RFT-SW-5 Samples collected from the diversion ditch at possible point of tailings entry.
- RFT-SW-6 Sample collected from point of diversion ditch discharge into marshy area.
- RFT-SW-7 Sample collected from the marshy area upgradient of its confluence with Silver Creek.
- RFT-SW-8 Sample collected from the point where Silver Creek enters marshy area.
- RFT-SW-9 Sample collected at culvert area where Silver Creek and marshy area drain under U.S. Route 40.
- RFT-SW-10 Downgradient sample collected from Silver Creek 800 feet upstream of the G.M. Pace irrigation diversion point.
- RFT-SW-16 Background surface water sample collected from Silver Creek downstream from the confluence of Pace Homer Ditch and Silver Creek.
- RFT-SW-17 Background surface water sample collected from Silver Creek approximately 20 feet upstream of the confluence of the Pace Homer Ditch and Silver Creek.

Heavy construction activity upgradient of surface water sample locations RFT-SW-2 and RFT-SW-3 resulted in highly turbid water at the time of sampling. The turbidity in the surface water was caused by heavy machinery moving through Silver Creek and disturbing streambed material.

#### 4.1.3 Sediment Sample Collection

Initially, the FIT proposed screening sediment samples using FASP XRF analysis for metal contaminant detection. However, during the sampling period the FIT XRF experienced operating problems and was not available to perform the analysis. The FIT opted to send a single sediment sample from each sample location to the CLP laboratory for sieving and analysis.

The FIT collected sediment samples in conjunction with each surface water sample. Each sediment sample was collected immediately following surface water sample collection. Each sample was collected using a plastic scoop or a decontaminated stainless steel spoon. The FIT composited each sediment sample on a plastic sheet prior to placing the sample in the appropriate sample container.

#### 4.1.4 Opportunity Samples

After performing a site reconnaissance the FIT selected two locations for opportunity sample collection. Additional surface water samples (RFT-OPW-1A and RFT-OPW-1B) and a sediment sample (RFT-OSE-1) were collected at the base of the tailings dam from a ponded seep area topographically elevated above and disjunct from the marshy area. A second opportunity sediment sample (RFT-OSE-2) was collected from a small seep area located approximately 50 feet northeast of the ponded seep area, along the face of the tailings dam (Figure 3). Flow in this seep area was insufficient for surface water sample collection. Surface water sample RFT-OPW-1A was filtered prior to preservation with nitric acid to a pH <2.

#### 4.2 SAMPLE SHIPPING

Samples collected during this effort were shipped on July 20, 1989 to the following Contract Laboratory Program (CLP) laboratories for analysis. Samples of tailings and surface water were shipped as low hazard environmental samples to Keystone Environmental Resources in



Houston, Texas for total metals analysis under Regular Analytical Services case number 12334. However, due to contractual difficulties Keystone Environmental performed only mercury analysis on these samples. Under the direction of the Sample Management Office (SMO) these samples were shipped by Keystone Environmental to Silver Valley Laboratory in Kellogg, Idaho for the remainder of the analyses. Sediment samples were shipped to Silver Valley Laboratory in Kellogg, Idaho under Special Analytical Service case number 4725H. These samples were sieved in an 80 mesh sieve in order to remove large gravel and organic matter prior to analysis for total metals.

## 5.0 QUALITY CONTROL

The FIT closely adhered to quality control procedures during the sampling activity as described in the Sampling Plan and in SOP III-2, Chapter 6.

### 5.1 INSTRUMENT CALIBRATION

Instruments utilized on this SI were calibrated by FIT members in the field. An Orion pH meter and a specific conductivity meter were calibrated daily and used at each surface water sample collection point. In addition, pH paper was used to determine tailings and sediment pH at each sample location. Surface water field data are presented in Table 1. Sediment and tailings field data are presented in Table 2 of this report. Daily instrument calibrations can be found in the Richardson Flat logbook (TDD F08-8903-06).

### 5.2 SAMPLE CONTAINERS

All sample containers were obtained through the Sample Management Office (SMO) Bottle Repository. A rinsate blank was collected for each day of sampling and submitted to the Contract Laboratory Program (CLP) laboratory to assess quality control (quality assurance on equipment decontamination and field handling).

### 5.3 BACKGROUND SAMPLES

The FIT collected background samples for both the Silver Creek and diversion ditch drainages. Upgradient surface water and sediment samples RFT-SW-1A, RFT-SW-1B and RFT-SE-1 were collected from the Pace Homer Ditch (an irrigation ditch which discharges into Silver Creek upgradient of the floodplain tailings area). Additional surface water and sediment samples RFT-SW/SE-16 and RFT-SW/SE-17 were collected on Silver Creek upgradient of the floodplain tailings. Samples RFT-SW/SE-16 and RFT-SW/SE-17 were collected downgradient from and upgradient of the confluence of the irrigation ditch with Silver Creek, respectively.

An upgradient surface water and sediment sample (RFT-SW/SE-4) was collected from the eastern end of the runoff diversion ditch which conveys runoff from the surrounding hills near the tailings pond (Figure 3).

### 5.4 BLANK SAMPLES

The FIT prepared a total of three blanks for this sampling effort. RFT-SW-12A, RFT-SW-12B, RFT-SW-15A, RFT-SW-15B, RFT-SW-18A and RFT-SW-18B were field rinsate blanks (prepared to check decontamination of sampling equipment). Blank samples with an "A" designator were passed through the barrel filtering device.

### 5.5 DUPLICATE SAMPLES

Samples RFT-SW-11A and RFT-SW-11B were collected as a duplicate of RFT-SW-2A and RFT-SW-2B. These samples provide verification of laboratory accuracy.

### 5.6 DECONTAMINATION PROCEDURES

The FIT followed decontamination procedures as set forth in SOP III-2, Chapter 11 Equipment Decontamination Procedures. This procedure

involved the following steps: a tap water wash, soapy water wash, triple deionized water rinse and air drying.

## 5.7 DOCUMENTATION

Following sample collection, all samples were handled in strict accordance with chain of custody protocol prescribed by the NEIC Procedures Manual for the Evidence Audit of Enforcement Investigation by Contractor Evidence Audit Teams, April 1984 (EPA-330/9-81-003R).

Appendix A of this report includes the sample identification numbers, sample tag numbers, traffic report numbers and chain of custody numbers. Copies of traffic reports, chain of custody records and pertinent airbills are available in TDD file F08-8903-06. The Richardson Flat logbook has a complete record of all documentation information (TDD F08-8903-06).

## 5.8 QUALITY ASSURANCE REVIEW

The inorganic data packages were examined thoroughly by FIT chemists for compliance using EPA Functional Guidelines for Reviewing Inorganic Data and the approved Region VIII FIT CLP Quality Assurance Standard Operating Procedures (SOP). The quality assurance reports and data sheets are attached as Appendix C. The data packages were judged acceptable overall, with qualifications as follows.

### 5.8.1 Sediment Samples

Spike recoveries were low for antimony and thallium indicating positive results for these elements are biased low and are flagged "j", estimated. Selenium recoveries were unacceptably low and positive values are flagged "j" and undetected values are rejected, "r". Thallium and selenium data were also flagged "j" for below criteria correlation in method of standard additions. Cadmium data were flagged "j", estimated, due to percent difference in serial dilution results.

### 5.8.2 Water And Tailings Samples

Samples were transferred from one CLP laboratory to another by the Sample Management Office. Recoveries for thallium and selenium were low and were flagged "[ ]" as estimated or "u" as undetected in surface water samples. Thallium results for tailings samples were flagged "j" or "[ ]" indicating the value is estimated due to minor quality control discrepancies, or the compound was detected below the contract required detection limit (CRDL). Lead results were flagged "j" due to duplicate results. Arsenic data were flagged "j", estimated data, due to poor correlation coefficients for RFT-SW-5A, RFT-SW-5B and RFT-SW-10B. Arsenic and zinc solid sample results were flagged "j" due to high serial dilution results. Field duplicates showed good relative agreement. Field blanks were free of contamination above contract detection limits except that arsenic in RFT-SW-12B was detected at 12 µg/l.

All arsenic and lead data are included in the discussion of analytical results in Section 6.1 and in Figures 4, 5 and 6 of this report. Refer to Tables 3, 4 and 5 for appropriate qualifications of data. Other analytical results discussed in Section 6.1 include those data which are not qualified and those data qualified as estimated or at a concentration greater than five times the quantity found in the blank.

## 6.0 RESULTS

Results of the supplemental site inspection are focused entirely on addressing issues associated with contaminant migration via the surface water route. Discussions of sample analytical data and field observations follow.

### 6.1 ANALYTICAL RESULTS

Results of the inorganic analysis of samples collected at Richardson Flat Tailings and the surrounding area are shown in Tables 3, 4 and 5. The sampling locations and the concentrations of arsenic

and lead at each sample location are depicted in Figures 3 through 6. Each figure gives relative concentrations of contaminants for each medium sampled (i.e. Figure 4 contains lead and arsenic concentrations for tailings samples. Figure 5 contains lead and arsenic concentrations for surface water samples. Figure 6 contains lead and arsenic concentrations for sediment samples).

The following is a discussion of analytical results for each medium sampled.

#### 6.1.1 Tailings Samples

Three tailings samples collected from south and southeast of the diversion ditch showed fairly constant concentrations of lead and arsenic. In particular, arsenic concentrations in tailings samples were relatively constant at approximately 200 mg/kg while lead concentrations were slightly more variable (ranging from 2580 mg/kg to 4520 mg/kg). Notable concentrations of cadmium (ranging from 21.1 to 95.9 mg/kg), copper (ranging from 149 to 336 mg/kg), mercury (ranging from 0.88 to 1.3 mg/kg), silver (ranging from 12.6 to 22.1 mg/kg) and zinc (ranging from 3220 to 14,100 mg/kg) were detected in these tailings samples as well.

Samples collected from the floodplain tailings (RFT-TA-4 and RFT-TA-5) exhibited a higher degree of variability. Arsenic concentrations in sample RFT-TA-4 were 259 mg/kg while sample RFT-TA-5 had an arsenic concentration of 175 mg/kg. Lead concentrations were also highly variable with sample RFT-TA-5 containing 31,600 mg/kg of lead while RFT-TA-4 had a concentration of 9300 mg/kg. Concentrations of cadmium (117 and 250 mg/kg), mercury (8.2 and 7.6 mg/kg), silver (62.8 and 115 mg/kg) and zinc (16,200 and 33,800 mg/kg) were notably higher in the floodplain tailings than in tailings samples collected south of the diversion ditch.

### 6.1.2 Surface Water Samples

Surface water samples were collected to assess the relationship of the site to contaminant distribution in Silver Creek and in the diversion ditch. For each surface water sample location, both a filtered sample and an unfiltered sample were submitted for analysis. As anticipated, the unfiltered surface water samples showed higher levels of contamination indicating a majority of the contaminants exist as suspended solids. The filtered and the unfiltered surface water samples exhibit similar trends in relative contaminant magnitude and in specific contaminants detected (Table 5). The following discussion focuses on results of unfiltered surface water samples. Figure 5 illustrates relative lead and arsenic concentrations in unfiltered surface water samples.

Background concentrations of metals in Silver Creek and the Pace Homer Ditch upgradient of their confluence were relatively low. Specifically, RFT-SW-1B in the Pace Homer Ditch had 0.93 µg/l of lead and 7.7 µg/l of arsenic. Sample RFT-SW-17B, collected from Silver Creek upgradient of the Pace Homer confluence, contained 0.9 µg/l of lead and 2.3 µg/l of arsenic. Background surface water sample RFT-SW-16B, collected from Silver Creek downgradient from the Pace Homer confluence contained 25.2 µg/l of lead and 5.6 µg/l of arsenic.

Surface water samples collected from Silver Creek in the vicinity of the floodplain tailings contained very high concentrations of lead and arsenic. Analytical results of RFT-SW-2B indicated the presence of lead at 20,000 µg/l and arsenic at 619 µg/l. Sample RFT-SW-3B contained 1100 µg/l of lead and 41.9 µg/l of arsenic. Also notable in sample RFT-SW-2B were high levels of cadmium (137 µg/l), chromium (72.2 µg/l), copper (1390 µg/l), mercury (11.50 µg/l), silver (131 µg/l) and zinc (19,300 µg/l). Further downstream as Silver Creek meanders through the marshy area, data from sample RFT-SW-8B indicated reduced concentrations of lead (36.6 µg/l) and arsenic (8.4 µg/l). Sample RFT-SW-9B, collected from Silver Creek on the south side of the U.S. Route 40 culvert contained 122 µg/l of lead and 12.2 µg/l of arsenic. Concentrations of

lead (35.8 µg/l) in RFT-SW-10B drop as the course of Silver Creek moves further from the site.

The background diversion ditch sample (RFT-SW-4B), collected near the point of origin of that drainage was highly contaminated. Lead was detected at 22,100 µg/l and arsenic was detected at 2326 µg/l. High concentrations of cadmium (289 µg/l), chromium (50.2 µg/l), copper (1540 µg/l), mercury (8.0 µg/l), silver (201 µg/l) and zinc (49,100 µg/l) were also detected in RFT-SW-4B.

Sample RFT-SW-5B, collected from the diversion ditch midway through the tailings contained 24.9 µg/l of lead and 17.4 µg/l of arsenic. Surface water collected from the point at which the diversion ditch enters the marshy area (RFT-SW-6B) contained greatly reduced concentrations of lead (1.9 µg/l) and arsenic (3.9 µg/l). RFT-SW-7B, collected in the center of the marshy area, contained 131 µg/l of lead and 9.4 µg/l of arsenic.

Opportunity surface water sample RFT-OPW-1B, collected from a seep area at the base of the tailings embankment contained 68.2 µg/l of lead, 33.1 µg/l of arsenic and 759 µg/l of zinc. Mercury was not detected in this sample.

#### 6.1.3 Sediment Samples

Sediment samples were collected from all surface water sampling locations throughout the study area. Two additional sediment samples (RFT-OSE-1 and RFT-OSE-2) were collected from seep areas at the toe of the tailings embankment. Flow in the area of RFT-OSE-2 was minimal at the time of sampling, precluding collection of a corresponding surface water sample. Analytical results of sediment samples are presented in Table 4. Figure 6 illustrates relative lead and arsenic concentrations in sediment samples.

Analytical results of background sediments collected from the Pace Homer Ditch and Silver Creek indicated the presence of elevated

concentrations of arsenic and lead upgradient of the influence of the floodplain tailings and the impoundment. Sample RFT-SE-1, collected in the Pace Homer Ditch, contained 1790 mg/kg of lead and 83.2 mg/kg of arsenic. Sediment sample RFT-SE-17, collected from Silver Creek upgradient of the Pace Homer Ditch confluence, contained 12,200 mg/kg of lead and 555 mg/kg of arsenic. Also notable in RFT-SE-17 were relatively high concentrations of cadmium (113 mg/kg), silver (39.8 mg/kg) and zinc (17,500 mg/kg). Sample RFT-SE-16, collected downgradient from the Pace Homer Ditch confluence contained 4430 mg/kg of lead and 211 mg/kg of arsenic.

Sediment samples collected in close proximity to the floodplain tailings (RFT-SE-2 and RFT-SE-3) contained high levels of arsenic (590 and 427 mg/kg), cadmium (91.4 and 82.0 mg/kg), lead (14,200 and 9880 mg/kg) and mercury (4.9 and 6.0 mg/kg).

Sediment sample RFT-SE-8, collected from Silver Creek within the marshy area contained 348 mg/kg arsenic, 82.3 mg/kg cadmium and 3510 mg/kg lead. Analytical data for Silver Creek sediment sample RFT-SE-9, collected at the U.S. Route 40 culvert, indicated contaminants present in the following concentrations: 295 mg/kg arsenic, 90.2 mg/kg cadmium, 6970 mg/kg lead and 5.0 mg/kg mercury. Concentrations of all contaminants including arsenic (5.4 mg/kg) and lead (108 mg/kg) were significantly reduced in sediment sample RFT-SE-10, collected from Silver Creek a few hundred feet downstream from the U.S. Route 40 culvert.

The background diversion ditch sediment sample (RFT-SE-4) was significantly contaminated with arsenic (776 mg/kg), cadmium (100 mg/kg), lead (13,600 mg/kg) and mercury (5.5 mg/kg). Arsenic, lead and mercury data for sediments collected from the diversion ditch midway through the tailings (RFT-SE-5) and at the point of discharge to the marshy area (RFT-SE-6) indicate a reduction in concentrations of these elements as compared to sample RFT-SE-4. Cadmium concentrations were not reduced, however, as RFT-SE-5 contained 149 mg/kg and RFT-SE-6 contained 62.3 mg/kg. Sample RFT-SE-7, collected in the center of the



marshy area, contained 198 mg/kg arsenic, 102 mg/kg cadmium and 3250 mg/kg lead.

Opportunity sediment samples were collected from two separate seep areas discovered during site reconnaissance. Sample RFT-0SE-1, collected from a ponded area at the base of the embankment, exhibited significant concentrations of arsenic (751 mg/kg), cadmium (185 mg/kg), lead (12,500 mg/kg), silver (60.6 mg/kg) and zinc (24,000 mg/kg). Sample RFT-0SE-2, obtained from a seep area along the face of the embankment, contained 839 mg/kg of arsenic, 131 mg/kg cadmium, 6900 mg/kg of lead and 20,000 mg/kg of zinc.

## 6.2 FIELD OBSERVATIONS

Discussed below are field observations made by the FIT during the July 1989 sampling effort, during a previous site visit in March 1989 and during a personal interview with a local rancher conducted in December 1989.

### 6.2.1 Source Data

Tailings material present on the south side of the diversion ditch was virtually indistinguishable in appearance from tailings material within the "impoundment". Tailings on both sides of the ditch were noted as light gray in color as shown in Photo 1 (Appendix B).

Floodplain tailings exhibited a different appearance than the impoundment tailings and the tailings located south of the diversion ditch. The floodplain tailings were noted as more orange in color (Photos 5 and 6, Appendix B), indicative of iron oxidation. The pH measurements of floodplain tailings samples RFT-TA-4 and RFT-TA-5 indicated highly acidic surface conditions (pH 2).

### 6.2.2 Pathway Data

No effective barrier to erosional transport of tailings material into the diversion ditch was observed. The ditch appeared to have been constructed through deposited tailings.

Although the diversion ditch contained standing water along much of its course, it may be an overland conduit of contamination from the tailings into the Silver Creek drainage during events of high precipitation. The diversion ditch terminates in the marshy area as depicted in Figure 7.

Floodplain tailings were noted as highly susceptible to erosional transport into Silver Creek, with no visible containment structure present.

Due to heavy construction activities upstream, Silver Creek was notably turbid along its course where RFT-SW-2 and RFT-SW-3 were collected. Turbidity may have contributed to excessive contaminant concentrations detected in these surface water samples.

After a thorough reconnaissance, two seep areas were located along the tailings embankment. One seep was found in an isolated pond area at the base of the embankment. The second seep area was located approximately 50 feet north of the pond area along the face of the embankment. Opportunity sediment samples were collected from both seep locations and an opportunity surface water sample was collected from the ponded area.

The facility has an average slope of less than three percent. The intervening terrain between seep samples RFT-OPW-1/RFT-OSE-1 and the marshy area was observed to be between three to five percent. The intervening terrain between seep samples RFT-OSE-2 and the marshy area was observed to be between five to eight percent.

The likely course that runoff can be expected to follow from seep areas to the marshy area is depicted on Figure 7. The distance from the RFT-OPW-1/RFT-OSE-1 sample location (ponded seep area) to the marshy area was approximately 150 feet at the time of sampling. The distance from the RFT-OSE-2 sample location to the marshy area was approximately 200 feet at the time of sampling.

#### 6.2.3 Target Data

Probable points of entry of seep contaminants into a surface water body (i.e. the marshy area) are illustrated on Figure 7. The distance measured across the marshy area from the nearest probable point of entry to Silver Creek at the U.S. Route 40 culvert is approximately 325 feet.

The nearest point of diversion of surface water from Silver Creek downgradient of the site is the G.M. Pace Ditch, used to irrigate alfalfa fields and pasture. The point at which the G.M. Pace Ditch diverts water from Silver Creek was measured as 2340 feet from the U.S. Route 40 culvert along the course of Silver Creek.

Mr. Standley Pace, in an interview conducted by FIT member Kevin Mackey in December 1989, stated that he currently irrigates about 115 acres of cow pasture and alfalfa fields with water from the G.M. Pace Ditch. Mr. Pace's cousin irrigates an additional 115 acres for similar purposes using water diverted by the G.M. Pace Ditch. Another local rancher, Mr. James Gilmore, was identified by Mr. Pace as a user of the ditch.

Mr. Gilmore stated during a December 1989 telephone conversation that he currently irrigates between 95 and 110 acres of alfalfa fields and sheep pasture using water from the G.M. Pace Ditch. Records of communication with Mr. Pace and Mr. Gilmore are provided in Appendix D.

## 7.0 CONCLUSIONS

Objectives of the supplemental site inspection for Richardson Flat Tailings have been accomplished as a result of follow-up sampling and field activities.

### 7.1 SURFACE HYDROLOGY

Surface water drainage patterns throughout the site area have been defined. The diversion ditch, which originates on the hill near the southeastern extension of the impounded tailings, cuts through tailings material throughout most of its course and terminates in the marshy area at the base of the tailings embankment (Figure 3).

Silver Creek flows parallel to the Union Pacific Railroad tracks for most of its course between the east/west access road and U.S. Route 40. About 250 feet south of U.S. Route 40, Silver Creek flows beneath the Union Pacific Railroad trestle where it meanders through a portion of the marshy area near the base of the tailings embankment. Silver Creek flows beneath U.S. Route 40 via a culvert, then flows in a northwest direction into the Weber River drainage (Figures 1 and 3).

The likely courses of runoff from seep locations into the marshy area are depicted on Figure 7.

### 7.2 OBSERVED RELEASE

Analytical results of surface water and sediment samples collected from Silver Creek and the diversion ditch do not support an observed release of contaminants to surface water. The significant contribution of contaminants to Silver Creek by the floodplain tailings and historic deposition of metal-bearing material into the streambed cannot be clearly segregated from contamination contributed by the Richardson Flat tailings.

The upgradient diversion ditch surface water and sediment samples (RFT-SW-4 and RFT-SE-4) revealed higher contaminant levels than did diversion ditch samples midway through the tailings (RFT-SW-5 and RFT-SE-5) and at the point of outflow (RFT-SW-6 and RFT-SE-6). Lower contaminant concentrations in RFT-SW-5, RFT-SE-5, RFT-SW-6 and RFT-SE-6 may result from high percentages of organic matter at these sample locations. Inability to establish clear trends of contaminant distribution in both the diversion ditch and Silver Creek drainages is probably due in part to the non-homogenous nature of tailings material deposited.

### 7.3 SOURCES

Source material analyzed during the course of the original site inspection and the supplemental activities include tailings within the impoundment, tailings on the south side of the diversion ditch and tailings adjacent to Silver Creek (referred to in this report as floodplain tailings). All tailings samples collected contained high concentrations of inorganic contaminants. Elemental concentrations and near neutral pH measurements of tailings samples RFT-TA-1, RFT-TA-2 and RFT-TA-3 (south side of diversion ditch) correspond closely with data for tailings samples collected from the impounded area during the original site inspection (Ecology and Environment, Inc. 1985). High concentrations of arsenic, cadmium, copper, lead, mercury, silver and zinc are associated with tailings deposited on Richardson Flat regardless of proximity to the diversion ditch.

Presence of arsenic, cadmium, lead, silver and zinc contamination in seep water and sediment samples indicate a loss of integrity in the tailings impoundment control structure. It is possible that tailings were mixed with native soil during construction of the earthen embankment, contributing to contamination of seep samples.

Analytical results of floodplain tailings indicated notably higher concentrations of cadmium, lead, mercury and zinc as compared to tailings collected from the impoundment and from the south side of the

diversion ditch. Surface water and sediment samples collected from Silver Creek in the vicinity of the floodplain tailings contained high levels of corresponding contaminants.

Background surface water and sediment samples collected from Silver Creek and the Pace Homer Ditch indicated additional sources of inorganic contamination upgradient of sources discussed in this report.

#### 7.4 SURFACE WATER DIVERSION

The distance to the G.M. Pace Ditch from the U.S. Route 40 culvert was measured in the field and was reported as 2340 feet along the course of Silver Creek. The distance from contaminated seep sediment sample RFT-0SE-2 to the probable point of entry of contaminants into surface water is approximately 200 feet along the likely course of runoff. The distance across the marsh from the probable point of entry to Silver Creek at the U.S. Route 40 culvert is approximately 325 feet. The total distance from contamination to the nearest diversion of water from Silver Creek is therefore 2865 feet measured along the course of surface water flow.

The total number of acres irrigated by water diverted from Silver Creek via the G.M. Pace Ditch was documented as 330 (Standly Pace, 115 acres; Angus Pace 115 acres; James Gilmore, 100 acres).

#### 7.5 SUMMARY

In summary, no observed release of contaminants attributable to the site has been clearly documented. Inorganic contamination is prevalent throughout the study area and additional sources of contamination other than those discussed in this report may exist.

Contaminated water and sediment samples collected at seep locations on the tailings embankment, however, demonstrate the diking is leaking and unsound. Contamination attributable to Richardson Flat tailings poses a potential threat to surface water in Silver Creek.

Within three miles downstream of documented contamination attributable to Richardson Flat Tailings, water is diverted by the G.M. Pace Ditch for crops and pasture irrigation of approximately 330 acres of land.

## 8.0 REFERENCES

Baker, C. H., Jr., 1970, Water Resources of the Heber-Kamas-Park City Area North Central Utah, Utah Dept. of Nat. Res. Tech. Publ. No. 27.

Ecology and Environment, Inc., 9/30/85, Sampling Activities Report for Richardson Flat Tailings, TDD R8-8505-27.

Ecology and Environment, Inc., 10/25/85, Analytical Results Report for Richardson Flat Tailings, TDD R8-8508-07.

Ecology and Environment, Inc., 9/11/86, Air Sampling Activities Report for Richardson Flat Tailings, TDD R8-8605-12.

Ecology and Environment, Inc., 9/9/8, Air Analytical Results Report for Richardson Flat Tailings, TDD R8-8608-05.

Ecology and Environment, Inc., 4/89, Standard Operating Procedures for Field Operations at Hazardous Waste Sites - SOP III-2.

Ecology and Environment, Inc., 1989, Standard Operating Procedures for FASP XRF Method--Screening for Metals in Soil/Solid Samples - SOP VI-2.


U.S. Department of Commerce, 1963, Rainfall Frequency Atlas of the United States, Technical Paper No. 40.

USEPA Contract Laboratory Program, July, 1987, Statement of Work, No. 787 for Inorganics Analysis; Multimedia, Multiconcentration.

USEPA Hazardous Site Control Division, 1985, USEPA Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analysis. TDD HQ-8410-01.

U.S. Weather Bureau, 1963, Normal Annual and May-September Precipitation (1931-60) for the State of Utah: Map of Utah, Scale 1:50,000.





Source: Salt Lake City Topographic Map, Utah. USGS, 1980

0 1 2 3 4 MILES

FIELD INVESTIGATIONS OF UNCONTROLLED  
HAZARDOUS WASTE SITES  
TASK REPORT TO THE E.P.A.

TITLE:


RICHARDSON FLAT TAILINGS  
Park City, Utah  
SITE LOCATION MAP

T.D.D. F08-8903-06

ecology & environment, inc.  
DENVER, COLORADO

FIG. 1


Date: 12/89 Drawn by: RSM Scale:



Source: Park City Quadrangle, Utah. USGS, 1955

0 1/2 1 Mile

# LOCATION MAP



## FIELD INVESTIGATIONS OF UNCONTROLLED HAZARDOUS WASTE SITES TASK REPORT TO THE E.P.A.

### TITLE:


RICHARDSON FLAT TAILINGS  
Park City, Utah  
DETAILED SITE LOCATION MAP

T.D.D. F08-8903-06


ecology & environment, inc.  
DENVER, COLORADO

FIG. 2

Date: 06/89 Drawn by: RSM Scale:



FIELD INVESTIGATIONS OF UNCONTROLLED HAZARDOUS WASTE SITES TASK REPORT TO THE E.P.A.	
TITLE: RICHARDSON FLAT TAILINGS Park City, Utah SAMPLE LOCATION MAP T.D.D. F08-8903-06	
ecology & environment, inc. DENVER, COLORADO	FIG. 3
Date: 08/89 Drawn by: RSM Scale:	




FIELD INVESTIGATIONS OF UNCONTROLLED  
HAZARDOUS WASTE SITES  
TASK REPORT TO THE E.P.A.

TITLE:  
RICHARDSON FLAT TAILINGS  
Park City, Utah  
CONCENTRATIONS OF ARSENIC  
AND LEAD IN TAILINGS SAMPLES  
T.D.D. F08-8903-06

ecology & environment, inc.  
DENVER, COLORADO

Date: 08/89 Drawn by: RSM Scale:



[20000] Lead concentration (ug/l)  
(619) Arsenic concentration (ug/l)


FIELD INVESTIGATIONS OF UNCONTROLLED  
HAZARDOUS WASTE SITES  
TASK REPORT TO THE E.P.A.

TITLE:  
RICHARDSON FLAT TAILINGS  
Park City, Utah  
CONCENTRATIONS OF ARSENIC AND  
LEAD IN UNFILTERED WATER SAMPLES  
T.D.D. F08-8903-06

ecology & environment, inc.  
DENVER, COLORADO

FIG. 5

Date: 08/89 Drawn by: RSM Scale:



**LEGEND**

- Tailings sample
- Surface water sample
- ▲ Sediment sample
- (839) Sediment Arsenic concentrations mg/kg
- [14200] Sediment Lead concentrations mg/kg


FIELD INVESTIGATIONS OF UNCONTROLLED HAZARDOUS WASTE SITES  
TASK REPORT TO THE E.P.A.

**TITLE:**  
RICHARDSON FLAT TAILINGS  
Park City, Utah

CONCENTRATIONS OF ARSENIC AND LEAD IN SEDIMENT SAMPLES  
T.D.D. F08-8903-06





ecology & environment, inc.  
DENVER, COLORADO

Date: 08/89 Drawn by: RSM Scale: \_\_\_\_\_



200 0 200  
Scale in Feet

#### LEGEND

-  Opportunity water sample
-  Sediment sample
-  Likely course of runoff
-  Probable point of entry

Source: Dames & Moore Aerial Photograph  
Plot Plan, August 24, 1980.

#### FIELD INVESTIGATIONS OF UNCONTROLLED HAZARDOUS WASTE SITES TASK REPORT TO THE E.P.A.

##### TITLE:

RICHARDSON FLAT TAILINGS  
Park City, Utah  
SURFACE HYDROLOGY MAP

T.D.D. F08-8903-06

ecology & environment, inc.  
DENVER, COLORADO

FIG. 7

Date: 12/89 Drawn by: RSM Scale:

TABLE 1 SURFACE WATER FIELD DATA

SITE: Richardson Flat Tailings

SAMPLE ID.	SAMPLING		SHIPPING DATE	FIELD DATA			COMMENTS
	DATE	TIME		pH	COND. umho	TEMP. C	
RFT-SW-1A & B	07/19/89	1107	07/20/89	7.5	620	20	
RFT-SW-2A & B	07/19/89	1040	07/20/89	7.3	1300	19	These samples were collected in Silver Creek downstream of construction activities. These activities resulted in highly turbid water which, in turn, may increase metals concentrations in unfiltered surface water samples RFT-SW-2B and RFT-SW-3B.
RFT-SW-3A & B	07/19/89	1016	07/20/89	7.5	1350	18	
RFT-SW-4A & B	07/19/89	0911	07/20/89	7.05	1000	14	
RFT-SW-5A & B	07/19/89	0854	07/20/89	7.09	1300	14	
RFT-SW-6A & B	07/19/89	0824	07/20/89	6.8	1600	17	
RFT-SW-7A & B	07/18/89	1648	07/20/89	6.01	1500	20	
RFT-SW-8A & B	07/18/89	1633	07/20/89	6.61	1500	19	
RFT-SW-9A & B	07/18/89	1345	07/20/89	7.74	1200	24	
RFT-SW-10A & B	07/18/89	1511	07/20/89	8.08	1200	22	
RFT-OPW-1A & B	07/19/89	1345	07/20/89	7.51	1200	17	



**SITE:** Richardson Flat Tailings

[illegible]

TABLE 2

## SOIL AND SEDIMENT FIELD DATA

SITE Richardson Flat Tailings

SAMPLE ID	SAMPLING		SHIPPING DATE	COMMENTS
	DATE	TIME		
RFT-SE-1	07/19/89	1107	07/20/89	Dark brown material, some organic matter present
RFT-SE-2	07/19/89	1040	07/20/89	Light gray medium to fine grained sediment
RFT-SE-3	07/19/89	1016	07/20/89	Light gray medium to fine grained sediment
RFT-SE-4	07/19/89	0925	07/20/89	Dark brown to medium gray, fine grained sediment
RFT-SE-5	07/19/89	0900	07/20/89	Gray with rust color
RFT-SE-6	07/19/89	0835	07/20/89	Light gray, medium to coarse grained sediment
RFT-SE-7	07/18/89	1700	07/20/89	Dark brown sediment high in organic matter
RFT-SE-8	07/18/89	1640	07/20/89	Dark brown sediment high in organic matter
RFT-SE-9	07/18/89	1351	07/20/89	Medium gray fine grained sediment, some organic matter present
RFT-SE-10	07/18/89	1524	07/20/89	Dark brown silty clay (fine grained)
RFT-SE-16	07/20/89	1025	07/20/89	Medium gray, fine to coarse grained sediment
RFT-SE-17	07/20/89	1040	07/20/89	Medium gray, fine to coarse grained sediments
RFT-TA-1	07/18/89	1115	07/20/89	Tan or rust colored, fine sand or tailings; pH 6.5
RFT-TA-2	07/18/89	1125	07/20/89	Tan colored, fine sand or tailings; pH 6

**TABLE 2**

## SOIL AND SEDIMENT FIELD DATA

**SITE** Richardson Flat Tailings

[illegible]

TABLE 3  
INORGANIC ANALYTICAL RESULTS FOR  
TAILINGS SAMPLES (mg/kg)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-TA-1	RFT-TA-2	RFT-TA-3	RFT-TA-4	RFT-TA-5
TRAFFIC RPT #	MHL-955	MHL-956	MHP-500	MHP-501	MHP-502
SAMPLE LOCATION	EAST OF TAILINGS POND	MIDDLE OF TAILINGS POND	WEST OF TAILINGS POND	FLOOD PLAIN TAILINGS	FLOOD PLAIN TAILINGS
Aluminum	691	1040	1530	1030	240
Antimony	63.1	84.4	87.0	120	144
Arsenic	220j	208j	222j	259j	175j
Barium	153	86.9	[32.8]	117	[39.5]
Beryllium	0.22u	0.22u	0.22u	0.27u	0.23u
Cadmium	21.1	41.2	95.9	117	250
Calcium	37000	54500	68200	5400	32800
Chromium	[2.0]	6.0	8.8	0.69u	0.59u
Cobalt	[5.5]	[2.6]	[7.4]	[3.9]	[3.2]
Copper	149	205	336	281	265
Iron	44700	36500	53400	97400	87000
Lead	2580	3060	4520	9300	31600
Magnesium	11200	18500	23000	[1140]	[142]
Manganese	1440	1740	2320	212	252
Mercury *	0.99	1.3	0.88	8.20	7.60
Nickel	8.2	9.4	[7.1]	[5.1]	[6.2]
Potassium	[255]	[496]	[827]	[1140]	[680]
Selenium	23.6	12.7	19.2	45.7	38.4
Silver	12.6	18.5	22.1	62.8	115
Sodium	[22.4]	[34.8]	[42.6]	[603]	[117]
Thallium	6.6j	3.0j	[4.2]j	[9.7]j	[6.8]j
Vanadium	[1.3]	[3.8]	[3.7]	[2.6]	0.57u
Zinc	3220	5710	14100	16200	33800

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellog, Idaho.

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 4  
INORGANIC ANALYTICAL RESULTS FOR  
SEDIMENT SAMPLES (mg/kg)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SE-1	RFT-SE-2	RFT-SE-3	RFT-SE-4	RFT-SE-5
PACKING LIST #	4725H-01	4725H-02	4725H-03	4725H-04	4725H-05
SAMPLE LOCATION	BCKGRND PACE HOMER DITCH	SILVER CRK NEAR FLOOD PLAIN TLGS	SILVER CRK NEAR FLOOD PLAIN TLGS	UPGRDNT DIVERSION DITCH	DIVERSION DITCH
Aluminum	18400	8620	7650	25100	2810
Antimony	19.8j	201j	114j	200j	178j
Arsenic	83.2	590	427	776	320
Barium	270	147	130	1220	134
Beryllium	1.7	[.86]	[.81]	[1.9]	[.47]
Cadmium	14.6j	91.4j	82.0j	100j	149j
Calcium	15000	25600	2610	82100	89700
Chromium	21.9	.77u	[1.0]	33.2	10.9
Cobalt	[11.4]	43.5	38.5	[10.1]	[5.3]
Copper	239	753	459	840	613
Iron	30800	181000	148000	58600	44800
Lead	1790	14200	9880	13600	9550
Magnesium	6130	9430	8480	33800	19700
Manganese	1260	1730	1630	2770	3090
Mercury	1.0	4.9	6.0	5.5	1.5
Nickel	23.5	21.5	28.8	27.0	[2.9]
Potassium	3160	[1160]	[1150]	6270	[794]
Selenium	3.1j	46.2j	42.7j	15.4j	16.1jr
Silver	9.7	47.5	30.3	86.0	60.9
Sodium	[239]	[181]	[173]	[447]	[84.6]
Thallium	[.81]j	[3.6]j	4.1j	23.2j	12.7j
Vanadium	48.7	19.0	21.2	46.5	[8.6]
Zinc	2770	15500	15100	15700	26400

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

r - Quality control indicates that data is not usable (material may or may not be present). DO NOT USE THIS DATA!

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 4 CONT.  
INORGANIC ANALYTICAL RESULTS FOR  
SEDIMENT SAMPLES (mg/kg)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SE-6	RFT-SE-7	RFT-SE-8	RFT-SE-9	RFT-SE-10
PACKING LIST #	4725H-06	4725H-07	4725H-08	4725H-09	4725H-10
SAMPLE LOCATION	OUT FLOW POINT FOR DIVERSION DITCH	MARSHY AREA	SILVER CRK DRAINAGE IN MARSH AREA	SILVER CRK CULVERT NEAR ROUTE 40	DNGRDNT SILVER CRK 800' UPSTRM G.M. PACE DITCH
Aluminum	11100	9710	14000	10900	20200
Antimony	40.8	37.6j	80.5j	107j	10.1uj
Arsenic	261j	198	348	295	5.4
Barium	944	384	286	229	408
Beryllium	[.85]	[1.1]	[1.5]	[1.4]	1.6
Cadmium	62.3j	102j	82.3j	90.2j	2.2j
Calcium	46900	90700	85800	38700	9640
Chromium	.71u	9.9	16.5	16.3	18.5
Cobalt	64.4	20.4	33.3	20.1	[10.9]
Copper	256	264	567	498	40.7
Iron	41400	64900	49200	68700	25500
Lead	3790	3250	3510	6970	108
Magnesium	13300	20700	18400	11100	6360
Manganese	207000	19100	14300	3070	303
Mercury	0.24	0.82	1.1	5.0	[.10]
Nickel	69.7	14.0	25.8	16.3	17.0
Potassium	1870	1880	2400	1590	6050
Selenium	5.6j	9.2j	13.2j	21.9j	5.6ur
Silver	13.7	23.9	36.9	36.2	.41u
Sodium	[344]	[254]	[276]	[220]	[389]
Thallium	8.5j	10.1j	14.2j	4.1j	.23uj
Vanadium	34.8	20.5	26.9	31.2	37.7
Zinc	18800	17600	18300	15900	302

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

r - Quality control indicates that data is not usable (material may or may not be present). DO NOT USE THIS DATA!

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 4 CONT.  
ANALYTICAL RESULTS FOR  
INORGANIC SEDIMENT SAMPLES (mg/kg)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-OSE-1	RFT-OSE-2	RFT-SE-16	RFT-SE-17
PACKING LIST #	4725H-11	4725H-12	4725H-13	4725H-14
SAMPLE LOCATION	OPPORTUNITY POND SEDIMENT SAMPLE	OPPORTUNITY SEEP SEDIMENT SAMPLE	DNSTRM OF PACE HOMER DITCH CONFLUENCE W/SILVER CRK	UPGRDNT CONFLUENCE SILVER CRK & PACE HOMER DITCH
Aluminum	19500	6880	15200	4440
Antimony	142j	49.3j	53.9j	183j
Arsenic	751	839	211	555
Barium	668	557	209	66.0
Beryllium	[2.3]	[1.6]	[1.4]	[.63]
Cadmium	185j	131j	43.9j	113j
Calcium	249000	167000	14500	18900
Chromium	18.2	1.0u	11.8	.72u
Cobalt	[5.9]	53.3	24.6	76.8
Copper	870	456	231	496
Iron	156000	132000	86100	263000
Lead	12500	6900	4430	12200
Magnesium	29700	23400	6340	5880
Manganese	19600	23700	1560	1370
Mercury	1.9	.73	3.3	.81
Nickel	32.1	26.3	22.4	31.4
Potassium	4790	1690	2490	[657]
Selenium	19.9j	2.5j	25.1j	84.0j
Silver	60.6	22.5	15.5	39.8
Sodium	[764]	[206]	[215]	[105]
Thallium	24.1j	21.0j	1.2bj	6.0j
Vanadium	38.0	[18.6]	40.5	[10.4]
Zinc	24000	20000	8580	17500

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 5  
ANALYTICAL RESULTS FOR  
INORGANIC SURFACE WATER SAMPLES (µg/l)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SW-1A	RFT-SW-1B	RFT-SW-2A	RFT-SW-2B	RFT-SW-3A
TRAFFIC RPT #	MHP-525	MHP-526	MHP-523	MHP-524	MHP-521
SAMPLE LOCATION	BCKGRND PACE HOMER DITCH	BCKGRND PACE HOMER DITCH	SILVER CRK NEAR FLOOD PLAIN TLGS	SILVER CRK NEAR FLOOD PLAIN TLGS	SILVER CRK NEAR FLOOD PLAIN TLGS
Aluminum	[27.9]ub	[26.3]ub	[18.2]ub	44500b	[16.5]ub
Antimony	19.9u	19.9u	[25.7]ub	210b	19.9u
Arsenic	[7.2]	[7.7]	[6.6]	619	[3.8]
Barium	[61.9]ub	[61.9]ub	[61.5]ub	881b	[52.9]ub
Beryllium	1.1u	1.1u	1.1u	[2.4]	1.1u
Cadmium	1.8u	1.8u	[5.0]ub	137b	9.2b
Calcium	132000b	131000b	211000b	248000b	199000b
Chromium	2.8u	2.8u	2.8u	72.2	2.8u
Cobalt	[3.1]ub	2.6u	[3.5]ub	[27.0]ub	[2.6]ub
Copper	1.1u	[2.4]ub	[1.2]ub	1390b	[1.5]ub
Iron	[56.4]ub	[84.7]ub	[63.2]ub	98500b	[39.9]ub
Lead	9.2bj	[0.93]ub	48.3bj	20000bj	38.2bj
Magnesium	34700b	34400b	41400b	68400b	39600b
Manganese	20.3b	19.1b	1170b	3080b	1080b
Mercury *	0.20u	0.20u	0.20u	11.50	0.20u
Nickel	9.7u	9.7u	[13.9]	67.3	9.7u
Potassium	[1820]ub	[2110]ub	[3180]	8980b	[3470]ub
Selenium	[15.4]ub	[15.2]ub	[2.6]ub	[34.2]ub	[14.7]ub
Silver	1.6u	1.6u	1.6u	131b	1.6u
Sodium	19700	19700	42300b	42900b	41000b
Thallium	0.90u	0.90u	0.90u	[4.7]	0.90u
Vanadium	2.7u	2.7u	2.7u	129	2.7u
Zinc	64.1b	52.7b	1730b	19300b	2360b

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellog, Idaho.

b - Material was detected in the laboratory blanks. Quantity reported is >5X the amount found in the blank. A false positive result may exist.

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).



TABLE 5 CONT.  
INORGANIC ANALYTICAL RESULTS FOR  
SURFACE WATER SAMPLES (µg/l)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SW-3B	RFT-SW-4A	RFT-SW-4B	RFT-SW-5A	RFT-SW-5B
TRAFFIC RPT #	MHP-522	MHP-515	MHP-516	MHP-517	MHP-518
SAMPLE LOCATION	SILVER CRK NEAR FLOOD PLAIN TLGS	UPGRDNT DIVERSION DITCH	UPGRDNT DIVERSION DITCH	DIVERSION DITCH	DIVERSION DITCH
Aluminum	1740b	[32.8]	30900	[32.6]	[33.7]
Antimony	[53.8]ub	[39.3]	937	19.9u	19.9u
Arsenic	41.9	68.6	2326	10.7j	17.4j
Barium	[82.2]ub	[102]	2330	[37.0]	[35.9]
Beryllium	1.1u	1.1u	[1.7]	1.1u	1.1u
Cadmium	[16.0]	[4.6]	289	[3.3]	6.2
Calcium	206000b	180000	446000	308000	314000
Chromium	2.8u	2.8u	50.2	2.8u	2.8u
Cobalt	[5.7]	[8.8]	[48.7]	2.6u	2.6u
Copper	71.4b	[13.6]	1540	[12.4]	[5.6]
Iron	5320b	267	107000	416	696
Lead	1100bj	41.8	22100j	12.9	24.9
Magnesium	42000b	38000	104000	61600	62700
Manganese	1220b	2780	21100	1310	1340
Mercury *	0.2u	0.2u	8.0	0.2u	0.2u
Nickel	9.7u	9.7u	65.5	[25.8]	9.7u
Potassium	[3160]ub	5580	15600	273u	273u
Selenium	[28.5]ub	14.0ur	1.2ur	14.0ur	14.0ur
Silver	[6.3]ub	1.6u	201	1.6u	1.6u
Sodium	42000b	54600	58500	28800	29300
Thallium	0.90u	14.1	83.4j	1.0u	1.0u
Vanadium	[5.5]	2.7u	58.7	2.7u	2.7u
Zinc	3790b	2650	49100	2990	3060

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellogg, Idaho.

b - Material was detected in the laboratory blanks. Quantity reported is >5X the amount found in the blank. A false positive result may exist.

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

r - Quality control indicates that data is not usable (material may or may not be present). **DO NOT USE THIS DATA!**

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 5 CONT.  
INORGANIC ANALYTICAL RESULTS FOR  
SURFACE WATER SAMPLES (µg/l)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SW-6A	RFT-SW-6B	RFT-SW-7A	RFT-SW-7B	RFT-SW-8A
TRAFFIC RPT #	MHP-519	MHP-520	MHP-509	MHP-510	MHP-511
SAMPLE LOCATION	DIVERSION DITCH OUTFLOW	DIVERSION DITCH OUTFLOW	MARSHY AREA	MARSHY AREA	SILVER CRK IN MARSHY AREA
Aluminum	[17.6]	[34.7]ub	11.5u	368	[16.8]
Antimony	19.9u	19.9u	19.9u	19.9u	19.9u
Arsenic	2.3u	[3.9]	2.3u	[9.4]	[5.3]
Barium	[14.9]	[14.9]ub	[14.9]ub	[37.0]	[32.1]
Beryllium	1.1u	1.1u	1.1u	1.1u	1.1u
Cadmium	1.8u	1.8u	1.8u	[2.6]	1.8u
Calcium	316000	330000b	322000	333000	320000
Chromium	2.8u	2.8u	2.8u	2.8u	2.8u
Cobalt	2.6u	[3.8]ub	2.6u	[3.8]	2.6u
Copper	[10.4]	[1.2]ub	[1.9]	[12.9]	1.1u
Iron	426	123	270	1070	224
Lead	1.8u	[1.9]ubj	0.90u	131	0.90u
Magnesium	68200	71200b	68700	70500	68600
Manganese	3180	3170b	94.8	2110	960
Mercury *	0.2u	0.2u	0.2u	0.2u	0.2u
Nickel	[13.2]	9.7u	9.7u	9.7u	9.7u
Potassium	[2010]	[2230]	[1480]	[1710]	[1330]
Selenium	14.0ur	12.0u	14.0ur	1.4ur	14.0ur
Sodium	45000	49600b	47500	48400	46700
Silver	1.6u	1.6u	1.6u	[2.4]	1.6u
Thallium	1.0u	0.9u	1.0u	1.0u	1.0u
Vanadium	2.7u	2.7u	2.7u	2.7u	2.7u
Zinc	219	198b	190	656	295

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellogg, Idaho.

b - Material was detected in the laboratory blanks. Quantity reported is >5X the amount found in the blank. A false positive result may exist.

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

r - Quality control indicates that data is not usable (material may or may not be present). **DO NOT USE THIS DATA!**

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 5 CONT.  
INORGANIC ANALYTICAL RESULTS FOR  
SURFACE WATER SAMPLES (µg/l)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SW-8B	RFT-SW-9A	RFT-SW-9B	RFT-SW-10A	RFT-SW-10B
TRAFFIC RPT #	MHP-512	MHP-506	MHP-507	MHP-503	MHP-504
SAMPLE LOCATION	SILVER CRK	SILVER CRK	SILVER CRK	DNGRDNT	DNGRDNT
CRK	IN MARSHY	CULVERT	CULVERT	SILVER	SILVER
	AREA	NEAR	NEAR	CREEK	CREEK
		ROUTE 40	ROUTE 40		
Aluminum	[106]	[24.6]	370	[26.6]	[75.8]
Antimony	19.9u	19.9u	19.9u	19.9u	19.9u
Arsenic	[8.4]	[6.8]	12.2	[3.3]	[5.6]r
Barium	[33.5]	[54.6]	[59.1]	[51.5]	[52.5]
Beryllium	1.1u	1.1u	1.1u	1.1u	1.1u
Cadmium	1.8u	1.8u	1.8u	[2.0]	[2.2]
Calcium	303000	139000	144000	147000	147000
Chromium	2.8u	2.8u	[2.8]	2.8u	2.8u
Cobalt	2.6u	[2.6]	2.6u	2.6u	[4.0]
Copper	[4.9]	[2.9]	[11.7]	[6.3]	[5.6]
Iron	1090	338	1200	195	481
Lead	36.6	6.2	122	[5.9]	35.8
Magnesium	64900	34600	35600	36400	36200
Manganese	950	274	335	223	240
Mercury *	0.2u	0.2u	0.2u	0.2u	0.2u
Nickel	9.7u	9.7u	9.7u	9.7u	9.7u
Potassium	[986]	[1790]	[1980]	2090	[1920]
Selenium	14.0ur	14.0ur	1.4ur	1.4ur	14.0ur
Silver	1.6u	1.6u	1.6u	1.6u	1.6u
Sodium	44300	22900	23400	25200	24100
Thallium	1.0u	1.0u	1.0u	1.0u	1.0u
Vanadium	2.7u	2.7u	2.7u	2.7u	2.7u
Zinc	332	429	726	419	519

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellogg, Idaho.

r - Quality control indicates that data is not usable (material may or may not be present). **DO NOT USE THIS DATA!**

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[ ] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 5 CONT.  
INORGANIC ANALYTICAL RESULTS FOR  
SURFACE WATER SAMPLES (µg/l)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SW-11A	RFT-SW-11B	RFT-SW-12A	RFT-SW-12B	RFT-SW-15A	RFT-SW-15B	RFT-SW-16A
TRAFFIC RPT #	MHP-528	MHP-527	MHP-513	MHP-514	MHP-529	MHP-530	MHP-534
LOCATION	DUPLICATE OF 2A	DUPLICATE OF 2B	FILTERED BLANK	UNFILTERED BLANK	FILTERED BLANK	UNFILTERED BLANK	DNSTRM OF PACE HOMER CONFLUENCE SILVER CRK
Aluminum	[28.0]ub	43400b	[23.3]	[16.6]	[24.9]ub	[32.1]ub	[44.6]ub
Antimony	[26.9]ub	199b	19.9u	19.9u	19.9u	19.9u	[20.1]ub
Arsenic	[5.6]	540	2.3u	12.0	2.3u	2.3u	2.3u
Barium	[60.8]	788b	1.3u	1.3u	1.3u	1.3u	[56.7]ub
Beryllium	1.1u	[2.1]	1.1u	1.1u	1.1u	1.1u	1.1u
Cadmium	6.0b	127b	1.8u	1.8u	1.8u	1.8u	10.3b
Calcium	211000b	246000b	[154]	[56.3]	[214]ub	[136]ub	205000b
Chromium	2.8u	68.5	[3.5]	2.8u	2.8u	2.8u	2.8u
Cobalt	[5.3]	[28.4]ub	2.6u	2.6u	2.6u	2.6u	[3.1]ub
Copper	[1.2]	1260b	1.1u	[4.4]	1.1u	1.1u	[2.7]ub
Iron	[55.1]	89300b	277	219	[64.2]ub	[41.5]ub	[31.5]ub
Lead	34.6bj	17900bj	0.90u	0.90u	[1.8]ubj	[1.6]ubj	[1.4]ubj
Magnesium	41400b	67100b	[42.5]	20.9u	[43.7]ub	[29.0]ub	40400b
Manganese	1180b	2950b	[2.3]	[2.0]	[1.4]ub	[2.5]ub	1070b
Mercury *	0.20u	8.50	0.2u	0.2u	.20u	.20u	.20u
Nickel	9.7u	57.3	9.7u	9.7u	9.7u	9.7u	9.7u
Potassium	[3060]ub	8770b	273u	273u	273u	273u	[3180]ub
Selenium	[15.1]ub	[43.9]ub	1.4ur	1.4ur	1.2u	1.2u	[2.7]ub
Silver	1.6u	117	1.6u	1.6u	1.6u	23.8b	1.6u
Sodium	41200	42700	[68.9]	[76.0]	[47.5]ub	13.2u	41900b
Thallium	0.90u	[4.2]	1.0u	1.0u	.90u	.90u	.90u
Vanadium	[3.8]	121	2.7u	2.7u	2.7u	2.7u	2.7u
Zinc	1730b	17700b	[4.5]	1.3u	[12.6]ub	[6.5]ub	2970b

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellog, Idaho.

b - Material was detected in the laboratory blanks. Quantity reported is >5X the amount found in the blank. A false positive result may exist.

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

r - Quality control indicates that data is not usable (material may or may not be present). **DO NOT USE THIS DATA!**

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 5 CONT.  
INORGANIC ANALYTICAL RESULTS FOR  
SURFACE WATER SAMPLES (µg/l)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE #	RFT-SW-16B	RFT-SW-17A	RFT-SW-17B	RFT-SW-18A	RFT-SW-18B
TRAFFIC RPT #	MHP-535	MHP-537	MHP-538	MHP-539	MHP-540
SAMPLE LOCATION	DNSTRM OF PACE HOMER DITCH CONFLUENCE W/SILVER CRK	UPGRDNT CONFLUENCE SILVER CRK PACE HOMER DITCH	UPGRDNT CONFLUENCE SILVER CRK PACE HOMER DITCH	BLANK	BLANK
Aluminum	[61.1]ub	[49.5]ub	[29.6]ub	[29.0]ub	[27.0]ub
Antimony	19.9u	19.9u	[20.1]ub	19.9u	19.9u
Arsenic	[5.6]	2.3u	2.3u	2.3u	2.3u
Barium	[56.0]ub	[54.3]ub	[51.1]ub	[1.7]ub	1.3u
Beryllium	1.1u	1.1u	1.1u	1.1u	1.1u
Cadmium	10.3b	13.3b	13.5b	1.8u	1.8u
Calcium	205000b	228000b	218000b	[109]ub	[90.8]ub
Chromium	2.8u	2.8u	2.8u	2.8u	2.8u
Cobalt	[3.5]ub	[6.6]ub	[5.3]ub	2.6u	[2.7]ub
Copper	[4.9]ub	[3.9]ub	[1.5]ub	1.1u	1.1u
Iron	496b	346bj	[43.7]ub	[33.4]ub	[32.2]ub
Lead	25.2bj	8.8b	0.90uj	[1.3]ub	0.90uj
Magnesium	40300b	41800b	39900b	[38.6]ub	[27.8]ub
Manganese	1080b	1380b	1330b	[2.0]ub	[1.4]ub
Mercury *	0.20u	0.20u	0.20u	0.20u	0.20u
Nickel	[10.6]	9.7u	9.7u	9.7u	9.7u
Potassium	[3380]ub	[3630]ub	[3570]ub	273u	[437]ub
Selenium	1.2u	[20.0]ub	[18.0]ub	1.2u	1.2u
Silver	1.6u	1.6u	1.6u	1.6u	1.6u
Sodium	41900	48000b	46400b	[41.8]ub	[13.3]ub
Thallium	0.90u	0.90u	0.90u	0.90u	0.90u
Vanadium	2.7u	2.7u	2.7u	2.7u	2.7u
Zinc	3130b	3880b	3720b	[2.9]ub	1.3u

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellogg, Idaho.

b - Material was detected in the laboratory blanks. Quantity reported is >5X the amount found in the blank. A false positive result may exist.

j - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL) or because minor quality control criteria were not met. Presence of the material is reliable.

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

TABLE 5 CONT.  
INORGANIC ANALYTICAL RESULTS FOR  
SURFACE WATER SAMPLES (µg/l)  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE # TRAFFIC RPT # SAMPLE LOCATION	RFT-OPW-1A MHP-532 PONDED AREA AT BASE OF TLGS DAM	RFT-OPW-1B MHP-533 PONDED AREA AT BASE OF TLGS DAM
Aluminum	[23.0]ub	317b
Antimony	19.9u	19.9u
Arsenic	[2.9]	33.1
Barium	[37.3]ub	[82.2]ub
Beryllium	1.1u	1.1u
Cadmium	1.8u	[3.6]ub
Calcium	312000	369000b
Chromium	2.8u	2.8u
Cobalt	[6.3]ub	[5.6]ub
Copper	[1.2]ub	[6.6]ub
Iron	503b	10200b
Lead	0.90u	68.2bj
Magnesium	56100b	58800b
Manganese	12900b	21400b
Mercury *	0.20u	0.20u
Nickel	9.7u	9.7u
Potassium	5380	9960
Selenium	12.0u	[18.5]ub
Silver	1.6u	1.6u
Sodium	60000b	63400b
Thallium	0.90u	0.90u
Vanadium	2.7u	2.7u
Zinc	[19.8]ub	759b

\* - Results have been provided by Keystone Laboratory of Houston, Texas. The remaining results are from analyses conducted by Silver Valley Laboratories of Kellog, Idaho.

b - Material was detected in the laboratory blanks. Quantity reported is >5X the amount found in the blank. A false positive result may exist.

u - The material was analyzed for, but was not detected. The associated numerical value is the estimated sample quantitation limit or CRDL.

[] - The associated numerical value is an estimated quantity because the amount detected is below the contract required detection limit (CRDL). Presence of the material is reliable. (Inorganic data only).

APPENDIX A

SAMPLE COLLECTION AND SHIPMENT INFORMATION

APPENDIX A  
SAMPLE COLLECTION AND SHIPMENT INFORMATION  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE ID	PARAMETERS	TRAFFIC RPT #	SAMPLE TAG #	CHAIN OF CUSTODY
RFT-SW-1A	METALS	MHP-525	8-94551	8-11438
RFT-SW-1B	METALS	MHP-526	8-94552	8-11438
RFT-SW-2A	METALS	MHP-523	8-94553	8-11438
RFT-SW-2B	METALS	MHP-524	8-94556	8-11438
RFT-SW-3A	METALS	MHP-521	8-94554	8-11438
RFT-SW-3B	METALS	MHP-522	8-94555	8-11438
RFT-SW-4A	METALS	MHP-515	8-94557	8-11438
RFT-SW-4B	METALS	MHP-516	8-94558	8-11438
RFT-SW-5A	METALS	MHP-517	8-94559	8-11438
RFT-SW-5B	METALS	MHP-518	8-94560	8-11438
RFT-SW-6A	METALS	MHP-519	8-94561	8-11438
RFT-SW-6B	METALS	MHP-520	8-94562	8-11438
RFT-SW-7A	METALS	MHP-509	8-94563	8-11446
RFT-SW-7B	METALS	MHP-510	8-94564	8-11446
RFT-SW-8A	METALS	MHP-511	8-94565	8-11446
RFT-SW-8B	METALS	MHP-512	8-94566	8-11446
RFT-SW-9A	METALS	MHP-506	8-94567	8-11446
RFT-SW-9B	METALS	MHP-507	8-94587	8-11446
RFT-SW-10A	METALS	MHP-503	8-94568	8-11446
RFT-SW-10B	METALS	MHP-504	8-94569	8-11446
RFT-SW-11A	METALS	MHP-528	8-94591	8-10998
RFT-SW-11B	METALS	MHP-527	8-94590	8-10998
RFT-SW-12A	METALS	MHP-513	8-94588	8-10998
RFT-SW-12B	METALS	MHP-514	8-94589	8-10998
RFT-SW-15A	METALS	MHP-529	8-94593	8-10998
RFT-SW-15B	METALS	MHP-530	8-94593	8-10998
RFT-SW-16A	METALS	MHP-534	8-94599	8-10997
RFT-SW-16B	METALS	MHP-535	8-94600	8-10997
RFT-SW-17A	METALS	MHP-537	8-94527	8-10997
RFT-SW-17B	METALS	MHP-538	8-94527	8-10997
RFT-SW-18A	METALS	MHP-539	8-94529	8-10997
RFT-SW-18B	METALS	MHP-540	8-94530	8-10997
RFT-TA-1	METALS	MHL-955	8-94580	8-11446
RFT-TA-2	METALS	MHL-956	8-94581	8-11446
RFT-TA-3	METALS	MHP-500	8-94582	8-11446
RFT-TA-4	METALS	MHP-501	8-94583	8-11446
RFT-TA-5	METALS	MHP-502	8-94584	8-11446
RFT-OPW-1A	METALS	MHP-532	8-94595	8-10998
RFT-OPW-1B	METALS	MHP-533	8-94596	8-10998



APPENDIX A CONT.  
SAMPLE COLLECTION AND SHIPMENT INFORMATION  
RICHARDSON FLAT TAILINGS  
SUMMIT COUNTY, UTAH  
TDD F08-8903-06 - PAN FUT0039HDA

SAMPLE ID	PARAMETERS	SAS #	SAMPLE TAG #	CHAIN OF CUSTODY
RFT-SE-1	METALS	4725H-01	8-94570	8-11437
RFT-SE-2	METALS	4725H-02	8-94571	8-11437
RFT-SE-3	METALS	4725H-03	8-94572	8-11437
RFT-SE-4	METALS	4725H-04	8-94573	8-11437
RFT-SE-5	METALS	4725H-05	8-94574	8-11437
RFT-SE-6	METALS	4725H-06	8-94575	8-11437
RFT-SE-7	METALS	4725H-07	8-94576	8-11437
RFT-SE-8	METALS	4725H-08	8-94577	8-11437
RFT-SE-9	METALS	4725H-09	8-94578	8-11437
RFT-SE-10	METALS	4725H-10	8-94579	8-11437
RFT-SE-16	METALS	4725H-13	8-94525	8-11440
RFT-SE-17	METALS	4725H-14	8-94528	8-11440
RFT-OSE-1	METALS	4725H-11	8-94594	8-11437
RFT-OSE-2	METALS	4725H-12	8-94597	8-11437

APPENDIX B  
SAMPLING PHOTO LOG



PHOTO 1: WEST FACING PHOTO OF SAMPLE LOCATION RFT-SW/SE-4.




PHOTO 2: WEST FACING PHOTO OF FIT MEMBER COLLECTING TAILINGS SAMPLE RFT-TA-1.




PHOTO 3 (LEFT): NORTHWEST FACING  
PHOTO OF FIT MEMBER  
COLLECTING TAILINGS SAMPLE  
RFT-TA-2.




PHOTO 4 (BELOW): SOUTH FACING  
PHOTO OF FIT MEMBER  
COLLECTING TAILINGS  
SAMPLE RFT-TA-3.




PHOTO 5: SOUTHWEST VIEW OF SAMPLE LOCATION  
RFT-TA-4.




PHOTO 6: SOUTH VIEW OF SAMPLE LOCATION RFT-TA-5.



PHOTO 7: FIT MEMBER COLLECTING SAMPLE RFT-SW-9.



PHOTO 8: NORTHEAST FACING PHOTO OF FIT MEMBER  
COLLECTING SURFACE WATER SAMPLE  
RFT-SW/SE-7.





PHOTO 9: SOUTHEAST FACING PHOTO OF FIT MEMBER  
COLLECTING SAMPLE RFT-SW/SE-8.



PHOTO 10: NORTH FACING PHOTO OF SAMPLE LOCATION  
RFT-SW/SE-6.



PHOTO 11: WEST FACING PHOTO OF SAMPLE LOCATION  
RFT-SW/SE-5.



PHOTO 12 (ABOVE): SOUTH FACING  
PHOTO OF SURFACE WATER  
SAMPLE LOCATION RFT-OPW-1  
AND RFT-OSE-1 AT BASE OF  
TAILINGS DAM.




PHOTO 13 (LEFT): NORTHEAST  
FACING PHOTO OF OPPOR-  
TUNITY SEDIMENT SAMPLE  
LOCATION RFT-OSE-2.

APPENDIX C

QUALITY ASSURANCE REVIEW

REGION VIII SUMMARY OF DATA QUALITY ASSURANCE REVIEW

\*\*\*guideline references are from Contract #787\*\*\*

Case No.: 12334

TDD No.: FO-8909-08

Site: Richardson Flats

Contractor Laboratory: Silver Valley Labs, Inc.; Kellogg, ID

Data Reviewer : Lynn Fischer

Date of Review: Oct. 11, 1989

Sample Matrix: 19 low waters

Analysis: Metals and Mercury.

Sample Nos.: MHP520, MHP521, MHP522, MHP523, MHP524, MHP525, MHP526,  
MHP527, MHP528, MHP529, MHP530, MHP532, MHP533, MHP534,  
MHP535, MHP537, MHP538, MHP539, and MHP540.

- ( ) Data are acceptable for use.
- (X) Data are acceptable for use with qualifications noted.
- ( ) Data are preliminary - pending verification.
- ( ) Data are unacceptable.

Action required by DPO?

No X Yes \_\_\_\_ The following items require action:

All Mercury data is unusable because of missed holding times. Mercury analysis however was performed by Keystone, TX prior to samples being shipped on to Silver Valley for analysis, this data is being used. SMO, or whomever decided to forward the samples should always consider holding time requirements when making these decisions.

Action required by project officer?

No X Yes \_\_\_\_

The following are our findings:

Data are acceptable for use, with the exception of the mercury analysis, with the following qualifications.

Holding time criteria were met for all analysis with the exception of the mercury cold vapor analysis; all the mercury results are flagged "a", unusable.

All calibration frequencies and requirements were met.

Quite a few contaminants were detected in analysis of the initial, continuing, and laboratory preparation blanks they are: aluminum, antimony, barium, calcium, cadmium, cobalt, copper, iron, magnesium, manganese, potassium, selenium, silver, sodium, zinc, and lead. All samples with positive results for these analytes were flagged "ub", "uj", or "b". "UB" was used to flag those results detected below the contract required detection limit (CRDL), "uj" was used to flag those results greater than the CRDL but less than five times the greatest amount detected in any blank, and "b" was used to flag all other positive results.

Brackets are applied to all results greater than the instrument detection limit (IDL) but less than the CRDL.

Duplicate results for the following analytes were outside limits (+/- 20%), however none were flagged because all were associated with either results below the CRDL, contaminants detected in the blanks, or one of the values was undetected: aluminum, copper, iron, potassium, arsenic, and selenium.

Analysis of the spiked sample had two outliers, lead (16.7%) and selenium (-134.3%), limits are (75-125%). All lead results were flagged "j", results may be biased low. No flags were added to selenium results since both the sample and spiked sample results were less than the CRDL.

All other quality control (QC) criteria were met.

## **Inorganic Data Completeness Checklist**

Inorganic analysis data (Form I)

Initial calibration and continuing calibration verification (Form IIA)

CRDL standard for AA and ICP (Form IIB)

Blanks (Form III)

ICP interference Check sample (Form IV)

Spike sample recovery (Form VA)

Post digestion spike sample recovery (Form VB)

Duplicates (Form VI)

Laboratory control sample (Form VII)

Standard addition results (Form VIII)

ICP serial dilutions (Form IX)

Holding times (Form X)

Instrument detection limits-quarterly (Form XI)

ICP interelement correction factors-quarterly (Form XII)

ICP linear ranges-quarterly (Form XIII)

Raw data for interference checks

Raw data for calibration standards

Raw data for blanks

Raw data for CRI and/or CRA

Raw data for samples

Raw data for duplicates

Raw data for spikes

Traffic reports



### Contract Compliance

#### **I. Initial and Continuing Calibration Verification (ICV and CCV) (guidelines pg. E-4, Form IIA)**

1. Was instrument calibrated daily and each time it was set up?  
yes X no ☐
2. Were instruments calibrated using 1 blank and several standards?  
yes X no ☐
3. Were calibration verifications within 90-110%?  
yes X no ☐
4. Were continuing calibrations run at 10% frequency?  
yes X no ☐
5. Were the raw data correctly transcribed onto Form IIA?  
yes X no ☐

#### **II. CRDL Standards for ICP (CRI) and/or AA (CRA) (guidelines pg. E-6, Form IIB)**

1. For ICP analysis, were standards (CRI) @ 2x the CRDL or the IDL (whichever was greater) analyzed at the beginning and the end of each sample run, or at a minimum of twice/8 hour shift, whichever was more frequent?  
yes X no ☐
2. For furnace AA analysis, were standards (CRA) analyzed at the beginning and the end of each sample run, or at a minimum of twice/8 hour shift, whichever was more frequent?  
yes X no ☐
3. Were the CRI and/or CRA standards analyzed after the ICV?  
yes X no ☐
4. Were these data reported on Form IIB?  
yes X no ☐
5. Were the raw data correctly transcribed onto Form IIB?  
yes X no ☐

#### **III. Blanks (guidelines pg. E-6, Form III)**

1. Was the initial calibration blank (ICB) analyzed immediately after the initial calibration verification (ICV)?  
yes X no ☐
2. Was a continuing calibration blank (CCB) analyzed immediately after each continuing calibration verification (CCV)?  
yes X no ☐
3. Was a preparation blank (PB) analyzed at a frequency of at least 1 in 20 samples?  
yes X no ☐ NA

4. How many elements were detected above the CRDLs? o (if 0, go to question 5)

4a. How many elements were detected in the blanks at greater than one-half the amount detected in any sample?

5. Were raw data correctly transcribed onto Form III?  
yes X no     

Comments: See narrative for elements detected in blanks.

#### IV. ICP Interference Checks (ICS) (guidelines pg. E-7, Form IV)

1. Was the ICS analyzed twice per 8 hour shift?  
yes X no     

2. Were the ICSs analyzed before and after samples?  
yes X no     

3. Was any massive interference detected?  
yes      no X

4. Were the ICSs within  $\pm 20\%$  mean value?  
yes X no     

5. Were raw data correctly transcribed onto Form IV?

#### V. Spike Sample Analysis (S) (guideline pg. E-8, Form V)

1. Were spikes analyzed at a frequency of 1 in 20 samples?  
yes X no     

2. Were spike recoveries correctly calculated?  
yes X no     

$$\% \text{ recovery} = \frac{(\text{SSR} - \text{SR})}{\text{SA}} \times 100$$

SSR = Spiked Sample Result

SR = Sample Result

SA = Spike Added

3. Were spike recoveries within the range of 75-125%?  
yes      no X

3a. For recoveries outside this range, were associated data flagged "N" by the laboratory on Forms I and V?  
yes X no      NA     

(an exception is granted where the sample concentration is  $>4X$  the spike concentration)

4. Were raw data correctly transcribed onto Form V?

yes X      no       

\* Refer to page E-9 (SOW 787) for information regarding the amount of spike to be added for each analyte and for other information about the Spike Sample Analysis.

VI. Duplicates (D) (guidelines pg. E-11, Form VI)

1. Were duplicates analyzed at a frequency of 1 in 20 samples?  
yes X      no       

2. Were RPDs correctly calculated?  
yes X      no       

$$RPD = \frac{S - D}{(S + D)/2} \times 100$$

S = Sample

D = Duplicate

3a. For sample concentrations >5x the CRDL, were RPDs  $\pm 20\%$ ? (limits of  $\pm 35\%$  apply for soil/sediment/tailings samples)

yes X      no \_\_\_\_      NA \_\_\_\_

3b. For sample concentrations >5x the CRDL, did duplicate analysis results fall outside the control window of  $\pm$  the CRDL?

yes \_\_\_\_      no X      NA \_\_\_\_

3c. Where the RPDs exceeded the control limits, were the data flagged '\*' on Forms I and VI by the laboratory?

yes X      no \_\_\_\_      NA \_\_\_\_

4. Were raw data correctly transcribed onto Form VI?

yes X      no \_\_\_\_

\* Other Considerations:

- Field blanks cannot be used for duplicate analyses
- Duplicates must be analyzed for each analytical method

VII. Laboratory Control Sample (LCS) Analysis (guideline pg. E-12, Form VII)

1. Was an LCS analyzed for every sample delivery group or batch of samples, whichever was more frequent?

yes X      no \_\_\_\_

2. Were recoveries within the 80-120% limit?

yes X      no \_\_\_\_

-if the recoveries were outside this range the analysis must be terminated, the problem corrected and the previous samples associated with that LCS redigested and reanalyzed.

3. Were the raw data correctly transcribed onto Form VII?

yes X      no \_\_\_\_

VIII. Furnace Atomic Absorption (AA) QC Analysis (guidelines pg. E-14, Form VIII)

1. Does the raw data package contain absorbance values for two injections per sample, the average values and the relative standard deviation (RSD)?

yes X      no \_\_\_\_

2. For analyte concentrations > the CRDL, did the RSD for the duplicate injections agree within 20%? (if yes, go to question 3)

yes X      no \_\_\_\_

$$RSD = \frac{SD}{M} \times 100$$

SD = Standard Deviation of Duplicate Injections  
M = Mean of Duplicate Injections

2a. Were samples that exceeded the 20% criteria reanalyzed?  
yes ☐ no ☐

2b. Did any reanalyzed samples exceed the 20% criteria?  
yes ☐ no ☐

2c. If yes, did the laboratory flag the data of Form I with an  
'M'?  
yes ☐ no ☐

3. Was the recovery of the spike > 40%? (if yes, go to question  
4).  
yes X no ☐

If no, was the sample diluted and rerun with another spike?  
yes ☐ no ☐

4. Was sample absorbance > 50% of spike absorbance?\* (if yes, go  
to question 5).  
yes ☐ no X ☐

\* Spike absorbance = absorbance of spiked sample - absorbance of sample.

4a. For spike recoveries between 85 and 115%, were results  
reported to the IDL?  
yes X no ☐

$$RPD = \frac{(SSR - SR)}{SA} \times 100$$

SSR = Spike Sample Recovery

SR = Sample Result

SA = Spike Added

4b. For spike recoveries outside the 85 and 115% range, were  
results reported to the IDL and flagged with 'W'?  
yes X no ☐

5. Was spike recovery between 85 and 115%? (if no, go to  
question 6)

5a. Were results quantified from calibration curve and  
reported to IDL?  
yes ☐ no ☐

6. Was an MSA at 50, 100 and 150% of the sample absorbance  
analyzed?  
yes ☐ no ☐

6a. Was each MSA analysis identified in the raw data along  
with the slope, intercept and correlation coefficient?  
yes ☐ no ☐

6b. Were these data correctly transcribed onto Form VIII?

yes no

6c. Were correlation coefficients(r) > 0.995?

yes no

6d. If no, were MSAs run once more?

yes no

- If the correlation coefficients were still > 0.995, data on Form I must be from the run with the best 'r' and the data on Forms I and VII must be flagged with a '+'.  
=

Were these criteria met?

yes no

6e. Were all MSA obtained data marked with an 'S' or an S+ on form I?

yes no

IX. ICP Serial Dilution (L) Analysis (guidelines pg. E-12, Form IX)

1. Was an ICP serial dilution performed on each group of samples of a similar matrix (i.e., soil, water) and concentration (i.e., low, high) or for each sample delivery group, whichever was more frequent?

yes X no \_\_\_\_

2. For elements with concentrations >10X the CRDL, did any exceed the serial dilution results by more than 10%? (if no, skip questions 3 and 4)

yes  $\frac{I}{S}$  X no \_\_\_\_  
//

$$\% \text{ difference} = \frac{I - S}{I} \times 100$$

I = Initial Sample Result

S = Serial Dilution Result (instrument reading X5)

3. Which elements had concentrations that exceeded the 10% criteria? only those associated with undetected values or blank contaminanats.

4. Did the laboratory flag these data with an 'E' on Form IX?

yes no

5. Were the raw data correctly transcribed onto Form IX?

yes X no \_\_\_\_

X. Instrument Detection Limits (IDL) (guidelines pg. E-13, Form XI)

1. Were IDLs reported for each analyzed element?

yes X no \_\_\_\_

2. Were IDLs reported for each instrument used?

yes X no \_\_\_\_

3. Did the IDLs meet the contract requirements? (refer to pg. E-13, SOW 787)

**XI. Interelement Corrections for ICP (guidelines pg. E-13, Form XII)**

1. Were correction factors reported on Form XII?

yes X          no ☐

**XII. Linear Range Analysis (LRA) (guidelines pg. E-14, Form XII)**

1. Was a linear range verification standard analyzed?

yes X          no ☐

2. Was the results within  $\pm 5\%$  of the true value?

yes X          no ☐

**Holding Times**

Limits: Metals - 6 months; Hg - 30 days; Cn - 28 days.

1. Verified date of sample receipt by laboratory 8-16-89

2. Date of preparation/analyses ICP - 8-24-89

AS - 8-31-89

SE - 8-31-89

PB - 8-29-89

TL - 8-24-89

3. Were holding times met? yes X, for all but HG

## U.S. EPA - CLP

1-  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: SILVER VALLEY LABS., INC.

Contract: 8608-0074

MHP520

Lab Code: SILVER

Case No.: 12334

SAS No.: \_\_\_\_\_

SDC No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	34.7	B	UB	P
7440-36-0	Antimony	19.9	U		P
7440-38-2	Arsenic	3.9	B		P
7440-39-3	Barium	14.9	B		P
7440-41-7	Beryllium	1.1	U		P
7440-43-9	Cadmium	1.8	U		P
7440-70-2	Calcium	830000.		B	P
7440-47-3	Chromium	2.8	U		P
7440-48-4	Cobalt	3.87	B		P
7440-50-8	Copper	1.2	B		P
7439-89-6	Iron	123.			P
7439-92-1	Lead	1.9	B	N	P
7439-95-4	Magnesium	71200.		B	P
7439-96-5	Manganese	3170.		B	P
7439-97-6	Mercury	0.2	U	R	P
7440-02-0	Nickel	9.7	U		P
7440-09-7	Potassium	2230.	B		P
7782-49-2	Selenium	12.0	U	NK	P
7440-22-4	Silver	1.6	U		P
7440-23-5	Sodium	49600.		B	P
7440-28-0	Thallium	0.9	U		P
7440-62-2	Vanadium	2.7	U		P
7440-66-6	Zinc	198.		B	P
	Cyanide				P

Color Before: COLORLESS

Clarity Before: CLEAR

Texture: \_\_\_\_\_

Color After: COLORLESS

Clarity After: CLEAR

Artifacts: \_\_\_\_\_

Comments:



U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-03-0071~~ <sup>68-080074</sup>

MHP521

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>mab</sup> 1908/89

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	D	M	
7429-90-5	Aluminum	[16.5]	8	UG	P	LAF
7440-36-0	Antimony	19.9	U		P	
7440-38-2	Arsenic	[3.8]	8	IN	F	mab 08/08/89
7440-39-3	Barium	[52.9]	8	UG	P	LAF
7440-41-7	Beryllium	1.1	U		P	
7440-43-9	Cadmium	9.2	1		P	LAF
7440-70-2	Calcium	199000	1	P	P	LAF
7440-47-3	Chromium	2.8	U		P	
7440-48-4	Cobalt	[2.6]	8	UG	P	LAF
7440-50-8	Copper	[1.5]	8	UG	P	LAF
7439-89-6	Iron	[39.9]	8	UG	P	LAF
7439-92-1	Lead	38.2	1	NS	F	mab 08/08/89
7439-95-4	Magnesium	39600	1	B	P	LAF
7439-96-5	Manganese	1080	1	B	P	LAF
7439-97-6	Mercury	0.20	U	IN R	CV	mab LAF 08/08/89
7440-02-0	Nickel	9.7	U		P	
7440-09-7	Potassium	[3470]	8	UG	P	LAF
7782-49-2	Selenium	14.7	8	IN* UG	F	LAF
7440-22-4	Silver	1.6	U		P	
7440-23-5	Sodium	41000	1	B	P	LAF
7440-28-0	Thallium	0.90	U	IN	F	LAF
7440-62-2	Vanadium	2.7	U		P	
7440-66-6	Zinc	2360	1	B	P	LAF
	Cyanide				NR	

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-05-0071~~ *68-08-0014*

MHP522

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1740	1	B	P
7440-36-0	Antimony	53.8	1	B	P
7440-38-2	Arsenic	41.9	1	N	F
7440-39-3	Barium	182.2	1	B	P
7440-41-7	Beryllium	1.1	U	1	P
7440-43-3	Cadmium	16.0	1	B	P
7440-70-2	Calcium	206000	1	B	P
7440-47-3	Chromium	2.8	U	1	P
7440-48-4	Cobalt	15.7	1	B	P
7440-50-8	Copper	71.4	1	B	P
7439-89-6	Iron	5320	1	B	P
7439-92-1	Lead	1100	1	B	P
7439-95-4	Magnesium	42000	1	B	P
7439-96-5	Manganese	1220	1	B	P
7439-97-6	Mercury	2.2	1	N	R
7440-02-0	Nickel	9.7	U	1	P
7440-09-7	Potassium	3160	1	B	P
7782-49-2	Selenium	28.5	1	B	NW*
7440-22-4	Silver	16.3	1	B	P
7440-23-5	Sodium	42000	1	B	P
7440-28-0	Thallium	0.90	U	1	F
7440-62-2	Vanadium	15.5	1	B	P
7440-66-6	Zinc	3790	1	B	P
	Cyanide				NR

Color Before: BROWN

Clarity Before: CLEAR

Texture:

Color After: BROWN

Clarity After: CLEAR

Artifacts:

Comments:

18

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-89-0071~~ **62-108-0074**

MHP523

Lab Code: SILVER

Case No.: 12334

SAS No.: **mb 10/2/89**

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	18.2	BI	UB	P
7440-36-0	Antimony	25.7	BI	UB	P
7440-38-2	Arsenic	16.6	BI	NW	F
7440-39-3	Barium	61.5	BI	UB	P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	5.0	BI	UB	P
7440-70-2	Calcium	211000		B	P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	3.5	BI	UB	P
7440-50-8	Copper	1.2	BI	UB	P
7439-89-6	Iron	63.2	BI	UB	P
7439-92-1	Lead	48.3	BI	NW	F
7439-95-4	Magnesium	41400		B	P
7439-96-5	Manganese	1170		B	P
7439-97-6	Mercury	0.20	UI	N	CV
7440-02-0	Nickel	13.9	BI		P
7440-09-7	Potassium	3180	BI	UB	P
7782-49-2	Selenium	2.6	BI	N*UB	F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	42300		B	P
7440-28-0	Thallium	0.90	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	1730		B	P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-08-0071~~ *68-08-0074*  
*mab/10/187*

MHP524

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M	
7429-90-5	Aluminum	44500	13		P	LAF
7440-38-0	Antimony	210	13		P	LAF
7440-38-2	Arsenic	619	1		P	
7440-39-3	Barium	881	13		P	LAF
7440-41-7	Beryllium	[2.4]	81		P	
7440-43-9	Cadmium	137	13		P	LAF
7440-70-2	Calcium	248000	13		P	LAF
7440-47-3	Chromium	72.2	1		P	
7440-48-4	Cobalt	[27.0]	81	13	P	LAF
7440-50-8	Copper	1390	13		P	LAF
7439-89-6	Iron	98500	13		P	LAF
7439-92-1	Lead	20000	12	13	P	LAF
7439-95-4	Magnesium	68400	13		P	LAF
7439-96-5	Manganese	3080	13		P	LAF
7439-97-6	Mercury	39.2	N	R	CV	<i>mab LAF</i> <i>09/08/89</i>
7440-02-0	Nickel	67.3	1		P	
7440-09-7	Potassium	8980	13		P	LAF
7782-49-2	Selenium	134.2	81	N*	13	LAF
7440-22-4	Silver	131	13		P	LAF
7440-23-5	Sodium	42300	13		P	LAF
7440-28-0	Thallium	[4.7]	81	W	13	LAF
7440-62-2	Vanadium	129	1		P	
7440-66-6	Zinc	19300	13		P	LAF
	Cyanide		1		NR	

Color Before: BROWN

Clarity Before: OPAQUE

Texture:

Color After: BROWN

Clarity After: OPAQUE

Artifacts:

Comments:

20

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-08-0074~~  
68-08-0074  
MHP-100481

MHP525

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	127.9	BI	UB	IP
7440-36-0	Antimony	19.9	UI		IP
7440-38-2	Arsenic	17.2	BI	NW	IF
7440-39-3	Barium	161.9	BI	UB	IP
7440-41-7	Beryllium	1.1	UI		IP
7440-43-3	Cadmium	1.8	UI		IP
7440-70-2	Calcium	132000	1	B	IP
7440-47-3	Chromium	2.8	UI		IP
7440-48-4	Cobalt	13.1	BI	UB	IP
7440-50-8	Copper	1.1	UI		IP
7439-89-6	Iron	156.4	BI	UB	IP
7439-92-1	Lead	9.2	INS*	BJ	IF
7439-95-4	Magnesium	34700	1	B	IP
7439-96-5	Manganese	20.3	1	B	IP
7439-97-6	Mercury	0.20	UI	N	CV
7440-02-0	Nickel	9.7	UI		IP
7440-09-7	Potassium	18201	BI	UB	IP
7782-49-2	Selenium	15.4	BI	N*	IF
7440-22-4	Silver	1.6	UI		IP
7440-23-5	Sodium	19700			IP
7440-28-0	Thallium	0.90	UI		IF
7440-62-2	Vanadium	2.7	UI		IP
7440-66-6	Zinc	64.1	1	R	IP
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-09-0071~~ *68-08-0014*

MHP526

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	26.31	BI	UB	P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	17.7	BI	NW	F
7440-39-3	Barium	61.9	BI	UB	P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.8	UI		P
7440-70-2	Calcium	131000	18		P
7440-47-3	Chromium	2.9	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	12.41	BI	UB	P
7439-89-6	Iron	84.71	BI	UB	P
7439-92-1	Lead	0.931	BI	NW	F
7439-95-4	Magnesium	34400	12		P
7439-96-9	Manganese	19.1	13		P
7439-97-6	Mercury	0.20	UI	N	CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	2110	BI	UB	P
7782-49-2	Selenium	15.2	BI	NW	F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	19700	1		P
7440-29-0	Thallium	0.30	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	32.7	13		P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

22

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

MHP527

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-038-0074~~  
MB 1902/81

Lab Code: SILVER

Case No.: 12334

SAS No.

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	43400	13	P	LAF
7440-36-0	Antimony	199	13	P	LAF
7440-38-2	Arsenic	540	13	P	LAF
7440-39-3	Barium	788	13	P	LAF
7440-41-7	Beryllium	2.1	13	P	LAF
7440-43-9	Cadmium	127	13	P	LAF
7440-70-2	Calcium	246000	13	P	LAF
7440-47-3	Chromium	68.5	13	P	LAF
7440-48-4	Cobalt	28.4	13	P	LAF
7440-50-8	Copper	1260	13	P	LAF
7439-89-6	Iron	89300	13	P	LAF
7439-92-1	Lead	17900	13	P	LAF
7439-95-4	Magnesium	67100	13	P	LAF
7439-96-5	Manganese	2950	13	P	LAF
7439-97-6	Mercury	36.0	13	P	LAF
7440-02-0	Nickel	57.3	13	P	LAF
7440-09-7	Potassium	8770	13	P	LAF
7782-49-2	Selenium	43.9	13	P	LAF
7440-22-4	Silver	117	13	P	LAF
7440-23-5	Sodium	42700	13	P	LAF
7440-28-0	Thallium	4.27	13	P	LAF
7440-62-2	Vanadium	121	13	P	LAF
7440-66-6	Zinc	17700	13	P	LAF
	Cyanide		1	NR	

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

23

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

MHP528

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-08-0074~~  
MHP 9/02/89

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	228.0	BI	UB	P
7440-36-0	Antimony	26.9	BI	UB	P
7440-38-2	Arsenic	5.6	BI	NW	F
7440-39-3	Barium	60.8	BI	UB	P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	6.0	1	B	P
7440-70-2	Calcium	211000	1	B	P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	15.3	BI	UB	P
7440-50-8	Copper	1.2	BI	UB	P
7439-99-6	Iron	55.1	BI	UB	P
7439-92-1	Lead	34.6	INX		F
7439-95-4	Magnesium	41400	1	B	P
7439-96-5	Manganese	1180	1	B	P
7439-97-6	Mercury	0.20	UI	N	CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	3060	BI	UB	P
7782-49-2	Selenium	15.1	BI	NW*	F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	41200	1		P
7440-28-0	Thallium	0.90	UI		F
7440-62-2	Vanadium	3.8	BI		P
7440-66-6	Zinc	1730	1	B	P
	Cyanide				NR

68-08-0074  
MHP 9/02/89

MHP 9/02/89

MHP 9/02/89

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:



24

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-W8-0074~~  
MAB 09/02/89

MHP529

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	[24.9]	BI	UA	P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	2.3	UI	N	F
7440-39-3	Barium	1.3	UI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.8	UI		P
7440-70-2	Calcium	[214]	BI	UA	P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	1.1	UI		P
7439-89-6	Iron	[64.2]	BI	UA	P
7439-92-1	Lead	[1.8]	BI	NX	F
7439-95-4	Magnesium	43.7	BI	UA	P
7439-96-5	Manganese	1.4	BI	UA	P
7439-97-6	Mercury	0.20	UI	N	R
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	273	UI		P
7782-49-2	Selenium	1.2	UI	NW*	F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	[47.5]	BI	UA	P
7440-28-0	Thallium	0.90	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	[12.6]	BI	UA	P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

25

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-08-0074~~  
68-08-0074  
MHP/04/89

MHP530

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	132.1	81	UA	P
7440-36-0	Antimony	19.9	UI		P
7440-33-2	Arsenic	2.3	UI	N	F
7440-39-3	Barium	1.3	UI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.8	UI		P
7440-70-2	Calcium	136	81	UA	P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	1.1	UI		P
7439-89-6	Iron	41.5	81	UA	P
7439-92-1	Lead	1.6	81	NW	F
7439-95-4	Magnesium	29.0	81	UA	P
7439-96-5	Manganese	2.5	81	UA	P
7439-97-6	Mercury	0.20	UI	N R	CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	273	UI		P
7782-49-2	Selenium	1.2	UI	N*	F
7440-22-4	Silver	23.8	13		P
7440-23-5	Sodium	13.2	UI		P
7440-28-0	Thallium	0.90	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	6.5	81	UA	P
	Cyanide				NR

LAF  
MAB  
09/08/89

LAF  
09/08/89

MAB LAF  
09/08/89

LAF

LAF

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

EPA SAMPLE NO.

## INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-008-0074~~ *MHP 532*

MHP532

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	23.0	BLUB	IP	LAF
7440-38-0	Antimony	19.9	UI	IP	
7440-38-2	Arsenic	12.9	BLUB	IP	LAF
7440-39-3	Barium	137.3	BLUB	IP	LAF
7440-41-7	Beryllium	1.1	UI	IP	
7440-43-9	Cadmium	1.8	UI	IP	
7440-70-2	Calcium	321000		IP	
7440-47-3	Chromium	2.8	UI	IP	
7440-48-4	Cobalt	6.3	BLUB	IP	LAF
7440-50-8	Copper	1.2	BLUB	IP	LAF
7439-89-6	Iron	503	IB	IP	LAF
7439-92-1	Lead	0.90	UINW*	IP	LAF
7439-95-4	Magnesium	56100	IB	IP	LAF
7439-96-5	Manganese	12900	IB	IP	LAF
7439-97-6	Mercury	0.20	UINW*	IP	LAF
7440-02-0	Nickel	9.7	UI	IP	
7440-09-7	Potassium	5380		IP	
7782-49-2	Selenium	12.0	UINW*	IP	LAF
7440-22-4	Silver	1.6	UI	IP	
7440-23-5	Sodium	60000	IB	IP	LAF
7440-28-0	Thallium	0.90	UI	IP	
7440-62-2	Vanadium	2.7	UI	IP	
7440-66-6	Zinc	19.8	BLUB	IP	LAF
	Cyanide			INR	

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

27

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

MHP533

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-W8-0074~~  
68-W8-0074  
mbs 10/2/89

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	317	B	P	LAF
7440-36-0	Antimony	19.9	UI	P	
7440-38-2	Arsenic	33.1	NS	F	
7440-39-3	Barium	22.2	B	P	mbs 08/02/89
7440-41-7	Beryllium	1.1	UI	P	
7440-43-9	Cadmium	13.6	B	P	LAF
7440-70-2	Calcium	369000	B	P	LAF
7440-47-3	Chromium	2.8	UI	P	
7440-48-4	Cobalt	5.6	B	P	LAF
7440-50-8	Copper	6.6	B	P	LAF
7439-89-6	Iron	10200	B	P	LAF
7439-92-1	Lead	68.2	NS	F	mbs 08/02/89
7439-95-4	Magnesium	58800	B	P	LAF
7439-96-5	Manganese	21400	B	P	LAF
7439-97-6	Mercury	0.20	UI	R	CV LAF
7440-02-0	Nickel	9.7	UI	P	
7440-09-7	Potassium	9960		P	
7782-49-2	Selenium	18.5	B	NR*	F LAF
7440-22-4	Silver	1.6	UI	P	
7440-23-5	Sodium	63400	B	P	LAF
7440-28-0	Thallium	0.20	UI	F	
7440-62-2	Vanadium	2.7	UI	P	
7440-66-6	Zinc	759	B	P	LAF
	Cyanide			NR	

Color Before: YELLOW

Clarity Before: CLOUDY

Texture:

Color After: YELLOW

Clarity After: CLOUDY

Artifacts:

Comments:

28

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-03-0071~~ 68-W8-0074

MHP534

Lab Code: SILVER

Case No.: 12334

SAS No.: 07/14/89

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	744.6	81	UB	P
7440-38-0	Antimony	20.1	81	UB	P
7440-38-2	Arsenic	2.3	UI	NW	F
7440-39-3	Barium	156.7	81	UB	P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	10.3	1B		P
7440-70-2	Calcium	205000	1B		P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	3.17	81	UB	P
7440-50-8	Copper	2.7	81	UB	P
7439-89-6	Iron	31.5	81	UB	P
7439-92-1	Lead	1.4	81	NW	F
7439-95-4	Magnesium	40400	1B		P
7439-96-5	Manganese	1070	1B		P
7439-97-6	Mercury	0.20	UI	R	CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	3180	81	UB	P
7782-49-2	Selenium	2.7	81	NW	F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	41900	1B		P
7440-28-0	Thallium	0.90	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	2970	1B		P
	Cyanide		1		NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

29

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: 68-08-0074

MHP535

Lab Code: SILVER

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	161.1	UI	IB	IP
7440-38-0	Antimony	19.9	UI		IP
7440-38-2	Arsenic	15.6	UI	IB	IP
7440-39-3	Barium	56.0	UI	IB	IP
7440-41-7	Beryllium	1.1	UI		IP
7440-43-9	Cadmium	10.3	UI	IB	IP
7440-70-2	Calcium	205000	UI	IB	IP
7440-47-3	Chromium	2.8	UI		IP
7440-48-4	Cobalt	3.5	UI	IB	IP
7440-50-8	Copper	4.9	UI	IB	IP
7439-99-6	Iron	496	UI	IB	IP
7439-92-1	Lead	25.2	UI	IB	IP
7439-95-4	Magnesium	40300	UI	IB	IP
7439-96-5	Manganese	1080	UI	IB	IP
7439-97-6	Mercury	0.20	UI	IB	IP
7440-02-0	Nickel	10.6	UI	IB	IP
7440-09-7	Potassium	3350	UI	IB	IP
7782-49-2	Selenium	1.2	UI	NW*	IF
7440-22-4	Silver	1.6	UI		IP
7440-23-5	Sodium	41900	UI		IP
7440-28-0	Thallium	0.90	UI		IF
7440-62-2	Vanadium	2.7	UI		IP
7440-66-6	Zinc	3130	UI	IB	IP
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

30

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-108-0074~~  
68-108-0071

MHP537

Lab Code: SILVER

Case No.: 12334

SAS No.: ~~10/2/89~~

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	149.5	UI	UB	P LAF
7440-36-0	Antimony	19.9	UI		P LAF
7440-38-2	Arsenic	2.3	UI	NW	F LAF
7440-39-3	Barium	54.3	UI	UB	P LAF
7440-41-7	Beryllium	1.1	UI		P LAF
7440-43-9	Cadmium	13.3		B	P LAF
7440-70-2	Calcium	228000		B	P LAF
7440-47-3	Chromium	2.3	UI		P LAF
7440-48-4	Cobalt	6.6	UI	UB	P LAF
7440-50-8	Copper	3.9	UI	UB	P LAF
7439-89-6	Iron	346		B	P LAF
7439-92-1	Lead	8.8		NR	F LAF
7439-95-4	Magnesium	41800		B	P LAF
7439-96-5	Manganese	1380		B	P LAF
7439-97-6	Mercury	0.20	UI	N R	CV LAF
7440-02-0	Nickel	9.7	UI		P LAF
7440-09-7	Potassium	3630	UI	UB	P LAF
7782-49-2	Selenium	20.0	UI	NW* UB	F LAF
7440-22-4	Silver	1.6	UI		P LAF
7440-23-5	Sodium	48000		B	P LAF
7440-28-0	Thallium	0.90	UI		F LAF
7440-62-2	Vanadium	2.7	UI		P LAF
7440-66-6	Zinc	3880		B	P LAF
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

32

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-03-0071~~ **68-W8-0074**

MHP539

Lab Code: SILVER

Case No.: 12334

SAS No.: **mab 9/2/89**

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	22.0	BLUB	P	
7440-36-0	Antimony	12.9	UI	P	
7440-38-2	Arsenic	2.3	UIN	F	
7440-39-3	Barium	1.7	BLUB	P	
7440-41-7	Beryllium	1.1	UI	P	
7440-43-8	Cadmium	1.9	UI	P	
7440-70-2	Calcium	1109	BLUB	P	
7440-47-0	Chromium	2.8	UI	P	
7440-48-4	Cobalt	2.6	UI	P	
7440-50-8	Copper	1.1	UI	P	
7439-89-6	Iron	33.4	BLUB	P	
7439-92-1	Lead	1.3	UINWA	F	
7439-93-4	Magnesium	38.6	BLUB	P	
7439-96-3	Manganese	2.0	BLUB	P	
7439-97-6	Mercury	0.20	UIN R	CV	
7440-02-0	Nickel	9.7	UI	P	
7440-09-7	Potassium	272	UI	P	
7782-49-2	Selenium	1.2	UIN*	F	
7440-22-4	Silver	1.6	UI	P	
7440-23-5	Sodium	41.8	BLUB	P	
7440-28-0	Thallium	0.90	UI	F	
7440-82-2	Vanadium	2.7	UI	P	
7440-66-6	Zinc	2.9	BLUB	P	
	Cyanide			NR	

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:



U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: ~~68-08-0071~~ **68-08-0014**

MHP538

Lab Code: SILVER

Case No.: 12334

SAS No.: **08/01/89**

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M	
7429-90-5	Aluminum	29.6	B	00	P	LAF
7440-36-0	Antimony	20.1	B	00	P	LAF
7440-38-2	Arsenic	2.3	U	NW	F	LAF
7440-39-3	Barium	51.1	B	00	P	LAF
7440-41-7	Beryllium	1.1	U		P	LAF
7440-43-9	Cadmium	13.5	B		P	LAF
7440-70-2	Calcium	218000	B		P	LAF
7440-47-3	Chromium	2.8	U		P	LAF
7440-48-4	Cobalt	15.3	B	00	P	LAF
7440-50-8	Copper	11.5	B	00	P	LAF
7439-89-6	Iron	43.7	B	00	P	LAF
7439-92-1	Lead	0.90	U	NW	F	LAF
7439-95-4	Magnesium	39900	B		P	LAF
7439-96-5	Manganese	1330	B		P	LAF
7439-97-6	Mercury	0.20	U	N R	CV	LAF
7440-02-0	Nickel	3.7	U		P	LAF
7440-09-7	Potassium	3570	B	00	P	LAF
7782-49-2	Selenium	18.0	B	NW*	F	LAF
7440-22-4	Silver	1.6	U		P	LAF
7440-23-5	Sodium	46400	B		P	LAF
7440-28-0	Thallium	0.90	U		F	LAF
7440-62-2	Vanadium	2.7	U		P	LAF
7440-66-6	Zinc	3720	B		P	LAF
	Cyanide				NR	

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

3-3

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS, INC.

Contract: 68-008-0074

MHP540

Lab Code: SILVER

Case No.: 12334

SAS No.: mb 08/08/89

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	127.0	8	LAB	P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	2.3	UI	NW	F
7440-39-3	Barium	1.3	UI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.3	UI		P
7440-70-2	Calcium	190.8	8	LAB	P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.7	8	LAB	P
7440-50-9	Copper	1.1	UI		P
7439-89-6	Iron	132.2	8	LAB	P
7439-92-1	Lead	0.90	UI	NW	F
7439-93-4	Magnesium	127.8	8	LAB	P
7439-96-5	Manganese	1.4	8	LAB	P
7439-97-6	Mercury	0.20	UI	N R	CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	1437	8	LAB	P
7782-49-2	Selenium	1.2	UI	NW*	F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	113.3	8	LAB	P
7440-28-0	Thallium	0.90	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	1.3	UI		P
	Cyanide				NR

mb 08/08/89

mb 08/08/89

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

**REGION VIII SUMMARY OF DATA QUALITY ASSURANCE REVIEW**

**\*\*\*guideline references are from Contract #787\*\*\***

Case No.: 12334

TDD No.: F08-8909-08

Site: Richardson Flats

Contractor Laboratory: Keystone-Houston

Data Reviewer : Annette Sackman

Date of Review: 10-3-89

Sample Matrix: 19 Low Waters

Analysis: Mercury

Sample Nos.: MHP520, MHP521, MHP522, MHP523, MHP524, MHP525, MHP526,  
MHP527, MHP528, MHP529, MHP530, MHP532, MHP533, MHP534,  
MHP535, MHP537, MHP538, MHP539, MHP540

☒ (X) Data are acceptable for use.

☐ ( ) Data are acceptable for use with qualifications noted.

☐ ( ) Data are preliminary - pending verification.

☐ ( ) Data are unacceptable.

Action required by DPO?

No ☒ X Yes      The following items require action:

Action required by project officer?

No ☒ X Yes

The following are our findings:

All requirements were met for the mercury analysis except Form VII - Laboratory Control Sample was not included. Since the LCS was analyzed and reported in the raw data and met all other requirements, no action is taken.

### **Inorganic Data Completeness Checklist**

- X Inorganic analysis data (Form I)
- X Initial calibration and continuing calibration verification (Form IIA)
- X CRDL standard for AA and ICP (Form IIB)
- X Blanks (Form III)
- X ICP interference Check sample (Form IV)
- X Spike sample recovery (Form VA)
- X Post digestion spike sample recovery (Form VB)
- X Duplicates (Form VI)
- X Laboratory control sample (Form VII)
- X Standard addition results (Form VIII)
- X ICP serial dilutions (Form IX)
- X Holding times (Form X)
- X Instrument detection limits-quarterly (Form XI)
- X ICP interelement correction factors-quarterly (Form XII)
- X ICP linear ranges-quarterly (Form XIII)
- X Raw data for interference checks
- X Raw data for calibration standards
- X Raw data for blanks
- X Raw data for CRI and/or CRA
- X Raw data for samples
- X Raw data for duplicates
- X Raw data for spikes
- X Traffic reports

Contract Compliance

**I. Initial and Continuing Calibration Verification (ICV and CCV)  
(guidelines pg. E-4, Form IIA)**

1. Was instrument calibrated daily and each time it was set up?  
yes X no
2. Were instruments calibrated using 1 blank and several standards?  
yes X no
3. Were calibration verifications within 90-110%?  
yes X no
4. Were continuing calibrations run at 10% frequency?  
yes X no
5. Were the raw data correctly transcribed onto Form IIA?  
yes X no

Comments: All requirements met.

**II. CRDL Standards for ICP (CRI) and/or AA (CRA) (guidelines pg. E-6,  
Form IIB)**

1. For ICP analysis, were standards (CRI) @ 2x the CRDL or the IDL  
(whichever was greater) analyzed at the beginning and the end of  
each sample run, or at a minimum of twice/8 hour shift,  
whichever was more frequent?  
yes no
2. For furnace AA analysis, were standards (CRA) analyzed at the  
beginning and the end of each sample run, or at a minimum of  
twice/8 hour shift, whichever was more frequent?  
yes no
3. Were the CRI and/or CRA standards analyzed after the ICV?  
yes no
4. Were these data reported on Form IIB?  
yes no
5. Were the raw data correctly transcribed onto Form IIB?  
yes no

Comments: Not required.

**III. Blanks (guidelines pg. E-6, Form III)**

1. Was the initial calibration blank (ICB) analyzed immediately after the initial calibration verification (ICV)?  
yes X                      no
2. Was a continuing calibration blank (CCB) analyzed immediately after each continuing calibration verification (CCV)?  
yes X                      no
3. Was a preparation blank (PB) analyzed at a frequency of at least 1 in 20 samples?  
yes X                      no                      NA
4. How many elements were detected above the CRDLs? 0 (if 0, go to question 5)  
  
4a. How many elements were detected in the blanks at greater than one-half the amount detected in any sample?
5. Were raw data correctly transcribed onto Form III?  
yes X                      no

Comments: All requirements met.

**IV. ICP Interference Checks (ICS) (guidelines pg. E-7, Form IV)**

1. Was the ICS analyzed twice per 8 hour shift?  
yes                      no
2. Were the ICSs analyzed before and after samples?  
yes                      no
3. Was any massive interference detected?  
yes                      no
4. Were the ICSs within  $\pm 20\%$  mean value?  
yes                      no
5. Were raw data correctly transcribed onto Form IV?

Comments: Not required.

V. Spike Sample Analysis (S) (guideline pg. E-8, Form V)

1. Were spikes analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were spike recoveries correctly calculated?  
yes X no

$$\% \text{ recovery} = \frac{(\text{SSR} - \text{SR})}{\text{SA}} \times 100$$

SSR = Spiked Sample Result

SR = Sample Result

SA = Spike Added

3. Were spike recoveries within the range of 75-125%?  
yes X no

3a. For recoveries outside this range, were associated data  
flagged "N" by the laboratory on Forms I and V?  
yes no NA X

(an exception if granted where the sample concentration is >4X  
the spike concentration)

4. Were raw data correctly transcribed onto Form V?  
yes X no

\* Refer to page E-9 (SOW 787) for information regarding the amount of  
spike to be added for each analyte and for other information about the  
Spike Sample Analysis.

Comments: All requirements met.

VI. Duplicates (D) (guidelines pg. E-11, Form VI)

1. Were duplicates analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were RPDs correctly calculated?  
yes X no

$$\text{RPD} = \frac{S - D}{(S + D)/2} \times 100$$

S = Sample

D = Duplicate



3a. For sample concentrations >5x the CRDL, were RPDs  $\pm 20\%$ ? (limits of  $\pm 35\%$  apply for soil/sediment/tailings samples)

yes X                      no                      NA

3b. For sample concentrations >5x the CRDL, did duplicate analysis results fall outside the control window of  $\pm$  the CRDL?

yes                      no X                      NA

3c. Where the RPDs exceeded the control limits, were the data flagged '\*' on Forms I and VI by the laboratory?

yes                      no                      NA

4. Were raw data correctly transcribed onto Form VI?

yes X                      no

\* Other Considerations:

- Field blanks cannot be used for duplicate analyses
- Duplicates must be analyzed for each analytical method

Comments: All requirements met.

VII. Laboratory Control Sample (LCS) Analysis (guideline pg. E-12, Form VII)

1. Was an LCS analyzed for every sample delivery group or batch of samples, whichever was more frequent?

yes X                      no

2. Were recoveries within the 80-120% limit?

yes X                      no

-if the recoveries were outside this range the analysis must be terminated, the problem corrected and the previous samples associated with that LCS redigested and reanalyzed.

3. Were the raw data correctly transcribed onto Form VII?

yes                      no X

Comments: Form VII was not included in the data package, however, the LCS was analyzed and met contract requirements, therefore, no action is taken.

**VIII. Furnace Atomic Absorption (AA) QC Analysis (guidelines pg. E-14, Form VIII)**

1. Does the raw data package contain absorbance values for two injections per sample, the average values and the relative standard deviation (RSD)?

yes                      no

2. For analyte concentrations > the CRDL, did the RSD for the duplicate injections agree within 20%? (if yes, go to question 3)

yes                      no

$$RSD = \frac{SD}{M} \times 100$$

SD = Standard Deviation of Duplicate Injections  
M = Mean of Duplicate Injections

- 2a. Were samples that exceeded the 20% criteria reanalyzed?

yes                      no

- 2b. Did any reanalyzed samples exceed the 20% criteria?

yes                      no

- 2c. If yes, did the laboratory flag the data of Form I with an 'M'?

yes                      no

3. Was the recovery of the spike > 40%? (if yes, go to question 4).

yes                      no

If no, was the sample diluted and rerun with another spike?

yes                      no

4. Was sample absorbance 50% of spike absorbance?\* (if yes, go to question 5).

yes                      no

\* Spike absorbance = absorbance of spiked sample - absorbance of sample.

4a. For spike recoveries between 85 and 115%, were results reported to the IDL?

yes                      no

$$RPD = \frac{(SSR - SR)}{SA} \times 100$$

SSR = Spike Sample Recovery

SR = Sample Result

SA = Spike Added

4b. For spike recoveries outside the 85 and 115% range, were results reported to the IDL and flagged with 'W'?

yes                      no

5. Was spike recovery between 85 and 115%? (if no, go to question 6)

5a. Were results quantified from calibration curve and reported to IDL?

yes                      no

6. Was an MSA at 50, 100 and 150% of the sample absorbance analyzed?

yes                      no

6a. Was each MSA analysis identified in the raw data along with the slope, intercept and correlation coefficient?

yes                      no

6b. Were these data correctly transcribed onto Form VIII?

yes                      no

6c. Were correlation coefficients(r) > 0.995?

yes                      no

6d. If no, were MSAs run once more?

yes                      no

- If the correlation coefficients were still > 0.995, data on Form I must be from the run with the best 'r' and the data on Forms I and VII must be flagged with a '+'.  
Were these criteria met?

yes                      no

6e. Were all MSA obtained data marked with an 'S' or an S+ on form I?

yes                      no

Comments: Not required.

**IX. ICP Serial Dilution (L) Analysis (guidelines pg. E-12, Form IX)**

1. Was an ICP serial dilution performed on each group of samples of a similar matrix (i.e., soil, water) and concentration (i.e., low, high) or for each sample delivery group, whichever was more frequent?

yes                      no

2. For elements with concentrations >10X the CRDL, did any exceed the serial dilution results by more than 10%? (if no, skip questions 3 and 4)

yes                      no

$$\% \text{ difference} = \frac{I - S}{I} \times 100$$

I = Initial Sample Result

S = Serial Dilution Result (instrument reading X5)

3. Which elements had concentrations that exceeded the 10% criteria?

4. Did the laboratory flag these data with an 'E' on Form IX?

yes                      no

5. Were the raw data correctly transcribed onto Form IX?

yes                      no

Comments: Not required.

**X. Instrument Detection Limits (IDL) (guidelines pg. E-13, Form XI)**

1. Were IDLs reported for each analyzed element?  
yes X no

2. Were IDLs reported for each instrument used?  
yes X no

3. Did the IDLs meet the contract requirements? (refer to pg. E-13, SOW 787)  
yes X no

Comments: All requirements met.

**XI. Interelement Corrections for ICP (guidelines pg. E-13, Form XII)**

1. Were correction factors reported on Form XII?  
yes X no

Comments: All requirements met.

**XII. Linear Range Analysis (LRA) (guidelines pg. E-14, Form XII)**

1. Was a linear range verification standard analyzed?  
yes X no

2. Were the results within  $\pm 5\%$  of the true value?  
yes no

### Holding Times -

Limits: Metals - 6 months; Hg - 30 days; Cn - 28 days.

1. Verified date of sample receipt by laboratory 7-21-89
2. Date of preparation/analyses 8-3-89
3. Were holding times met? yes X                      no

Analyte	Matrix	Date Sampled	Prep Date	Holding Time	Holding Time Limit/Met
Mercury	Low Water	7-18-89	8-3-89	16 days	30 days    yes

Keystone 12334-8-5-

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP520

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-WB-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774002

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000007

Keystone 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP521

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-WB-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774005

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

-----  
-----  
-----  
-----



Keystone 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP522

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774006

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000009

Keystone<sup>DCX</sup> 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP523

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774007

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

-----  
-----  
-----  
-----

Keystone<sup>TX</sup> 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP524

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-WB-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774008

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	11.50			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000011

Keystone ~~12334~~-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP525

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774009

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000012

Keystone 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP526

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774010

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-29-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP527

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-WB-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774011

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	8.50			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP528

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774012

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000015

Keystone 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP529

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774013

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:



Keystone 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP530

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774014

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP532

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774015

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

-----  
-----  
-----  
-----

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP533

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774016

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone OC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP534

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774017

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum_				NR
7440-36-0	Antimony_				NR
7440-38-2	Arsenic__				NR
7440-39-3	Barium__				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium__				NR
7440-70-2	Calcium__				NR
7440-47-3	Chromium_				NR
7440-48-4	Cobalt__				NR
7440-50-8	Copper__				NR
7439-89-6	Iron_____				NR
7439-92-1	Lead_____				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury__	0.20	U		CV
7439-02-0	Nickel__				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium_				NR
7440-22-4	Silver__				NR
7440-23-5	Sodium__				NR
7440-28-0	Thallium_				NR
7440-62-2	Vanadium_				NR
7440-66-6	Zinc_____				NR
	Cyanide__				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

-----  
-----  
-----  
-----

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP535

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774018

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP537

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774019

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000022

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP538

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774020

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP539

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-WB-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774021

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000024



Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP540

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHP520

Matrix (soil/water): WATER

Lab Sample ID: 890774022

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000025

REGION VIII SUMMARY OF DATA QUALITY ASSURANCE REVIEW

\*\*\*guideline references are from Contract #787\*\*\*

Case No.: SAS 4725H

TDD No.: F08-8909-08

Site: Richardson Flats

Contractor Laboratory: Silver Valley Labs

Data Reviewer : Annette Sackman

Date of Review: 9-15-89

Sample Matrix: 14 Low Soils

Analysis: Metals plus Mercury

Sample Nos.: 4725H01, 4725H02, 4725H03, 4725H04, 4725H05, 4725H06,  
4725H07, 4725H08, 4725H09, 4725H10, 4725H11, 4725H12,  
4725H13, 4725H14

( ) Data are acceptable for use.

(X) Data are acceptable for use with qualifications noted.

( ) Data are preliminary - pending verification.

( ) Data are unacceptable.

Action required by DPO?

No X Yes The following items require action:

Action required by project officer?

No X Yes

The following are our findings:

All calibration and blank contract compliances were met except that for the last half of the thallium analysis the ICV, ICB, CCV and CCB was not recorded on forms IIA and III.

The CRDL standards were run only at the beginning of the furnace AA analysis and not at the end. No qualifications have been prescribed for this discrepancy so no flags are assigned.

Spike recoveries were low for antimony (52.9%) and thallium (48.7%) and indicate positive values for these elements are biased low and flagged "J", estimated. Undetected values indicate antimony and thallium may or may not be present due to elevated detection limits; therefore, these values are flagged "UJ", estimated. Selenium spike recoveries were very low (-33.1%) and indicate these values are severely biased low. Positive values confirm the presence of the element but are flagged "J" and estimated low. Undetected values do not indicate the nonexistence of the element and are unusable and flagged "R", rejected.

For the MSA analysis for thallium, no raw data was presented for duplicate injections. One of the correlation coefficients was below 0.995 for samples 4725H02, 4725H06, 4725H09 and 4725H11; therefore, thallium values for these samples are flagged "J", estimated. For sample 4725H03, both correlation coefficients were below 0.995; therefore, the thallium value for this sample is unusable and flagged "R", rejected.

For the MSA analysis for selenium, both correlation coefficients were below 0.995 for samples 4725H01, 4725H04, 4725H05 and 4725H08; therefore, values for these samples are unusable and flagged "R", rejected.

The percent difference was high for the serial dilution for cadmium (14.5%); therefore these values are flagged "J", estimated.

Lead was analyzed by ICAP due to high sample concentrations, therefore the CRDL of 5µg/l was not met but is waived under these unusual conditions.

### **Inorganic Data Completeness Checklist**

- X Inorganic analysis data (Form I)
- X Initial calibration and continuing calibration verification (Form IIA)
- X CRDL standard for AA and ICP (Form IIB)
- X Blanks (Form III)
- X ICP interference Check sample (Form IV)
- X Spike sample recovery (Form VA)
- X Post digestion spike sample recovery (Form VB)
- X Duplicates (Form VI)
- X Laboratory control sample (Form VII)
- X Standard addition results (Form VIII)
- X ICP serial dilutions (Form IX)
- X Holding times (Form X)
- X Instrument detection limits-quarterly (Form XI)
- X ICP interelement correction factors-quarterly (Form XII)
- X ICP linear ranges-quarterly (Form XIII)
- X Raw data for interference checks
- X Raw data for calibration standards
- X Raw data for blanks
- X Raw data for CRI and/or CRA
- X Raw data for samples
- X Raw data for duplicates
- X Raw data for spikes
- X Traffic reports

### Contract Compliance

#### **I. Initial and Continuing Calibration Verification (ICV and CCV) (guidelines pg. E-4, Form IIA)**

1. Was instrument calibrated daily and each time it was set up?  
yes X no
2. Were instruments calibrated using 1 blank and several standards?  
yes X no
3. Were calibration verifications within 90-110%?  
yes X no
4. Were continuing calibrations run at 10% frequency?  
yes X no
5. Were the raw data correctly transcribed onto Form IIA?  
yes no X

Comments: For thallium, one-half of the CCV's were not recorded on Forms IIA. All other requirements were met.

#### **II. CRDL Standards for ICP (CRI) and/or AA (CRA) (guidelines pg. E-6, Form IIB)**

1. For ICP analysis, were standards (CRI) @ 2x the CRDL or the IDL (whichever was greater) analyzed at the beginning and the end of each sample run, or at a minimum of twice/8 hour shift, whichever was more frequent?  
yes X no
2. For furnace AA analysis, were standards (CRA) analyzed at the beginning and the end of each sample run, or at a minimum of twice/8 hour shift, whichever was more frequent?  
yes no X
3. Were the CRI and/or CRA standards analyzed after the ICV?  
yes X no
4. Were these data reported on Form IIB?  
yes X no
5. Were the raw data correctly transcribed onto Form IIB?  
yes X no

Comments: No CRA was run at the end of the furnace AA analyses.

III. Blanks (guidelines pg. E-6, Form III)

1. Was the initial calibration blank (ICB) analyzed immediately after the initial calibration verification (ICV)?  
yes X no
2. Was a continuing calibration blank (CCB) analyzed immediately after each continuing calibration verification (CCV)?  
yes X no
3. Was a preparation blank (PB) analyzed at a frequency of at least 1 in 20 samples?  
yes X no NA
4. How many elements were detected above the CRDLs? 0 (if 0, go to question 5)  
  
4a. How many elements were detected in the blanks at greater than one-half the amount detected in any sample?
5. Were raw data correctly transcribed onto Form III?  
yes no X

Comments: Only one-half of the blanks for thallium were recorded on Form III. All other requirements were met.

IV. ICP Interference Checks (ICS) (guidelines pg. E-7, Form IV)

1. Was the ICS analyzed twice per 8 hour shift?  
yes X no
2. Were the ICSs analyzed before and after samples?  
yes X no
3. Was any massive interference detected?  
yes no X
4. Were the ICSs within  $\pm 20\%$  mean value?  
yes X no
5. Were raw data correctly transcribed onto Form IV?  
yes X no

Comments: All requirements met.

**V. Spike Sample Analysis (S) (guideline pg. E-8, Form V)**

1. Were spikes analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were spike recoveries correctly calculated?  
yes X no

$$\% \text{ recovery} = \frac{(\text{SSR} - \text{SR})}{\text{SA}} \times 100$$

SSR = Spiked Sample Result

SR = Sample Result

SA = Spike Added

3. Were spike recoveries within the range of 75-125%?  
yes no X

3a. For recoveries outside this range, were associated data  
flagged "N" by the laboratory on Forms I and V?  
yes X no NA

(an exception if granted where the sample concentration is >4X  
the spike concentration)

4. Were raw data correctly transcribed onto Form V?  
yes X no

\* Refer to page E-9 (SOW 787) for information regarding the amount of  
spike to be added for each analyte and for other information about the  
Spike Sample Analysis.

Comments: For antimony and thallium, recoveries were 52.9% and 48.7%,  
respectively; therefore, positive values are flagged "J", estimated and  
undetected values are flagged "UJ". For selenium, recoveries were  
-33.1%, therefore, positive values are flagged "J", estimated and  
confirm the presence of selenium in the sample and undetected values are  
unusable and flagged "R", rejected.

**VI. Duplicates (D) (guidelines pg. E-11, Form VI)**

1. Were duplicates analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were RPDs correctly calculated?  
yes X no

$$\text{RPD} = \frac{S - D}{(S + D)/2} \times 100$$

S = Sample

D = Duplicate

3a. For sample concentrations >5x the CRDL, were RPDs  $\pm 20\%$ ? (limits of  $\pm 35\%$  apply for soil/sediment/tailings samples)

yes X      no      NA

3b. For sample concentrations >5x the CRDL, did duplicate analysis results fall outside the control window of  $\pm$  the CRDL?

yes      no X      NA

3c. Where the RPDs exceeded the control limits, were the data flagged '\*' on Forms I and VI by the laboratory?

yes      no      NA X

4. Were raw data correctly transcribed onto Form VI?

yes X      no

\* Other Considerations:

- Field blanks cannot be used for duplicate analyses
- Duplicates must be analyzed for each analytical method

Comments: All requirements met.

VII. Laboratory Control Sample (LCS) Analysis (guideline pg. E-12, Form VII)

1. Was an LCS analyzed for every sample delivery group or batch of samples, whichever was more frequent?

yes X      no

2. Were recoveries within the 80-120% limit?

yes X      no

-if the recoveries were outside this range the analysis must be terminated, the problem corrected and the previous samples associated with that LCS redigested and reanalyzed.

3. Were the raw data correctly transcribed onto Form VII?

yes X      no

Comments: All requirements met.



**VIII. Furnace Atomic Absorption (AA) QC Analysis (guidelines pg. E-14, Form VIII)**

1. Does the raw data package contain absorbance values for two injections per sample, the average values and the relative standard deviation (RSD)?  
yes                      no X
2. For analyte concentrations > the CRDL, did the RSD for the duplicate injections agree within 20%? (if yes, go to question 3)  
yes                      no X

$$RSD = \frac{SD}{M} \times 100$$

SD = Standard Deviation of Duplicate Injections  
M = Mean of Duplicate Injections

- 2a. Were samples that exceeded the 20% criteria reanalyzed?  
yes X                      no
- 2b. Did any reanalyzed samples exceed the 20% criteria?  
yes X                      no
- 2c. If yes, did the laboratory flag the data of Form I with an 'M'?  
yes X                      no
3. Was the recovery of the spike > 40%? (if yes, go to question 4).  
yes                      no X
- If no, was the sample diluted and rerun with another spike?  
yes X                      no
4. Was sample absorbance > 50% of spike absorbance?\* (if yes, go to question 5).  
yes                      no X

\* Spike absorbance = absorbance of spiked sample - absorbance of sample.

- 4a. For spike recoveries between 85 and 115%, were results reported to the IDL?

yes X          no

$$RPD = \frac{(SSR - SR)}{SA} \times 100$$

SSR = Spike Sample Recovery

SR = Sample Result

SA = Spike Added

- 4b. For spike recoveries outside the 85 and 115% range, were results reported to the IDL and flagged with 'W'?

yes X          no

5. Was spike recovery between 85 and 115%? (if no, go to question 6)

- 5a. Were results quantified from calibration curve and reported to IDL?

yes          no X

6. Was an MSA at 50, 100 and 150% of the sample absorbance analyzed?

yes X          no

- 6a. Was each MSA analysis identified in the raw data along with the slope, intercept and correlation coefficient?

yes X          no

- 6b. Were these data correctly transcribed onto Form VIII?

yes X          no

- 6c. Were correlation coefficients(r) > 0.995?

yes          no X

- 6d. If no, were MSAs run once more?

yes X          no

- If the correlation coefficients were still > 0.995, data on Form I must be from the run with the best 'r' and the data on Forms I and VII must be flagged with a '+'.  
Were these criteria met?

yes X          no

6e. Were all MSA obtained data marked with an 'S' or an S+ on form I?

yes X      no

Comments: There was no raw data for duplicate injections for the thallium analysis. For the duplicate sample in the selenium analysis, the duplicate injections and the third injection was greater than 20%D. No flag was assigned since this was a QA sample. The thallium values for the following samples had on correlation coefficient <0.995 and are flagged "J", estimated: 4725H02, 4725H06, 4725H09 and 4725H11. The thallium and selenium values for the following samples had both correlation coefficients <0.995 and are flagged "R", rejected: thallium - 4725H03, selenium - 4725H01, 4725H04, 4725H05 and 4725H08.

IX. ICP Serial Dilution (L) Analysis (guidelines pg. E-12, Form IX)

1. Was an ICP serial dilution performed on each group of samples of a similar matrix (i.e., soil, water) and concentration (i.e., low, high) or for each sample delivery group, whichever was more frequent?

yes X      no

2. For elements with concentrations >10X the CRDL, did any exceed the serial dilution results by more than 10%? (if no, skip questions 3 and 4)

yes X      no

$$\% \text{ difference} = \frac{I - S}{I} \times 100$$

I = Initial Sample Result

S = Serial Dilution Result (instrument reading X5)

3. Which elements had concentrations that exceeded the 10% criteria? Cadmium
4. Did the laboratory flag these data with an 'E' on Form IX?  
yes X      no
5. Were the raw data correctly transcribed onto Form IX?  
yes X      no

Comments: Cadmium values are flagged "J", estimated due to high %D (14.5%).

**X. Instrument Detection Limits (IDL) (guidelines pg. E-13, Form XI)**

1. Were IDLs reported for each analyzed element?  
yes X                      no
2. Were IDLs reported for each instrument used?  
yes X                      no
3. Did the IDLs meet the contract requirements? (refer to pg. E-13, SOW 787)  
yes                      no X

Comments: Lead was analyzed by ICAP due to high sample concentration.  
No action is taken due to these conditions.

**XI. Interelement Corrections for ICP (guidelines pg. E-13, Form XII)**

1. Were correction factors reported on Form XII?  
yes X                      no

Comments: All requirements met.

**XII. Linear Range Analysis (LRA) (guidelines pg. E-14, Form XII)**

1. Was a linear range verification standard analyzed?  
yes X                      no
2. Was the results within  $\pm 5\%$  of the true value?  
yes                      no

### Holding Times

Limits: Metals - 6 months; Hg - 30 days; Cn - 28 days.

1. Verified date of sample receipt by laboratory 7-24-89
2. Date of preparation/analyses 8-10-89
3. Were holding times met? yes X            no

Analyte	Matrix	Date Sampled	Prep Date	Holding Time	Holding Time Limit/Met
Mercury	Low soil	7-18-89	8-10-89	23 days	30 days    Yes
Metals	Low soil	7-18-89	8-10-89	23 days	6 months    Yes

1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.:

4725H01

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725H01Matrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 69.6Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	18400.			P
7440-36-0	Antimony	19.8		N	P
7440-38-2	Arsenic	83.2			P
7440-39-3	Barium	270.		E	P
7440-41-7	Beryllium	1.7			P
7440-43-9	Cadmium	14.6			P
7440-70-2	Calcium	15000.			P
7440-47-3	Chromium	21.9			P
7440-48-4	Cobalt	11.4	B		P
7440-50-8	Copper	239.			P
7439-89-6	Iron	30800.			P
7439-92-1	Lead	1790.			P
7439-95-4	Magnesium	6130.			P
7439-96-5	Manganese	1260.			P
7439-97-6	Mercury	1.0			CV
7440-02-0	Nickel	23.5			P
7440-09-7	Potassium	3160.			P
7782-49-2	Selenium	3.1		+N	F
7440-22-4	Silver	9.7			P
7440-23-5	Sodium	239.	B		P
7440-28-0	Thallium	.81	B	N	F
7440-62-2	Vanadium	48.7			P
7440-66-6	Zinc	2770			P
	Cyanide				NR

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.:

4725H02

Lab Name: SILVER VALLEY LABS., INC.

Contract: 68-W8-0074

Lab Code: SILVER

Case No.:

SAS No.: 4725H SDG No.: 4725H

Matrix (soil/water): SOIL

Lab Sample ID:

Level (low/med):

LOW

Date Received: 07/24/89

% Solids:

73.0

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	8620.			P
7440-36-0	Antimony	201.		N	P
7440-38-2	Arsenic	590.			P
7440-39-3	Barium	147		E	P
7440-41-7	Beryllium	.86	B		P
7440-43-9	Cadmium	91.4			P
7440-70-2	Calcium	25600			P
7440-47-3	Chromium	.77	U		P
7440-48-4	Cobalt	43.5			P
7440-50-8	Copper	753			P
7439-89-6	Iron	181000			P
7439-92-1	Lead	14200			P
7439-95-4	Magnesium	9430			P
7439-96-5	Manganese	1730			P
7439-97-6	Mercury	4.9			CV
7440-02-0	Nickel	21.5			P
7440-09-7	Potassium	1160.	B		P
7782-49-2	Selenium	46.2		* N	E
7440-22-4	Silver	47.5			P
7440-23-5	Sodium	181	B		P
7440-28-0	Thallium	3.6	B	SN	E
7440-62-2	Vanadium	19.0			P
7440-66-6	Zinc	15500.			P
	Cyanide				NR

JAS

JAS

mab  
08/22/89 JAS

JAS

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUM

Color After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

4725H03

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725Matrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 77.9Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	7650			P
7440-36-0	Antimony	114.		N	P
7440-38-2	Arsenic	427			P
7440-39-3	Barium	130.		E	P
7440-41-7	Beryllium	.81	B		P
7440-43-9	Cadmium	82.0			P
7440-70-2	Calcium	2610			P
7440-47-3	Chromium	1.0	A		P
7440-48-4	Cobalt	38.5			P
7440-50-8	Copper	459			P
7439-89-6	Iron	148000			P
7439-92-1	Lead	9880			P
7439-95-4	Magnesium	8480			P
7439-96-5	Manganese	1630.			P
7439-97-6	Mercury	6.0			CV
7440-02-0	Nickel	28.8			P
7440-09-7	Potassium	1150	A		P
7782-49-2	Selenium	42.7		N	E
7440-22-4	Silver	30.3			P
7440-23-5	Sodium	173	B		P
7440-28-0	Thallium	4.1		+N	E
7440-62-2	Vanadium	21.2			P
7440-66-6	Zinc	15100			P
	Cyanide				NR

JAS

JAS

mg/kg JAS  
08/22/89

JAS RAS

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:



1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO:

4725H04

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725HMatrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89

% Solids: \_\_\_\_\_

52.3Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	25100.			P
7440-36-0	Antimony	200.		N	P
7440-38-2	Arsenic	776.			P
7440-39-3	Barium	1220		E	P
7440-41-7	Beryllium	1.9	B		P
7440-43-9	Cadmium	100.			P
7440-70-2	Calcium	82100			P
7440-47-3	Chromium	33.2			P
7440-48-4	Cobalt	10.1	B		P
7440-50-8	Copper	840.			P
7439-89-6	Iron	58600.			P
7439-92-1	Lead	13600			P
7439-95-4	Magnesium	33800			P
7439-96-5	Manganese	2770.			P
7439-97-6	Mercury	5.5			CV
7440-02-0	Nickel	27.0			P
7440-09-7	Potassium	6270			P
7782-49-2	Selenium	15.4		+N	F
7440-22-4	Silver	86.0			P
7440-23-5	Sodium	447	B		P
7440-28-0	Thallium	23.2		N	F
7440-62-2	Vanadium	46.5			P
7440-66-6	Zinc	15700.			P
	Cyanide				NR

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments: \_\_\_\_\_

1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

4725H05

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725HMatrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 78.3Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	2810			P
7440-36-0	Antimony	178		N	P
7440-38-2	Arsenic	320			P
7440-39-3	Barium	134		E	P
7440-41-7	Beryllium	.47	B		P
7440-43-9	Cadmium	149			P
7440-70-2	Calcium	89700			P
7440-47-3	Chromium	10.9			P
7440-48-4	Cobalt	5.3	B		P
7440-50-8	Copper	613			P
7439-89-6	Iron	44800			P
7439-92-1	Lead	9550			P
7439-95-4	Magnesium	19700			P
7439-96-5	Manganese	3090			P
7439-97-6	Mercury	1.5			CV
7440-02-0	Nickel	2.9	B		P
7440-09-7	Potassium	774	B		P
7782-49-2	Selenium	16.1		+ N	F
7440-22-4	Silver	60.9			P
7440-23-5	Sodium	84.6	B		P
7440-28-0	Thallium	12.7		S N	F
7440-62-2	Vanadium	5.6	B		P
7440-66-6	Zinc	26400			P
	Cyanide				NR

JAS

JAS

JAS RAS

JAS

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

4725H06

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725HCMatrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 78.6Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	11100.			P
7440-36-0	Antimony	40.8		N	P
7440-38-2	Arsenic	261			P
7440-39-3	Barium	944		E	P
7440-41-7	Beryllium	.85	B		P
7440-43-9	Cadmium	62.3			P
7440-70-2	Calcium	46900.			P
7440-47-3	Chromium	.71	U		P
7440-48-4	Cobalt	64.4			P
7440-50-8	Copper	256			P
7439-89-6	Iron	4400.			P
7439-92-1	Lead	3790			P
7439-95-4	Magnesium	13500.			P
7439-96-5	Manganese	207000			P
7439-97-6	Mercury	8.24			CV
7440-02-0	Nickel	69.7			P
7440-09-7	Potassium	1870			P
7782-49-2	Selenium	5.6		V	F
7440-22-4	Silver	13.7			P
7440-23-5	Sodium	344.	B		P
7440-28-0	Thallium	8.5		SN	F
7440-62-2	Vanadium	34.8			P
7440-66-6	Zinc	18800.			P
	Cyanide				NR

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

4725H07

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725HMatrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 66.8Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	9710			P
7440-36-0	Antimony	37.6		N	P
7440-38-2	Arsenic	198			P
7440-39-3	Barium	384		E	P
7440-41-7	Beryllium	1.1	B		P
7440-43-9	Cadmium	102.			P
7440-70-2	Calcium	90700			P
7440-47-3	Chromium	9.9			P
7440-48-4	Cobalt	20.4			P
7440-50-8	Copper	264.			P
7439-89-6	Iron	64900.			P
7439-92-1	Lead	3250			P
7439-95-4	Magnesium	20700			P
7439-96-5	Manganese	19100.			P
7439-97-6	Mercury	1.82			CV
7440-02-0	Nickel	14.0			P
7440-09-7	Potassium	1880			P
7782-49-2	Selenium	9.2		N	F
7440-22-4	Silver	23.9			P
7440-23-5	Sodium	254	B		P
7440-28-0	Thallium	10.1		SV	F
7440-62-2	Vanadium	20.5			P
7440-66-6	Zinc	17600.			P
	Cyanide				NR

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

4725H08

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725HCMatrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 64.6Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	14000			P
7440-36-0	Antimony	80.5		N	P
7440-38-2	Arsenic	348.			P
7440-39-3	Barium	286		E	P
7440-41-7	Beryllium	1.5	0		P
7440-43-9	Cadmium	82.3			P
7440-70-2	Calcium	85800			P
7440-47-3	Chromium	16.5			P
7440-48-4	Cobalt	33.3			P
7440-50-8	Copper	567			P
7439-89-6	Iron	49200			P
7439-92-1	Lead	3510			P
7439-95-4	Magnesium	18400			P
7439-96-5	Manganese	14300			P
7439-97-6	Mercury	1.1			CV
7440-02-0	Nickel	25.8			P
7440-09-7	Potassium	2400			P
7782-49-2	Selenium	13.2		+N	E
7440-22-4	Silver	36.9			P
7440-23-5	Sodium	276	0		P
7440-28-0	Thallium	14.2		SN	E
7440-62-2	Vanadium	26.9	0		P
7440-66-6	Zinc	18300			P
	Cyanide				NK

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

4725H09

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725HMatrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 72.6Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	10900			P
7440-36-0	Antimony	107		N	P
7440-38-2	Arsenic	295			P
7440-39-3	Barium	229		E	P
7440-41-7	Beryllium	1.4	A		P
7440-43-9	Cadmium	90.2			P
7440-70-2	Calcium	38700			P
7440-47-3	Chromium	16.3			P
7440-48-4	Cobalt	20.1			P
7440-50-8	Copper	498			P
7439-89-6	Iron	68700			P
7439-92-1	Lead	6970			P
7439-95-4	Magnesium	1100.			P
7439-96-5	Manganese	3070			P
7439-97-6	Mercury	5.0			CV
7440-02-0	Nickel	16.3			P
7440-09-7	Potassium	1590			P
7782-49-2	Selenium	21.9		SN	F
7440-22-4	Silver	36.2			P
7440-23-5	Sodium	220	B		P
7440-28-0	Thallium	4.1		SN	F
7440-62-2	Vanadium	31.2			P
7440-66-6	Zinc	15900.			P
	Cyanide				NR

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.:

4725 H10

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-0074Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725HSDG No.: 4725HMatrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89Solids: 79.0Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	20200.			P
7440-36-0	Antimony	10.1	U	N	P
7440-38-2	Arsenic	54 70.6	U	S	E
7440-39-3	Barium	408		E	P
7440-41-7	Beryllium	1.6			P
7440-43-9	Cadmium	2.2			P
7440-70-2	Calcium	9640			P
7440-47-3	Chromium	18.5			P
7440-48-4	Cobalt	10.9	B		P
7440-50-8	Copper	40.7			P
7439-89-6	Iron	25500.			P
7439-92-1	Lead	108			P
7439-95-4	Magnesium	6340			P
7439-96-5	Manganese	303			P
7439-97-6	Mercury	10	B		CV
7440-02-0	Nickel	17.0			P
7440-09-7	Potassium	6050			P
7782-49-2	Selenium	5.6	U	N	E
7440-22-4	Silver	.41	U		P
7440-23-5	Sodium	389	B		P
7440-28-0	Thallium	123	U	N	E
7440-62-2	Vanadium	37.7			P
7440-66-6	Zinc	202.			P
	Cyanide				NR

4725H  
8-2387

JAS

R AS

4725H

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments: \_\_\_\_\_

1-  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-00744725H11Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725HSDG No.: 4725H10Matrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 07/24/89% Solids: 37.2Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	<u>19500.</u>			P
7440-36-0	Antimony	<u>142.</u>		N	P
7440-38-2	Arsenic	<u>251.</u>			P
7440-39-3	Barium	<u>1068</u>		E	P
7440-41-7	Beryllium	<u>2.3</u>	B		P
7440-43-9	Cadmium	<u>185</u>			P
7440-70-2	Calcium	<u>249000</u>			P
7440-47-3	Chromium	<u>18.2</u>			P
7440-48-4	Cobalt	<u>5.9</u>	B		P
7440-50-8	Copper	<u>770</u>			P
7439-89-6	Iron	<u>156000</u>			P
7439-92-1	Lead	<u>12500</u>			P
7439-95-4	Magnesium	<u>29700</u>			P
7439-96-5	Manganese	<u>19600</u>			P
7439-97-6	Mercury	<u>1.9</u>			CU
7440-02-0	Nickel	<u>32.1</u>			P
7440-09-7	Potassium	<u>4790</u>			P
7782-49-2	Selenium	<u>19.9</u>		N	F
7440-22-4	Silver	<u>60.6</u>			P
7440-23-5	Sodium	<u>764</u>	A		P
7440-28-0	Thallium	<u>24.1</u>		SN	F
7440-62-2	Vanadium	<u>38.0</u>			P
7440-66-6	Zinc	<u>24000</u>			P
	Cyanide				NR

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:



1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: SILVER VALLEY LABS., INC.Contract: 68-W8-00744725H12Lab Code: SILVER

Case No.: \_\_\_\_\_

SAS No.: 4725H SDG No.: 4725H0Matrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOWDate Received: 01/24/89Solids: 53.6Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	<u>6880</u>			P
7440-36-0	Antimony	<u>49.3</u>		N	P
7440-38-2	Arsenic	<u>839</u>			P
7440-39-3	Barium	<u>557</u>		E	P
7440-41-7	Beryllium	<u>1.6</u>	0		P
7440-43-9	Cadmium	<u>131</u>			P
7440-70-2	Calcium	<u>167000</u>			P
7440-47-3	Chromium	<u>1.0</u>	U		P
7440-48-4	Cobalt	<u>53.3</u>			P
7440-50-8	Copper	<u>456</u>			P
7439-89-6	Iron	<u>132000</u>			P
7439-92-1	Lead	<u>6900</u>			P
7439-95-4	Magnesium	<u>23400</u>			P
7439-96-5	Manganese	<u>23700</u>			P
7439-97-6	Mercury	<u>.73</u>			CV
7440-02-0	Nickel	<u>26.3</u>			P
7440-09-7	Potassium	<u>1690.</u>			P
7782-49-2	Selenium	<u>2.5</u>		SN	F
7440-22-4	Silver	<u>22.5</u>			P
7440-23-5	Sodium	<u>206</u>	0		P
7440-28-0	Thallium	<u>21.0</u>		SN	F
7440-62-2	Vanadium	<u>18.6</u>	0		P
7440-66-6	Zinc	<u>20000.</u>			P
	Cyanide				NR

JAS

JAS

JAS

JAS

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUMColor After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

1-  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.:

4725H13

Lab Name: SILVER VALLEY LABS., INC.

Contract: 68-W8-0074

Lab Code: SILVER

Case No.:

SAS No.: 4725H

SDG No.: 4725H

Matrix (soil/water): SOIL

Lab Sample ID:

Level (low/med): LOW

Date Received: 07/24/89

% Solids: 73.2

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	15200			P
7440-36-0	Antimony	53.9	N		P JAS
7440-38-2	Arsenic	211			P
7440-39-3	Barium	209	E		P
7440-41-7	Beryllium	1.4	B		P
7440-43-9	Cadmium	43.9			P JAS
7440-70-2	Calcium	14500			P
7440-47-3	Chromium	11.8			P
7440-48-4	Cobalt	24.6			P
7440-50-8	Copper	231			P
7439-89-6	Iron	86100			P
7439-92-1	Lead	4430			P
7439-95-4	Magnesium	6340			P
7439-96-5	Manganese	1560			P
7439-97-6	Mercury	3.3			CV
7440-02-0	Nickel	22.4			P
7440-09-7	Potassium	2490			P
7782-49-2	Selenium	25.1	N		F JAS
7440-22-4	Silver	15.5			P
7440-23-5	Sodium	215	B		P
7440-28-0	Thallium	1.2	B	N	F JAS
7440-62-2	Vanadium	40.5			P
7440-66-6	Zinc	3580			P
	Cyanide				NR

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: YELLOW

Clarity After:

Artifacts:

Comments:

1.  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.:

4725H14

Lab Name: SILVER VALLEY LABS., INC.

Contract: 68-W8-0074

Lab Code: SILVER

Case No.: 47251 SAS No.: 4725H SDG No.: 4725H

Matrix (soil/water): SOIL

Lab Sample ID: \_\_\_\_\_

Level (low/med): LOW

Date Received: 07/24/89

Solids: 77.9 77.4

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	4440			P
7440-36-0	Antimony	183		N	P
7440-38-2	Arsenic	555			P
7440-39-3	Barium	66.0		E	P
7440-41-7	Beryllium	.63	B		P
7440-43-9	Cadmium	113			P
7440-70-2	Calcium	18900			P
7440-47-3	Chromium	.72	U		P
7440-48-4	Cobalt	76.8			P
7440-50-8	Copper	496.			P
7439-89-6	Iron	263000			P
7439-92-1	Lead	12200.			P
7439-95-4	Magnesium	5880.			P
7439-96-5	Manganese	1370			P
7439-97-6	Mercury	.81			CV
7440-02-0	Nickel	31.4			P
7440-09-7	Potassium	657	B		P
7782-49-2	Selenium	84.0		N	F
7440-22-4	Silver	39.8			P
7440-23-5	Sodium	105	B		P
7440-28-0	Thallium	6.0		SN	F
7440-62-2	Vanadium	10.4	B		P
7440-66-6	Zinc	17500			P
	Cyanide				NR

Color Before: BROWN

Clarity Before: \_\_\_\_\_

Texture: MEDIUM

Color After: YELLOW

Clarity After: \_\_\_\_\_

Artifacts: \_\_\_\_\_

Comments:

REGION VIII SUMMARY OF DATA QUALITY ASSURANCE REVIEW

\*\*\*guideline references are from Contract #787\*\*\*

Case No.: 12334

TDD No.: F08-8909-08

Site: Richardson Flats

Contractor Laboratory: Keystone-Houston

Data Reviewer : Annette Sackman

Date of Review: 10-3-89

Sample Matrix: 5 Low Soils, 15 Low Waters

Analysis: Mercury

Sample Nos.: MHL955, MHL956, MHP500, MHP501, MHP502, MHP503, MHP504,  
MHP506, MHP507, MHP509, MHP510, MHP511, MHP512, MHP513,  
MHP514, MHP515, MHP516, MHP517, MHP518, MHP519

☒ (X) Data are acceptable for use.

☐ ( ) Data are acceptable for use with qualifications noted.

☐ ( ) Data are preliminary - pending verification.

☐ ( ) Data are unacceptable.

Action required by DPO?

No X Yes      The following items require action:

Action required by project officer?

No X Yes

The following are our findings:

All requirements were met for the mercury analysis. No flags were assigned.

### **Inorganic Data Completeness Checklist**

- X Inorganic analysis data (Form I)
- X Initial calibration and continuing calibration verification (Form IIA)  
CRDL standard for AA and ICP (Form IIB)
- X Blanks (Form III)  
ICP interference Check sample (Form IV)
- X Spike sample recovery (Form VA)  
Post digestion spike sample recovery (Form VB)
- X Duplicates (Form VI)
- X Laboratory control sample (Form VII)  
Standard addition results (Form VIII)  
ICP serial dilutions (Form IX)
- X Holding times (Form X)
- X Instrument detection limits-quarterly (Form XI)
- X ICP interelement correction factors-quarterly (Form II)
- X ICP linear ranges-quarterly (Form XIII)  
Raw data for interference checks
- X Raw data for calibration standards
- X Raw data for blanks  
Raw data for CRI and/or CRA
- X Raw data for samples
- X Raw data for duplicates
- X Raw data for spikes
- X Traffic reports

### Contract Compliance

#### **I. Initial and Continuing Calibration Verification (ICV and CCV) (guidelines pg. E-4, Form IIA)**

1. Was instrument calibrated daily and each time it was set up?  
yes X                      no
2. Were instruments calibrated using 1 blank and several standards?  
yes X                      no
3. Were calibration verifications within 90-110%?  
yes X                      no
4. Were continuing calibrations run at 10% frequency?  
yes X                      no
5. Were the raw data correctly transcribed onto Form IIA?  
yes X                      no

Comments: All requirements met.

#### **II. CRDL Standards for ICP (CRI) and/or AA (CRA) (guidelines pg. E-6, Form IIB)**

1. For ICP analysis, were standards (CRI) @ 2x the CRDL or the IDL  
(whichever was greater) analyzed at the beginning and the end of  
each sample run, or at a minimum of twice/8 hour shift,  
whichever was more frequent?  
yes                      no
2. For furnace AA analysis, were standards (CRA) analyzed at the  
beginning and the end of each sample run, or at a minimum of  
twice/8 hour shift, whichever was more frequent?  
yes                      no
3. Were the CRI and/or CRA standards analyzed after the ICV?  
yes                      no
4. Were these data reported on Form IIB?  
yes                      no
5. Were the raw data correctly transcribed onto Form IIB?  
yes                      no

Comments: Not required.

**III. Blanks (guidelines pg. E-6, Form-III)**

1. Was the initial calibration blank (ICB) analyzed immediately after the initial calibration verification (ICV)?  
yes X no
2. Was a continuing calibration blank (CCB) analyzed immediately after each continuing calibration verification (CCV)?  
yes X no
3. Was a preparation blank (PB) analyzed at a frequency of at least 1 in 20 samples?  
yes X no NA
4. How many elements were detected above the CRDLs? 0 (if 0, go to question 5)  
  
4a. How many elements were detected in the blanks at greater than one-half the amount detected in any sample?
5. Were raw data correctly transcribed onto Form III?  
yes X no

Comments: All requirements met.

**IV. ICP Interference Checks (ICS) (guidelines pg. E-7, Form IV)**

1. Was the ICS analyzed twice per 8 hour shift?  
yes no
2. Were the ICSs analyzed before and after samples?  
yes no
3. Was any massive interference detected?  
yes no
4. Were the ICSs within  $\pm 20\%$  mean value?  
yes no
5. Were raw data correctly transcribed onto Form IV?

Comments: Not required.



V. Spike Sample Analysis (S) (guideline pg. E-8, Form V)

1. Were spikes analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were spike recoveries correctly calculated?  
yes X no

$$\% \text{ recovery} = \frac{(\text{SSR} - \text{SR})}{\text{SA}} \times 100$$

SSR = Spiked Sample Result

SR = Sample Result

SA = Spike Added

3. Were spike recoveries within the range of 75-125%?  
yes X no

3a. For recoveries outside this range, were associated data  
flagged "N" by the laboratory on Forms I and V?  
yes no NA X

(an exception if granted where the sample concentration is >4X  
the spike concentration)

4. Were raw data correctly transcribed onto Form V?  
yes X no

\* Refer to page E-9 (SOW 787) for information regarding the amount of  
spike to be added for each analyte and for other information about the  
Spike Sample Analysis.

Comments: All requirements met.

VI. Duplicates (D) (guidelines pg. E-11, Form VI)

1. Were duplicates analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were RPDs correctly calculated?  
yes X no

$$\text{RPD} = \frac{S - D}{(S + D)/2} \times 100$$

S = Sample

D = Duplicate

3a. For sample concentrations >5x the CRDL, were RPDs  $\pm 20\%$ ? (limits of  $\pm 35\%$  apply for soil/sediment/tailings samples)  
yes X no NA

3b. For sample concentrations >5x the CRDL, did duplicate analysis results fall outside the control window of  $\pm$  the CRDL?  
yes no X NA

3c. Where the RPDs exceeded the control limits, were the data flagged '\*' on Forms I and VI by the laboratory?  
yes no NA

4. Were raw data correctly transcribed onto Form VI?  
yes X no

\* Other Considerations:

- Field blanks cannot be used for duplicate analyses
- Duplicates must be analyzed for each analytical method

Comments: All requirements met.

VII. Laboratory Control Sample (LCS) Analysis (guideline pg. E-12, Form VII)

1. Was an LCS analyzed for every sample delivery group or batch of samples, whichever was more frequent?  
yes X no

2. Were recoveries within the 80-120% limit?  
yes X no

-if the recoveries were outside this range the analysis must be terminated, the problem corrected and the previous samples associated with that LCS redigested and reanalyzed.

3. Were the raw data correctly transcribed onto Form VII?  
yes X no

Comments: All requirements met.

**VIII. Furnace-Atomic Absorption (AA) QC Analysis (guidelines pg. E-14, Form-VIII)**

1. Does the raw data package contain absorbance values for two injections per sample, the average values and the relative standard deviation (RSD)?  
yes                      no
2. For analyte concentrations > the CRDL, did the RSD for the duplicate injections agree within 20%? (if yes, go to question 3)  
yes                      no

$$RSD = \frac{SD}{M} \times 100$$

SD = Standard Deviation of Duplicate Injections  
M = Mean of Duplicate Injections

- 2a. Were samples that exceeded the 20% criteria reanalyzed?  
yes                      no
- 2b. Did any reanalyzed samples exceed the 20% criteria?  
yes                      no
- 2c. If yes, did the laboratory flag the data of Form I with an 'M'?  
yes                      no
3. Was the recovery of the spike > 40%? (if yes, go to question 4).  
yes                      no
- If no, was the sample diluted and rerun with another spike?  
yes                      no
4. Was sample absorbance 50% of spike absorbance?\* (if yes, go to question 5).  
yes                      no

\* Spike absorbance = absorbance of spiked sample - absorbance of sample.

- 4a. For spike recoveries between 85 and 115%, were results reported to the IDL?

yes                      no

$$RPD = \frac{(SSR - SR)}{SA} \times 100$$

SSR = Spike Sample Recovery

SR = Sample Result

SA = Spike Added

- 4b. For spike recoveries outside the 85 and 115% range, were results reported to the IDL and flagged with 'W'?

yes                      no

5. Was spike recovery between 85 and 115%? (if no, go to question 6)

- 5a. Were results quantified from calibration curve and reported to IDL?

yes                      no

6. Was an MSA at 50, 100 and 150% of the sample absorbance analyzed?

yes                      no

- 6a. Was each MSA analysis identified in the raw data along with the slope, intercept and correlation coefficient?

yes                      no

- 6b. Were these data correctly transcribed onto Form VIII?

yes                      no

- 6c. Were correlation coefficients(r) > 0.995?

yes                      no

- 6d. If no, were MSAs run once more?

yes                      no

- If the correlation coefficients were still > 0.995, data on Form I must be from the run with the best 'r' and the data on Forms I and VII must be flagged with a '+'.  
Were these criteria met?

yes                      no

6e. Were all MSA obtained data marked with an 'S' or an S+ on form I?

yes                      no

Comments: Not required.

**IX. ICP Serial Dilution (L) Analysis (guidelines pg. E-12, Form IX)**

1. Was an ICP serial dilution performed on each group of samples of a similar matrix (i.e., soil, water) and concentration (i.e., low, high) or for each sample delivery group, whichever was more frequent?

yes                      no

2. For elements with concentrations >10X the CRDL, did any exceed the serial dilution results by more than 10%? (if no, skip questions 3 and 4)

yes                      no

$$\% \text{ difference} = \frac{I - S}{I} \times 100$$

I = Initial Sample Result

S = Serial Dilution Result (instrument reading X5)

3. Which elements had concentrations that exceeded the 10% criteria?
4. Did the laboratory flag these data with an 'E' on Form IX?
- yes                      no
5. Were the raw data correctly transcribed onto Form IX?
- yes                      no

Comments: Not required.

**X. Instrument Detection Limits (IDL) (guidelines pg. E-13, Form XI)**

1. Were IDLs reported for each analyzed element?  
yes X no
2. Were IDLs reported for each instrument used?  
yes X no
3. Did the IDLs meet the contract requirements? (refer to pg. E-13, SOW 787)  
yes X no

Comments: All requirements met.

**XI. Interelement Corrections for ICP (guidelines pg. E-13, Form XII)**

1. Were correction factors reported on Form XII?  
yes X no

Comments: All requirements met.

**XII. Linear Range Analysis (LRA) (guidelines pg. E-14, Form XII)**

1. Was a linear range verification standard analyzed?  
yes X no
2. Was the results within  $\pm 5\%$  of the true value?  
yes no

### Holding Times:

Limits: Metals - 6 months; Hg - 30 days; Cn - 28 days.

1. Verified date of sample receipt by laboratory 7-21-89
2. Date of preparation/analyses 8-3-89
3. Were holding times met? yes X no

Analyte	Matrix	Date Sampled	Prep Date	Holding Time	Holding Time Limit/Met
Mercury	Low soil	7-18-89	8-3-89	13 days	30 days yes
Mercury	Low Water	7-18-89	8-3-89	13 days	30 days yes

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHL955

Lab-Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID: 890773003

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 98.3

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.99			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-23-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000007



Keystone OC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHL956

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID: 890773006

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 97.9

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	1.30			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP500

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID: 890773007

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 98.6

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-38-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.88			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP501

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-WB-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID: 890773008

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 82.4

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	8.20			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone OC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP502

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID: 890773009

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 92.0

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	7.60			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP503

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773010

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP504

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-WB-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773011

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000013

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP506

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-WB-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773012

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP507

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773013

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum_				NR
7440-36-0	Antimony_				NR
7440-38-2	Arsenic__				NR
7440-39-3	Barium__				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium__				NR
7440-70-2	Calcium__				NR
7440-47-3	Chromium_				NR
7440-48-4	Cobalt___				NR
7440-50-8	Copper___				NR
7439-89-6	Iron_____				NR
7439-92-1	Lead_____				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury__	0.20	U		CV
7439-02-0	Nickel___				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium_				NR
7440-22-4	Silver___				NR
7440-23-5	Sodium___				NR
7440-28-0	Thallium_				NR
7440-62-2	Vanadium_				NR
7440-66-6	Zinc_____				NR
	Cyanide__				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

000015



Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP509

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773014

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

-----  
-----  
-----  
-----

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP510

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER Lab Sample ID: 890773015

Level (low/med): LOW Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone OC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP511

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773016

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP512

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-WB-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773017

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP513

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-WB-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773020

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

MHP514

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773021

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-29-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP515

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773022

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP516

Lab-Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773023

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	8.00			CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:



Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP517

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773024

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP518

Lab Name: KEYSTONE ENVIRONMENTAL

Contract: 68-W8-0005

Lab Code: KEYTX

Case No.: 12334

SAS No.:

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773025

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum_				NR
7440-36-0	Antimony_				NR
7440-38-2	Arsenic_				NR
7440-39-3	Barium_				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium_				NR
7440-70-2	Calcium_				NR
7440-47-3	Chromium_				NR
7440-48-4	Cobalt_				NR
7440-50-8	Copper_				NR
7439-89-6	Iron_				NR
7439-92-1	Lead_				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury_	0.20	U		CV
7439-02-0	Nickel_				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium_				NR
7440-22-4	Silver_				NR
7440-23-5	Sodium_				NR
7440-28-0	Thallium_				NR
7440-62-2	Vanadium_				NR
7440-66-6	Zinc_				NR
	Cyanide_				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

-----  
-----  
-----  
-----

Keystone DC# 12334-8-5

U.S. EPA - CLP

1  
INORGANIC ANALYSIS DATA SHEET

EPA SAMPLE NO.

MHP519

Lab Name: KEYSTONE ENVIRONMENTAL Contract: 68-W8-0005

Lab Code: KEYTX Case No.: 12334 SAS No.: SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID: 890773026

Level (low/med): LOW

Date Received: 07/21/89

% Solids: 0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum				NR
7440-36-0	Antimony				NR
7440-38-2	Arsenic				NR
7440-39-3	Barium				NR
7440-41-7	Beryllium				NR
7440-43-9	Cadmium				NR
7440-70-2	Calcium				NR
7440-47-3	Chromium				NR
7440-48-4	Cobalt				NR
7440-50-8	Copper				NR
7439-89-6	Iron				NR
7439-92-1	Lead				NR
7439-95-4	Magnesium				NR
7439-96-5	Manganese				NR
7439-97-6	Mercury	0.20	U		CV
7439-02-0	Nickel				NR
7440-09-7	Potassium				NR
7782-49-2	Selenium				NR
7440-22-4	Silver				NR
7440-23-5	Sodium				NR
7440-28-0	Thallium				NR
7440-62-2	Vanadium				NR
7440-66-6	Zinc				NR
	Cyanide				NR

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

-----  
-----  
-----  
-----

REGION VIII SUMMARY OF DATA QUALITY ASSURANCE REVIEW

\*\*\*guideline references are from Contract #787\*\*\*

Case No.: 12334

TDD No.: F08-8909-08

Site: Richardson Flats

Contractor Laboratory: Silver Valley Labs

Data Reviewer : Annette Sackman

Date of Review: 10-3-89

Sample Matrix: 5 Low Soils, 15 Low Waters

Analysis: Metals plus Mercury

Sample Nos.: MHL955, MHL956, MHP500, MHP501, MHP502, MHP503, MHP504,  
MHP506, MHP507, MHP509, MHP510, MHP511, MHP512, MHP513,  
MHP514, MHP515, MHP516, MHP517, MHP518, MHP519

( ) Data are acceptable for use.

(X) Data are acceptable for use with qualifications noted.

( ) Data are preliminary - pending verification.

( ) Data are unacceptable.

Action required by DPO?

No X Yes The following items require action:

Action required by project officer?

No X Yes

The following are our findings:

These samples were originally sent to Keystone-Houston Labs for metal analysis; however, due to contractual problems, Keystone Houston only analyzed for mercury and then sent the samples to Silver Valley Labs for complete metal analysis. This package is the results for the analysis performed by Silver Valley Labs and includes metals plus mercury analysis. Since the samples were first sent to Keystone-Houston Labs, the holding times for the mercury analysis performed by Silver Valley Labs was missed by seven days. Therefore, all mercury values in this package are flagged "J" and considered estimate.

The remaining data is acceptable for use with the following qualifications:

No final CRDL standard was run for the furnace AA analysis. The CRDL value for selenium was transposed on Form IIB and the correct %D is 78.6%; however, no qualifications are required for these discrepancies.

The spike recovery was below 40% for selenium values for water matrix (22.8%); therefore, all associated selenium values are unusable and rejected "R". The thallium spike recovery for soil matrix was low (54.3%); therefore all thallium soil values are flagged "J" and considered biased low.

Duplicate results for lead water values obtained by ICAP were high (37.0%RPD). Since sample MHP516 was the only water sample in which lead was analyzed by ICAP, this lead value is considered estimated and flagged "J".

All MSA criteria were followed except for the following: MSA was required for arsenic for sample MHP517 and thallium for sample MHP516; therefore these values are estimated and flagged "J". One correlation coefficient was <0.995 for the arsenic analysis for sample MHP518; therefore, this value is flagged "J", estimated. Both correlation coefficients were <0.995 for the arsenic analysis for sample MHP504; therefore this value is unusable and flagged "R", rejected.

Serial dilution results for arsenic and zinc soil values were slightly high, 12.1% and 13.3 %, respectively. These soil values are therefore flagged "J", estimated.

The arsenic value for sample MHP516 was analyzed by furnace AA and reported as 46.5 µg/l; however, this number was not multiplied by the dilution factor of 50. The correct arsenic value is actually 2326 µg/l for this sample.

### **Inorganic Data Completeness Checklist**

- X Inorganic analysis data (Form I)
- X Initial calibration and continuing calibration verification (Form IIA)
- X CRDL standard for AA and ICP (Form IIB)
- X Blanks (Form III)
- X ICP interference Check sample (Form IV)
- X Spike sample recovery (Form VA)
- X Post digestion spike sample recovery (Form VB)
- X Duplicates (Form VI)
- X Laboratory control sample (Form VII)
- X Standard addition results (Form VIII)
- X ICP serial dilutions (Form IX)
- X Holding times (Form X)
- X Instrument detection limits-quarterly (Form XI)
- X ICP interelement correction factors-quarterly (Form XII)
- X ICP linear ranges-quarterly (Form XIII)
- X Raw data for interference checks
- X Raw data for calibration standards
- X Raw data for blanks
- X Raw data for CRI and/or CRA
- X Raw data for samples
- X Raw data for duplicates
- X Raw data for spikes
- X Traffic reports

### Contract Compliance

#### **I. Initial and Continuing Calibration Verification (ICV and CCV) (guidelines pg. E-4, Form IIA)**

1. Was instrument calibrated daily and each time it was set up?  
yes X no
2. Were instruments calibrated using 1 blank and several standards?  
yes X no
3. Were calibration verifications within 90-110%?  
yes X no
4. Were continuing calibrations run at 10% frequency?  
yes X no
5. Were the raw data correctly transcribed onto Form IIA?  
yes X no

Comments: All requirements met.

#### **II. CRDL Standards for ICP (CRI) and/or AA (CRA) (guidelines pg. E-6, Form IIB)**

1. For ICP analysis, were standards (CRI) @ 2x the CRDL or the IDL  
(whichever was greater) analyzed at the beginning and the end of  
each sample run, or at a minimum of twice/8 hour shift,  
whichever was more frequent?  
yes X no
2. For furnace AA analysis, were standards (CRA) analyzed at the  
beginning and the end of each sample run, or at a minimum of  
twice/8 hour shift, whichever was more frequent?  
yes no X
3. Were the CRI and/or CRA standards analyzed after the ICV?  
yes X no
4. Were these data reported on Form IIB?  
yes X no
5. Were the raw data correctly transcribed onto Form IIB?  
yes no X

Comments: The CRA was run only at the beginning of the sample runs and not at the end. The selenium CRDL value was transposed on Form IIB and the correct %D is 78.6%. No flags are required for these discrepancies.

**III. Blanks (guidelines pg. E-6, Form III)**

1. Was the initial calibration blank (ICB) analyzed immediately after the initial calibration verification (ICV)?  
yes X no
2. Was a continuing calibration blank (CCB) analyzed immediately after each continuing calibration verification (CCV)?  
yes X no
3. Was a preparation blank (PB) analyzed at a frequency of at least 1 in 20 samples?  
yes X no NA
4. How many elements were detected above the CRDLs? 0 (if 0, go to question 5)  
  
4a. How many elements were detected in the blanks at greater than one-half the amount detected in any sample?
5. Were raw data correctly transcribed onto Form III?  
yes X no

Comments: All requirements met.

**IV. ICP Interference Checks (ICS) (guidelines pg. E-7, Form IV)**

1. Was the ICS analyzed twice per 8 hour shift?  
yes X no
2. Were the ICSs analyzed before and after samples?  
yes X no
3. Was any massive interference detected?  
yes no X
4. Were the ICSs within  $\pm 20\%$  mean value?  
yes X no
5. Were raw data correctly transcribed onto Form IV?

Comments: All requirements met.



**V. Spike Sample Analysis (S) (guideline pg. E-8, Form V)**

1. Were spikes analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were spike recoveries correctly calculated?  
yes X no

$$\% \text{ recovery} = \frac{(\text{SSR} - \text{SR})}{\text{SA}} \times 100$$

SSR = Spiked Sample Result

SR = Sample Result

SA = Spike Added

3. Were spike recoveries within the range of 75-125%?  
yes no X

3a. For recoveries outside this range, were associated data  
flagged "N" by the laboratory on Forms I and V?  
yes X no NA

(an exception if granted where the sample concentration is >4X  
the spike concentration)

4. Were raw data correctly transcribed onto Form V?  
yes X no

\* Refer to page E-9 (SOW 787) for information regarding the amount of  
spike to be added for each analyte and for other information about the  
Spike Sample Analysis.

Comments: Selenium water values are unusable and flagged "R" due to  
spike recoveries below 40% (22.8%). Thallium soil values are estimated  
and flagged "J" due to low spike recoveries (54.3%).

**VI. Duplicates (D) (guidelines pg. E-11, Form VI)**

1. Were duplicates analyzed at a frequency of 1 in 20 samples?  
yes X no

2. Were RPDs correctly calculated?  
yes X no

$$\text{RPD} = \frac{S - D}{(S + D)/2} \times 100$$

S = Sample

D = Duplicate

3a. For sample concentrations >5x the CRDL, were RPDs  $\pm 20\%$ ? (limits of  $\pm 35\%$  apply for soil/sediment/tailings samples)

yes                      no X                      NA

3b. For sample concentrations >5x the CRDL, did duplicate analysis results fall outside the control window of  $\pm$  the CRDL?

yes                      no X                      NA

3c. Where the RPDs exceeded the control limits, were the data flagged '\*' on Forms I and VI by the laboratory?

yes X                      no                      NA

4. Were raw data correctly transcribed onto Form VI?

yes                      no X

\* Other Considerations:

- Field blanks cannot be used for duplicate analyses
- Duplicates must be analyzed for each analytical method

Comments: The selenium values for water sample MHP503D was done on ICAP and was compared to the furnace AA value for MHP503 which gave an RPD of 200%. The ICAP value for MHP503 of 28.02  $\mu\text{g/l}$ , which should have been used for comparison, gives a new RPD of 27.8%. Since no water samples were analyzed by ICAP no flags are assigned to selenium values.

Duplicate results for arsenic and lead water samples were high when analyzed by ICAP (200% and 37.0%, respectively). No arsenic values were acquired by ICAP analysis but the lead value for sample MHP516 was analyzed by ICAP and is therefore estimated and flagged "J".

VII. Laboratory Control Sample (LCS) Analysis (guideline pg. E-12, Form VII)

1. Was an LCS analyzed for every sample delivery group or batch of samples, whichever was more frequent?

yes X                      no

2. Were recoveries within the 80-120% limit?

yes X                      no

-if the recoveries were outside this range the analysis must be terminated, the problem corrected and the previous samples associated with that LCS redigested and reanalyzed.

3. Were the raw data correctly transcribed onto Form VII?

yes X                      no

Comments: All requirements met.

**VIII. Furnace Atomic Absorption (AA) QC Analysis (guidelines pg. E-14, Form VIII)**

1. Does the raw data package contain absorbance values for two injections per sample, the average values and the relative standard deviation (RSD)?  
yes X                      no
2. For analyte concentrations > the CRDL, did the RSD for the duplicate injections agree within 20%? (if yes, go to question 3)  
yes X                      no

$$RSD = \frac{SD}{M} \times 100$$

SD = Standard Deviation of Duplicate Injections  
M = Mean of Duplicate Injections

- 2a. Were samples that exceeded the 20% criteria reanalyzed?  
yes                      no
- 2b. Did any reanalyzed samples exceed the 20% criteria?  
yes                      no
- 2c. If yes, did the laboratory flag the data of Form I with an 'M'?  
yes                      no
3. Was the recovery of the spike > 40%? (if yes, go to question 4).  
yes                      no X
- If no, was the sample diluted and rerun with another spike?  
yes X                      no
4. Was sample absorbance > 50% of spike absorbance?\* (if yes, go to question 5).  
yes                      no X

\* Spike absorbance = absorbance of spiked sample - absorbance of sample.

- 4a. For spike recoveries between 85 and 115%, were results reported to the IDL?

yes X          no

$$RPD = \frac{(SSR - SR)}{SA} \times 100$$

SSR = Spike Sample Recovery

SR = Sample Result

SA = Spike Added

- 4b. For spike recoveries outside the 85 and 115% range, were results reported to the IDL and flagged with 'W'?

yes X          no

5. Was spike recovery between 85 and 115%? (if no, go to question 6)

- 5a. Were results quantified from calibration curve and reported to IDL?

yes X          no

6. Was an MSA at 50, 100 and 150% of the sample absorbance analyzed?

yes          no X

- 6a. Was each MSA analysis identified in the raw data along with the slope, intercept and correlation coefficient?

yes X          no

- 6b. Were these data correctly transcribed onto Form VIII?

yes          no

- 6c. Were correlation coefficients(r) > 0.995?

yes          no X

- 6d. If no, were MSAs run once more?

yes X          no

- If the correlation coefficients were still > 0.995, data on Form I must be from the run with the best 'r' and the data on Forms I and VII must be flagged with a '+'.  
Were these criteria met?

yes X          no

6e. Were all MSA obtained data marked with an 'S' or an S+ on form I?

yes X          no

Comments: MSA was required but not performed for sample MHP516's thallium value or for sample MHP517's arsenic value. These values are estimated and flagged "J". One correlation coefficient was <0.995 for sample MHP518's arsenic value and is flagged "J", estimated. Both correlation coefficients were <0.995 for sample MHP504's arsenic value and is considered unusable and flagged "R", rejected.

IX. ICP Serial Dilution (L) Analysis (guidelines pg. E-12, Form IX)

1. Was an ICP serial dilution performed on each group of samples of a similar matrix (i.e., soil, water) and concentration (i.e., low, high) or for each sample delivery group, whichever was more frequent?

yes X          no

2. For elements with concentrations >10X the CRDL, did any exceed the serial dilution results by more than 10%? (if no, skip questions 3 and 4)

yes X          no

$$\% \text{ difference} = \frac{I - S}{I} \times 100$$

I = Initial Sample Result

S = Serial Dilution Result (instrument reading X5)

3. Which elements had concentrations that exceeded the 10% criteria? For soils, arsenic and zinc.
4. Did the laboratory flag these data with an 'E' on Form IX?
- yes X          no
5. Were the raw data correctly transcribed onto Form IX?
- yes X          no

Comments: For the soil samples, the arsenic and zinc values are flagged "J", estimated due to slightly high %D's of 12.1 and 13.3%, respectively.

**X. Instrument Detection Limits (IDL) (guidelines pg. E-13, Form XI)**

1. Were IDLs reported for each analyzed element?  
yes X                      no
2. Were IDLs reported for each instrument used?  
yes X                      no
3. Did the IDLs meet the contract requirements? (refer to pg. E-13, SOW 787)  
yes X                      no

Comments: All requirements met.

**XI. Interelement Corrections for ICP (guidelines pg. E-13, Form XII)**

1. Were correction factors reported on Form XII?  
yes X                      no

Comments: All requirements met.

**XII. Linear Range Analysis (LRA) (guidelines pg. E-14, Form XII)**

1. Was a linear range verification standard analyzed?  
yes X                      no
2. Was the results within  $\pm 5\%$  of the true value?  
yes                          no

### Holding Times

Limits: Metals - 6 months; Hg - 30 days; Cn - 28 days.

1. Verified date of sample receipt by laboratory 8-16-89
2. Date of preparation/analyses 8-25-89
3. Were holding times met? yes                      no X

Mercury holding times were not met; therefore, all mercury values are estimated low and flagged "J".

Analyte	Matrix	Date Sampled	Prep Date	Holding Time	Holding Time Limit/Met
Mercury	Low soil	7-18-89	8-25-89	37 days	30 days no
Mercury	Low water	7-18-89	8-25-89	37 days	30 days no
Metals	Low soil	7-18-89	8-25-89	37 days	6 months yes
Metals	Low water	7-18-89	8-25-89	37 days	6 months yes

5-1

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-48-0074~~ <sup>68-48-0074</sup>

MHL955

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>AL</sup>41369

SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 98.5

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	691	*		P
7440-36-0	Antimony	63.1			P
7440-38-2	Arsenic	220			P
7440-39-3	Barium	153	*		P
7440-41-7	Beryllium	0.22	U		P
7440-43-9	Cadmium	21.1			P
7440-70-2	Calcium	37000			P
7440-47-3	Chromium	2.0	B		P
7440-48-4	Cobalt	5.5	B		P
7440-50-8	Copper	149			P
7439-89-6	Iron	44700			P
7439-92-1	Lead	2580			P
7439-95-4	Magnesium	11200			P
7439-96-5	Manganese	1440			P
7439-97-6	Mercury	0.9	N		CV
7440-02-0	Nickel	8.2			P
7440-09-7	Potassium	255	B		P
7782-49-2	Selenium	20.6			F
7440-22-4	Silver	12.6	*		P
7440-23-5	Sodium	22.4	B		P
7440-28-0	Thallium	6.6	NS		F
7440-62-2	Vanadium	1.3	B		P
7440-66-6	Zinc	3230	E		P
	Cyanide				NR

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: YELLOW

Clarity After:

Artifacts:

Comments:



32

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-02-0071~~ <sup>68-W8-0074</sup>

MHL956

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>08</sup> ~~12385~~

SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 98.4

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1040	*		P
7440-36-0	Antimony	84.4			P
7440-38-2	Arsenic	208			P
7440-39-3	Barium	86.9	*		P
7440-41-7	Beryllium	0.22	U		P
7440-43-9	Cadmium	41.2			P
7440-70-2	Calcium	54500			P
7440-47-3	Chromium	6.0			P
7440-48-4	Cobalt	2.6	B		P
7440-50-8	Copper	208			P
7439-89-6	Iron	36500			P
7439-92-1	Lead	3060			P
7439-95-4	Magnesium	18500			P
7439-96-5	Manganese	1740			P
7439-97-6	Mercury	1.4	N	JAS	CV
7440-02-0	Nickel	8.4			P
7440-09-7	Potassium	496	B		P
7782-49-2	Selenium	12.7			P
7440-22-4	Silver	18.3	*		P
7440-23-5	Sodium	34.8	B		P
7440-28-0	Thallium	3.0	NS		P
7440-62-2	Vanadium	3.8	B		P
7440-66-6	Zinc	5710	E		P
	Cyanide				NR

JAS

DC 9-2-89

JAS

JAS

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: YELLOW

Clarity After:

Artifacts:

Comments:

33

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-09-0071~~ <sup>68-W8-0074</sup>

MHP500

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>DC</sup> 41284

SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 99.2

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1530	*		P
7440-36-0	Antimony	87.0			P
7440-38-2	Arsenic	222			P
7440-39-3	Barium	32.8	BI*		P
7440-41-7	Beryllium	0.22	UI		P
7440-43-9	Cadmium	95.9			P
7440-70-2	Calcium	68200			P
7440-47-3	Chromium	8.8			P
7440-48-4	Cobalt	7.4	BI		P
7440-50-8	Copper	336			P
7439-89-6	Iron	53400			P
7439-92-1	Lead	4520			P
7439-95-4	Magnesium	23000			P
7439-96-3	Manganese	2320			P
7439-97-6	Mercury	1.1	IN	JAS	CV
7440-02-0	Nickel	7.1	BI		P
7440-09-7	Potassium	827	BI		P
7782-49-2	Selenium	19.2			F
7440-22-4	Silver	22.1	*		P
7440-23-5	Sodium	42.6	BI		P
7440-29-0	Thallium	4.2	BIN		F
7440-62-2	Vanadium	3.7	BI		P
7440-66-6	Zinc	14100	IE		P
	Cyanide				NR

JAS

DC 41284

JAS

JAS

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: YELLOW

Clarity After:

Artifacts:

Comments:

34

1

## MHP501

Contract: ~~66-05-0071~~

SAS No. : 64387

Lab Sample ID:

Date Received: 08/16/89

Concentration Units (ug/L or mg/kg dry weight): MG/KG

IAS

0-12-89

5-AS

丁卯

Texture: FINE

Artifacts:

Recycled paper

35

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

MHP502

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~48-W8-0074~~ ~~48-W8-0074~~

Lab Code: SILVER

Case No.: 12334

SAS No.: ~~48-W8-0074~~ ~~48-W8-0074~~

SDG No.: MHL955

Matrix (soil/water): SOIL

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 95.0

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-3	Aluminum	340	*		P
7440-36-0	Antimony	144			P
7440-38-2	Arsenic	175			P
7440-39-3	Barium	39.5	BI*		P
7440-41-7	Beryllium	0.23	UI		P
7440-43-3	Cadmium	250			P
7440-70-2	Calcium	32800			P
7440-47-3	Chromium	0.53	UI		P
7440-48-4	Cobalt	3.2	BI		P
7440-50-8	Copper	265			P
7439-89-6	Iron	87000			P
7439-92-1	Lead	31600			P
7439-95-4	Magnesium	142	BI		P
7439-96-5	Manganese	252			P
7439-97-6	Mercury	42.10	BI	IAS	CV
7440-02-0	Nickel	6.2	BI		P
7440-09-7	Potassium	680	BI		P
7782-49-2	Selenium	38.4			F
7440-32-4	Silver	115	*		P
7440-23-5	Sodium	117	BI		P
7440-38-0	Thallium	6.8	BI	N	F
7440-62-2	Vanadium	0.57	UI		P
7440-66-6	Zinc	33800	IE		P
	Cyanide				NR

JAS

DC 4-19

JAS

JAS

Color Before: BROWN

Clarity Before:

Texture: MEDIUM

Color After: YELLOW

Clarity After:

Artifacts:

Comments:

## U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-09-0074~~ <sup>68-08-0074</sup>

MHP503

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>DC</sup> ~~4-13-89~~

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	26.6	BI		P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	3.3	BINW		F
7440-39-3	Barium	51.5	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	2.0	BI		P
7440-70-2	Calcium	147000			P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	6.3	BI		P
7439-89-6	Iron	195			P
7439-92-1	Lead	5.9	BIN*		F
7439-95-4	Magnesium	36400			P
7439-96-5	Manganese	223			P
7439-97-6	Mercury	0.2	UI	TS	CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	2090	BI		P
7782-49-2	Selenium	1.4	UIN*		F
7440-32-4	Silver	1.6	UI		P
7440-33-5	Sodium	25200			P
7440-28-0	Thallium	1.0	UI		F
7440-61-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	419			P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-08-0074~~ <sup>68-W8-0074</sup>

MHP504

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>81</sup>~~413-11~~

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	75.8	BI		P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	5.6	BIN+		F
7440-39-3	Barium	52.5	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	2.2	BI		P
7440-70-2	Calcium	147000			P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	4.0	BI		P
7440-50-8	Copper	5.6	BI		P
7439-89-6	Iron	481			P
7439-92-1	Lead	35.8	INS*		F
7439-95-4	Magnesium	36200			P
7439-96-5	Manganese	240			P
7439-97-6	Mercury	0.2	UI	INS*	F
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	1920	BI		P
7782-49-2	Selenium	14.0	UIN*		F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	24100			P
7440-28-0	Thallium	1.0	UIW		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	519			P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

EPA SAMPLE NO

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-09-0071~~ <sup>68-W8-0074</sup>

MHP506

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>02</sup>~~94384~~

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	24.6	B		P
7440-36-0	Antimony	19.9	U		P
7440-38-2	Arsenic	6.8	B	NW	F
7440-39-3	Barium	54.6	B		P
7440-41-7	Beryllium	1.1	U		P
7440-43-9	Cadmium	1.8	U		P
7440-70-2	Calcium	139000			P
7440-47-3	Chromium	2.8	U		P
7440-48-4	Cobalt	2.6	B		P
7440-50-8	Copper	2.9	B		P
7439-89-6	Iron	338			P
7439-92-1	Lead	6.2		N*	F
7439-95-4	Magnesium	34600			P
7439-96-5	Manganese	274			P
7439-97-6	Mercury	0.2	U	N	P
7440-02-0	Nickel	9.7	U		P
7440-09-7	Potassium	1790	B		P
7782-49-2	Selenium	14.0	U	N*	F
7440-22-4	Silver	1.6	U		P
7440-23-5	Sodium	22900			P
7440-28-0	Thallium	1.0	U	W	F
7440-62-2	Vanadium	2.7	U		P
7440-66-6	Zinc	429			P
	Cyanide				NR

DC  
9-11-89

R 48

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-08-0074~~ ~~68-09-0071~~

MHP507

Lab Code: SILVER

Case No.: 12334

SAS No.: ~~68-08-0074~~ ~~68-09-0071~~

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	370			P
7440-36-0	Antimony	19.9	U		P
7440-39-2	Arsenic	12.2	INS		F
7440-39-3	Barium	59.1	B		P
7440-41-7	Beryllium	1.1	U		P
7440-43-9	Cadmium	1.8	U		P
7440-70-2	Calcium	144000			P
7440-47-3	Chromium	2.8	B		P
7440-48-4	Cobalt	2.6	U		P
7440-50-8	Copper	11.7	B		P
7439-89-6	Iron	1200			P
7439-92-1	Lead	122	IN*		F
7439-95-4	Magnesium	35600			P
7439-96-5	Manganese	335			P
7439-97-6	Mercury	0.2	U	U	P
7440-02-0	Nickel	9.7	U		P
7440-09-7	Potassium	1980	B		P
7782-49-2	Selenium	1.4	U	IN*	F
7440-32-4	Silver	1.6	U		P
7440-33-5	Sodium	23400			P
7440-38-0	Thallium	1.0	U	W	F
7440-62-2	Vanadium	2.7	U		P
7440-66-6	Zinc	726			P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:



## U.S. EPA - CLP

40-  
EPA SAMPLE NO1  
INORGANIC ANALYSIS DATA SHEET

MHP509

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-08-0074~~ *68-08-0074*

Lab Code: SILVER

Case No.: 12334

SAS No.: *AC 91784*

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	11.5	UI		P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	2.3	UINW		F
7440-39-3	Barium	14.9	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.8	UI		P
7440-70-2	Calcium	322000			P
7440-47-3	Chromium	2.9	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	1.9	BI		P
7439-89-6	Iron	270			P
7439-92-1	Lead	0.90	UINW*		F
7439-95-4	Magnesium	68700			P
7439-96-5	Manganese	94.8			P
7439-97-6	Mercury	0.2	UIN		CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	1480	BI		P
7782-49-2	Selenium	14.0	UIN*		F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	47500			P
7440-28-0	Thallium	1.0	UIW		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	190			P
	Cyanide				NR

*OC 9-11-89**RAS*

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

U.S. EPA - CLP

EPA SAMPLE NO.

INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-08-0071~~ <sup>68-08-0074</sup>

MHP510

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>68</sup> ~~68~~ <sup>64</sup>

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	368			P
7440-38-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	9.4	BINW		F
7440-39-3	Barium	37.0	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	2.6	BI		P
7440-70-2	Calcium	333000			P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	3.8	BI		P
7440-50-8	Copper	12.9	BI		P
7439-89-6	Iron	1070			P
7439-92-1	Lead	131	IN*		F
7439-95-4	Magnesium	70500			P
7439-96-5	Manganese	2110			P
7439-97-6	Mercury	0.2	UI	IN JAS	PV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	1710	BI		P
7782-49-2	Selenium	1.4	UIN*		F
7440-22-4	Silver	2.4	BI		P
7440-23-5	Sodium	48400			P
7440-28-0	Thallium	1.0	UIW		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	656			P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-09-0074~~ <sup>68-W8-0074</sup>

MHP511

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>PC</sup><sub>9-11-89</sub>

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	16.3	B		P
7440-36-0	Antimony	19.9	U		P
7440-38-2	Arsenic	5.3	B/NW		F
7440-39-3	Barium	32.1	B		P
7440-41-7	Beryllium	1.1	U		P
7440-43-9	Cadmium	1.8	U		P
7440-70-2	Calcium	320000			P
7440-47-3	Chromium	2.8	U		P
7440-48-4	Cobalt	2.6	U		P
7440-50-8	Copper	1.1	U		P
7439-89-6	Iron	224			P
7439-92-1	Lead	0.90	U/N*		F
7439-95-4	Magnesium	68600			P
7439-95-5	Manganese	960			P
7439-97-6	Mercury	0.2	U/N	CV	P
7440-02-0	Nickel	9.7	U		P
7440-09-7	Potassium	1330	B		P
7782-49-2	Selenium	14.0	U/N*		F
7440-22-4	Silver	1.6	U		P
7440-23-5	Sodium	46700			P
7440-28-0	Thallium	1.0	U/W		F
7440-62-2	Vanadium	2.7	U		P
7440-66-6	Zinc	295			P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

43

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-09-0071~~ <sup>68-W8-0074</sup>

MHP512

Lab Code: SILVER

Case No.: 12334

SAS No.:

DC 6/11/89

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	U	Q	M
7429-90-5	Aluminum	106	BI		P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	8.4	BI/N		F
7440-39-3	Barium	33.5	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.8	UI		P
7440-70-2	Calcium	303000			P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	4.9	BI		P
7439-89-6	Iron	1090			P
7439-92-1	Lead	36.6	INS*		F
7439-95-4	Magnesium	64900			P
7439-96-5	Manganese	950			P
7439-97-6	Mercury	0.2	UI/N	J	CV
7440-02-0	Nickel	3.7	UI		P
7440-09-7	Potassium	986	BI		P
7782-49-2	Selenium	14.0	UI/N*		F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	44300			P
7440-23-0	Thallium	1.0	UI/W		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	332			P
	Cyanide				NR

DC 6/11/89

RAS

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

U.S. EPA - CLP

44  
EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-89-0071~~ <sup>68-08-0074</sup>

MHP513

Lab Code: SILVER

Case No.: 12334

SAS No.: <sup>94359</sup>

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	23.3	BI		P
7440-38-0	Antimony	19.3	UI		P
7440-38-2	Arsenic	2.3	UIN		F
7440-39-3	Barium	1.3	UI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.8	UI		P
7440-70-2	Calcium	154	BI		P
7440-47-3	Chromium	3.5	BI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	1.1	UI		P
7439-89-6	Iron	277			P
7439-92-1	Lead	0.90	UIN*		F
7439-95-4	Magnesium	42.5	BI		P
7439-96-5	Manganese	2.3	BI		P
7439-97-6	Mercury	0.2	UIN	JAS	CV
7440-02-0	Nickel	3.7	UI		P
7440-09-7	Potassium	273	UI		P
7782-49-2	Selenium	1.4	UIN*		F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	68.9	BI		P
7440-28-0	Thallium	1.0	UIW		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	4.5	BI		P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-WF-0074~~ ~~68-03-0071~~

MHP514

Lab Code: SILVER

Case No.: 12334

SAS No.: ~~95-18~~

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	16.6	BI		P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	12.0	INS		F
7440-39-3	Barium	1.3	UI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	1.8	UI		P
7440-70-2	Calcium	56.3	BI		P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	4.4	BI		P
7439-89-6	Iron	219			P
7439-92-1	Lead	0.90	UINW*		F
7439-95-4	Magnesium	20.9	UI		P
7439-96-5	Manganese	2.0	BI		P
7439-97-6	Mercury	0.2	UINW*		CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	273	UI		P
7782-49-2	Selenium	1.4	UIN*		F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	76.0	BI		P
7440-28-0	Thallium	1.0	UINW		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	1.3	UI		P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

MHP515

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-03-1071~~ *68-080074*

Lab Code: SILVER

Case No.: 12334

SAS No.: *68-03-1071*

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	32.8	BI		P
7440-35-0	Antimony	39.3	BI		P
7440-38-2	Arsenic	68.6	IN		F
7440-39-3	Barium	102	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	4.6	BI		P
7440-70-2	Calcium	180000			P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	8.8	BI		P
7440-50-8	Copper	13.6	BI		P
7439-89-6	Iron	267			P
7439-92-1	Lead	41.8	IN*		F
7439-95-4	Magnesium	38000			P
7439-96-5	Manganese	2780			P
7439-97-6	Mercury	0.2	UI		P
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	5580			P
7782-49-2	Selenium	14.0	UI		F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	54600			P
7440-28-0	Thallium	14.1			F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	2650			P
	Cyanide				NR

*DC 9-11-89*

*R 48*

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: 68-WB-0074

MHP516

Lab Code: SILVER

Case No.: 12334

SAS No.: AC 4-7-84

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	<del>30900</del>			P
7440-38-0	Antimony	<del>337</del>			P
7440-38-2	Arsenic	<del>340</del>			AF
7440-39-3	Barium	2330			P
7440-41-7	Beryllium	1.7	BI		P
7440-43-9	Cadmium	289			P
7440-70-2	Calcium	446000			P
7440-47-3	Chromium	50.2			P
7440-48-4	Cobalt	48.7	BI		P
7440-50-8	Copper	1540			P
7439-89-6	Iron	107000			P
7439-92-1	Lead	22100			P
7439-95-4	Magnesium	104000			P
7439-96-5	Manganese	21100			P
7439-97-6	Mercury	<del>16.0</del>	N	JAS	CV
7440-02-0	Nickel	65.5			P
7440-09-7	Potassium	15600			P
7782-49-2	Selenium	<del>1.2</del>	UI	W	AF
7440-22-4	Silver	201			P
7440-23-5	Sodium	58500			P
7440-28-0	Thallium	83.4			F
7440-62-2	Vanadium	58.7			P
7440-66-6	Zinc	49100			P
	Cyanide				NR

lab didn't  
multiply by  
dilution factor  
SOX

JAS

DC 9-12-89

AC 9-12-89 RAS

JAS

Color Before: BROWN

Clarity Before: CLOUDY

Texture:

Color After: BROWN

Clarity After: CLOUDY

Artifacts:

Comments:



U.S. EPA - CLP

EPA SAMPLE NO.

1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-03-0074~~ *68-08-0074*

MHP517

Lab Code: SILVER

Case No.: 12334

SAS No.: *bc 7476*

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	32.6	BI		P
7440-36-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	10.7	IN		F
7440-39-3	Barium	37.0	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	3.3	BI		P
7440-70-2	Calcium	308000			P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	12.4	BI		P
7439-89-6	Iron	416			P
7439-92-1	Lead	12.9	IN*		F
7439-95-4	Magnesium	61600			P
7439-96-5	Manganese	1310			P
7439-97-6	Mercury	0.2	UI	IN	P
7440-02-0	Nickel	25.8	BI		P
7440-09-2	Potassium	273	UI		P
7782-49-2	Selenium	14.0	UI	IN*	F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	28800			P
7440-28-0	Thallium	1.0	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	2990			P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

49  
EPA SAMPLE NO.1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: ~~68-WJ-0074~~ ~~68-69-0074~~

MHP519

Lab Code: SILVER

Case No.: 12334

SAS No.: ~~NC~~ ~~67-73-84~~

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	33.7	BI		P
7440-38-0	Antimony	19.9	UI		P
7440-38-2	Arsenic	17.4	INS		F
7440-39-3	Barium	35.9	BI		P
7440-41-7	Beryllium	1.1	UI		P
7440-43-9	Cadmium	6.2			P
7440-70-2	Calcium	314000			P
7440-47-3	Chromium	2.8	UI		P
7440-48-4	Cobalt	2.6	UI		P
7440-50-8	Copper	5.6	BI		P
7439-89-6	Iron	696			P
7439-92-1	Lead	24.9	IN*		F
7439-95-4	Magnesium	62700			P
7439-96-5	Manganese	1340			P
7439-97-5	Mercury	0.270	UIN		CV
7440-02-0	Nickel	9.7	UI		P
7440-09-7	Potassium	273	UI		P
7782-49-2	Selenium	14.0	UIN*		F
7440-22-4	Silver	1.6	UI		P
7440-23-5	Sodium	29300			P
7440-28-0	Thallium	1.0	UI		F
7440-62-2	Vanadium	2.7	UI		P
7440-66-6	Zinc	3060			P
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

## U.S. EPA - CLP

50  
EPA SAMPLE NO.1  
INORGANIC ANALYSIS DATA SHEET

Lab Name: SILVER VALLEY LABS., INC.

Contract: 68-08-0074

MHPS19

Lab Code: SILVER

Case No.: 12334

SAS No.: 6C 417/84

SDG No.: MHL955

Matrix (soil/water): WATER

Lab Sample ID:

Level (low/med): LOW

Date Received: 08/16/89

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	D	M
7429-90-5	Aluminum	17.6	BI		IP
7440-38-0	Antimony	19.9	UI		IP
7440-38-2	Arsenic	2.2	UINW		IF
7440-39-3	Barium	14.9	BI		IP
7440-41-7	Beryllium	1.1	UI		IP
7440-43-9	Cadmium	1.8	UI		IP
7440-70-2	Calcium	316000			IP
7440-47-3	Chromium	2.8	UI		IP
7440-48-4	Cobalt	2.6	UI		IP
7440-50-8	Copper	10.4	BI		IP
7439-89-6	Iron	426			IP
7439-92-1	Lead	1.8	UIN*		IF
7439-95-4	Magnesium	68200			IP
7439-96-5	Manganese	3190			IP
7439-97-6	Mercury	0.2	UIN		IP
7440-02-0	Nickel	13.2	BI		IP
7440-09-7	Potassium	2010	BI		IP
7782-49-2	Selenium	14.0	UIN*		IF
7440-22-4	Silver	1.6	UI		IP
7440-22-5	Sodium	45000			IP
7440-28-0	Thallium	1.0	UI		IF
7440-62-2	Vanadium	2.7	UI		IP
7440-66-6	Zinc	219			IP
	Cyanide				NR

Color Before: COLORLESS

Clarity Before: CLEAR

Texture:

Color After: COLORLESS

Clarity After: CLEAR

Artifacts:

Comments:

APPENDIX D  
RECORDS OF COMMUNICATION

**RECORD OF  
COMMUNICATION**☐ PHONE CALL    ☐ DISCUSSION    ☒ FIELD TRIP    ☐ CONFERENCE  
☐ OTHER (SPECIFY)


(Record of item checked above)

**TO:** Standley Pace**FROM:** Kevin Mackey, E & E FIT  
*K. Mackey***DATE**  
November 27, 1989**TIME**  
10:30 A.M.**SUBJECT** Amount of land irrigated by the G.M. Pace diversion ditch downgradient of the Richardson Flat tailings dam.**SUMMARY OF COMMUNICATION**

Mr. Pace informed me that both he and his cousin (Angus Pace) use water from the G.M. Pace diversion ditch. According to Mr. Pace, both he and his cousin own 47% of the diverted water and use it to irrigate approximately 115 acres each (total of 230 acres).

In addition, Mr. Pace informed me that the Gilmore family owns 53% of the water from the G.M. Pace ditch but he does not know how much land they irrigated with water diverted from the G.M. Pace ditch.

**CONCLUSIONS, ACTION TAKEN OR REQUIRED****INFORMATION COPIES****TO:**

<b>RECORD OF COMMUNICATION</b>	<input checked="" type="checkbox"/> <b>PHONE CALL</b> <input type="checkbox"/> <b>DISCUSSION</b> <input type="checkbox"/> <b>FIELD TRIP</b> <input type="checkbox"/> <b>CONFERENCE</b> <input type="checkbox"/> <b>OTHER (SPECIFY)</b> (801) 466-6094	
(Record of item checked above)		
<b>TO:</b> James Gilmore Rancher	<b>FROM:</b> Susan Kennedy, E & E FIT 	<b>DATE</b> 12/11/89  <b>TIME</b> 9:00 P.M.
<b>SUBJECT</b> Number of acres and use of land irrigated from G.M. Pace Ditch		
<b>SUMMARY OF COMMUNICATION</b>  When asked the number of acres irrigated by the G.M. Pace Ditch and the nature of use of the land, Mr. Gilmore provided the following information:  - Approximately 100 (between 95 to 110) acres of his land are irrigated by water from the G.M. Pace Ditch.  - The irrigated land is used to grow alfalfa, and to graze sheep.		
<b>CONCLUSIONS, ACTION TAKEN OR REQUIRED</b>  Use 100 acres of irrigated land to determine the population served by surface water -- Richardson Flat Tailings HRS package.		
<b>INFORMATION COPIES</b> <b>TO:</b>		



## ecology and environment, inc.

1776 SOUTH JACKSON STREET, DENVER, COLORADO 80210, TEL. 303-757-4984

International Specialists in the Environment

TO : Janet Liner, FIT-RPO  
FROM : Susan Kennedy, E & E FIT  
DATE : December 20, 1989  
SUBJECT: Transmittal of Supplemental Site Inspection Report for  
Richardson Flat Tailings, Summit County, Utah,  
TDD F08-8903-06, PAN FUT0039HDA.

Attached is a copy of the Supplemental Site Inspection Report for Richardson Flat Tailings (TDD F08-8903-06). This report is a revised edition of the draft report entitled Sampling Activities Report and Analytical Results Report for Richardson Flat Tailings, submitted to you by Kevin Mackey on October 13, 1989.

If you have any questions, please contact Kevin Mackey or me at 757-4984.

cc: Thomas Burns (2 copies)



## ecology and environment, inc.

1776 SOUTH JACKSON STREET, DENVER, COLORADO 80210, TEL. 303-757-4984

International Specialists in the Environment

To: T. Burns

From: S. Kennedy, FIT

Date: December 20, 1989

Re: Supplemental Site Inspection Report, Richardson Flats  
TDD #F08-8903-06.

Attached is the revised Richardson Flats report. In our view, it is still a **draft document** until you have reviewed and concur with its language. If you have any questions, please contact me.